



# EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT

Purchasing Department

411 North 8<sup>th</sup> Street

Edinburg, Texas 78541

PHONE: (956) 289-2311 FAX: (956) 383-7687

*Dr. René Gutiérrez, Superintendent*

*Dr. Rebecca Morrison, Asst. Supt. for Finance & Operations*



*Innovate through Technology*



## ADDENDUM 1

**BID 19-98, Lincoln Elementary Installation of HVAC Building Automatic Controls**

**March 8, 2019**

### I. INSTRUCTIONS:

1. This addendum to Request for Proposals is issued after the receipt of bids. All changes covered in this addendum shall be included in your bid, and the addendum will be considered as one of the contract documents.
2. Proposers shall acknowledge receipt of this ADDENDUM as a signed attachment included with your bid if you haven't sent the bid.

### II. PLEASE CHANGE:

**PLEASE SEE ATTACHED ADDENDUM.**

Respectfully Submitted,

Amaro Tijerina  
Purchasing Director

\_\_\_\_\_  
(Signature of authorized officer)      Date

\_\_\_\_\_  
Company Name

**CSP 19-98**

**ADDENDUM No. 1 LINCOLN ELEMENTARY INSTALLATION OF HVAC BUILDING AUTOMATED CONTROLS**

**EDINBURG CONSOLIDATED INDEPENDENT SCHOOL DISTRICT**

**DATE:** March 8, 2019

**BID DATE:** March 19, 2019

---

**NOTICE:**

- A. *The following changes, omissions or alterations to the specification and drawings shall be made insofar as the specifications and drawings are inconsistent with following, this addendum shall govern.*
  - B. *Acknowledge receipt of this addendum by inserting its number and date of issue in the place provided for same in the proposal. This addendum forms a part of the Contract Documents.*
  - C. *It is imperative that this addendum be inserted INTO set of specifications.*
- 

**Item No. 1 To add humidity sensors and controls:**

- A. Contractor to add humidity sensors to monitor following spaces: Library and Front Office Space
- B. Library, cafeteria and Front Office AC units should include a second humidity and CO2 sensors at the discharge or return. Additionally, a specific sequence of operation will be necessary to control ac units and properly de-humidify and keep appropriate indoor air quality.

**Item No. 2 To replace thermostat plates in some specific areas:**

- A. Replace thermostat plates to thermostat devices where local personnel can read temperature and humidity values among other standard values.

**Item No. 3 Points to control and monitor:**

- A. Any two stage AC units such as Library, Front Office, Gymnasium and cafeteria must include 1 and 2 stage compressors monitoring status and controls.

**Item No. 4 Alternate 1 pricing:**

- A. Contractor to include pricing for additional humidity sensors to monitor 45 areas or AC discharges.

**Item No. 5 Wireless controls and hard wired options:**

- A. ECISD prefers wireless controllers, however, bidding with hard wired controls will be accepted. Conduit must be consider and specified for this option.