





ECISD HIGH SCHOOL ATHLETIC MULTI-USE BUILDING

411 N 8TH AVE, EDINBURG, TX 78541

ECISD CSP 25-74




VICINITY MAP:



GENERAL INFO:

EDINBURG HIGH SCHOOL:
2600 E WISCONSIN RD, EDINBURG TX.



INDEX OF DRAWINGS1	
Sheet Number	Sheet Name
GENERAL	
G0.0	COVER PAGE
G1.0	ADA INFORMATION
G1.1	ADA INFORMATION
G1.2	ADA INFORMATION
STRUCTURAL	
S1.0	GENERAL NOTES
S1.1	GENERAL NOTES
S1.2	GENERAL NOTES
S2.0	FOUNDATION PLAN
S3.0	ROOF FRAMING PLAN
S3.1	ALTERNATE ROOF FRAMING PLAN
SD1.0	DETAILS
SD2.0	DETAILS

INDEX OF DRAWINGS1	
Sheet Number	Sheet Name
ARCHITECTURAL	
A2.0	FLOOR PLAN BASE BID
A2.0A	FLOOR PLAN ALTERNATE
A2.1	ROOF PLAN BASE BID
A2.1A	ROOF PLAN ALTERNATE
A2.3	REFLECTED CEILING PLAN BASE BID
A2.3A	REFLECTED CEILING PLAN ALTERNATE
A3.0	EXTERIOR ELEVATIONS BASE BID
A3.0A	EXTERIOR ELEVATIONS ALTERNATE
A4.0	BUILDING SECTIONS BASE BID
A4.0A	BUILDING SECTIONS ALTERNATE
A4.1	WALL SECTIONS AND DETAILS BASE BID
A7.0	DOOR SCHEDULE

INDEX OF DRAWINGS1	
Sheet Number	Sheet Name
MEP	
E0.0	ELECTRICAL NOTES
E1.0	ELECTRICAL SITE
E1.1	ELECTRICAL POWER
E1.2	ELECTRICAL LIGHTING
E2.0	ELECTRICAL ONE-LINE DIAGRAM
E3.0	ELECTRICAL SCHEDULES
E4.0	ELECTRICAL DETAILS
E5.0	ELECTRICAL SPECIFICATIONS
E5.1	ELECTRICAL SPECIFICATIONS
M0.0	MECHANICAL LEGEND
M1.0	MECHANICAL SITE
M1.1	MECHANICAL FLOOR PLAN
M2.0	MECHANICAL SCHEDULES
M3.0	MECHANICAL DETAILS
M4.0	MECHANICAL SPECS

PROJECT INFORMATION

ADDRESS:	411 N 8th Ave, Edinburg, TX 78541
ARCHITECT OF RECORD:	JOSE CARLOS GARCIA III, RA, AIA TBAE: # 22658 TBAE FIRM: BR 4247 CG5 ARCHITECT LLC 1314 E 22ND ST. MISSION, TX, 78572
OWNER:	EDINBURG CISD
PROJECT DESCRIPTION:	MULTIPURPOSE BUILDINGS

CIVIL



2105 S. JACKSON RD.
EDINBURG, TX 78539
(956) 281-1818

STRUCTURAL



701 S 15TH ST.
MCALLEN, TX 78501
(956) 687-5560
www.clhengineeringinc.com

M.E.P.



1706 MILLER AVE.
DONNA, TX 78537
956.472.5161
www.vme-engineering.com



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:



ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:

EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

COVER PAGE

G0.0



TEXAS ARCHITECT
FIRM NO: BR4247
WWW.CGSGARCHITECT.COM

SEAL:



5/16/2025

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:
No. Description Date
PROJECT #: 25-03102
DRAWN BY: NM
CHECKED BY: CG3
DATE: 4/28/25

ADA
INFORMATION

G1.1

703.6.2 Finish and Contrast. Pictograms and their field shall have a non-glass finish. Pictograms shall contrast with their field with either a light pictogram on a dark field or a dark pictogram on a light field.
Advisory 703.6.2 Finish and Contrast. Signs are more legible for persons with low vision when characters contrast as much as possible with their background. Additional factors affecting the ease with which the text can be distinguished from its background include shadows cast by lighting sources, surface glare, and the uniformity of the text and background colors and textures.

703.6.3 Text Descriptors. Pictograms shall have text descriptors located directly below the pictogram field. Text descriptors shall comply with 703.3.7.3.3 and 703.4.

703.7 Symbols of Accessibility. Symbols of accessibility shall comply with 703.7.1.

703.7.1 Finish and Contrast. Symbols of accessibility and their background shall have a non-glass finish. Symbols of accessibility shall contrast with their background with either a light symbol on a dark background or a dark symbol on a light background.

Advisory 703.7.1 Finish and Contrast. Signs are more legible for persons with low vision when characters contrast as much as possible with their background. Additional factors affecting the ease with which the text can be distinguished from its background include shadows cast by lighting sources, surface glare, and the uniformity of the text and background colors and textures.

703.7.2 Symbols.

703.7.2.1 International Symbol of Accessibility. The International Symbol of Accessibility shall comply with Figure 703.7.2.1.



Figure 703.7.2.1 International Symbol of Accessibility

703.7.2.2 International Symbol of TTY. The International Symbol of TTY shall comply with Figure 703.7.2.2.



Figure 703.7.2.2 International Symbol of TTY

703.7.2.3 Volume Control Telephones. Telephones with a volume control shall be identified by a pictogram of a telephone handset with radiating sound waves on a square field such as shown in Figure 703.7.2.3.



Figure 703.7.2.3 Volume Control Telephone

703.7.2.4 Assistive Listening Systems. Assistive listening systems shall be identified by the International Symbol of Access for Hearing Loss complying with Figure 703.7.2.4.



Figure 703.7.2.4 International Symbol of Access for Hearing Loss

705 Detectable Warnings.

705.1 General. Detectable warnings shall consist of a surface of truncated domes and shall comply with 705.

705.1.1 Dome Size. Truncated domes in a detectable warning surface shall have a base diameter of 0.8 inch (22 mm) minimum and 1.4 inches (36 mm) maximum, a top diameter of 50 percent of the base diameter minimum to 65 percent of the base diameter maximum, and a height of 0.2 inch (5 mm).

705.1.2 Dome Spacing. Truncated domes in a detectable warning surface shall have a center-to-center spacing of 48 inches (1219 mm) minimum and 60 inches (1525 mm) maximum, and a base-to-base spacing of 0.65 inch (17 mm) minimum, measured between the most adjacent domes on a square grid.

705.1.3 Contrast. Detectable warning surfaces shall contrast visually with adjacent walking surfaces either light-on-dark, or dark-on-light.

705.2 Platform Edges. Detectable warning surfaces at platform boarding edges shall be 24 inches (610 mm) wide and shall extend the full length of the public use area of the platform.

603.6 Height. Lavatories and sinks shall be installed with the front of the higher of the rim or counter surface 34 inches (865 mm) maximum above the finish floor or ground.

EXCEPTIONS:

1. A lavatory in a toilet or bathing facility for a single occupant accessed only through a private office and not for common use or public use shall not be required to comply with 603.6.2.

2. In residential dwelling units, the height of the water closet shall be permitted to be 4 inches (100 mm) maximum from the side wall or partition farthest from the water closet. Where located in the side wall or partition, the door opening shall be 4 inches (100 mm) maximum from the side wall or partition farthest from the water closet. Where located in the side wall or partition, the door opening shall be 4 inches (100 mm) maximum from the front partition. The door shall be self-closing. A door pull complying with 604.2.3.2 shall be placed on both sides of the door near the latch. Toilet compartment doors shall not swing into the minimum required compartment area.

604.4 Faucets. Controls for faucets shall comply with 309. Hand-operated metering faucets shall remain open for 10 seconds minimum.

605.5 Exposed Pipes and Surfaces. Water supply and drain pipes under lavatories and sinks shall be insulated or otherwise configured to prevent contact. There shall be no sharp or abrasive surfaces under lavatories and sinks.

703 Signs.

703.1 General. Signs shall comply with 703.3. Where both visual and tactile characters are required, one sign with both visual and tactile characters, or two separate signs, one with visual, and one with tactile characters, shall be provided.

703.2 Raised Characters. Raised characters shall comply with 703.3 and shall be duplicated in braille complying with 703.3. Raised characters shall be installed in accordance with 703.4.

Advisory 703.2 Raised Characters. Signs that are designed to be read by touch should not have sharp or abrasive edges.

703.2.1 Depth. Raised characters shall be 1/32 inch (0.8 mm) minimum above their background.

703.2.2 Case. Characters shall be uppercase. Characters shall be 1/16 inch (1.6 mm) minimum and 4 times the raised character stroke width maximum at the base of the cross sections, and 1/8 inch (3.2 mm) minimum and 4 times the raised character stroke width maximum at the top of the cross sections. Characters shall be separated from raised borders and decorative elements 3/8 inch (9.5 mm) minimum.

703.2.3 Character Proportions. Characters shall be selected from fonts where the width of the uppercase letter "O" is 55 percent minimum and 110 percent maximum of the height of the uppercase letter "I".

703.2.5 Character Height. Character height measured vertically from the baseline of the character shall be 5/8 inch (15 mm) minimum and 2 inches (51 mm) maximum based on the height of the uppercase letter "I".

EXCEPTION: Where separate raised and visual characters with the same information are provided, raised character height shall be permitted to be 1/2 inch (13 mm) minimum.

703.2.6 Stroke Thickness. Stroke thickness of the uppercase letter "I" shall be 15 percent maximum of the height of the character.

703.2.7 Character Spacing. Character spacing shall be measured between the two closest points of adjacent raised characters within a message, excluding word spaces. Where characters have rectangular cross sections, spacing between individual raised characters shall be 1/8 inch (3.2 mm) minimum and 4 times the raised character stroke width maximum. Where characters have other cross sections, spacing between individual raised characters shall be 1/16 inch (1.6 mm) minimum and 4 times the raised character stroke width maximum at the base of the cross sections, and 1/8 inch (3.2 mm) minimum and 4 times the raised character stroke width maximum at the top of the cross sections. Characters shall be separated from raised borders and decorative elements 3/8 inch (9.5 mm) minimum.

703.2.8 Line Spacing. Spacing between the baselines of separate lines of raised characters within a message shall be 135 percent minimum and 170 percent maximum of the raised character height.

703.3 Braille. Braille shall be contracted Grade 2 and shall comply with 703.3 and 703.4.

703.3.1 Dimensions and Capitalization. Braille dots shall have a domed or rounded shape and shall comply with Table 703.3.1. The indicator for uppercase letters shall only be used before the first word of sentences, proper nouns and names, individual letters of the alphabet, initials, and acronyms.

Table 703.3.1 Braille Dimensions

Measurement Range	Minimum to Maximum Dimension
Dot Size Range	0.009 to 0.014 inch (0.23 to 0.36 mm)
Dot Spacing Range	0.009 to 0.014 inch (0.23 to 0.36 mm)
Dot Size Range	0.009 to 0.014 inch (0.23 to 0.36 mm)
Dot Spacing Range	0.009 to 0.014 inch (0.23 to 0.36 mm)
Dot Size Range	0.009 to 0.014 inch (0.23 to 0.36 mm)
Dot Spacing Range	0.009 to 0.014 inch (0.23 to 0.36 mm)

1. Measured center to center.

703.3.2 Position of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.3 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.4 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.5 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.6 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.7 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.8 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.9 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.10 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.11 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.12 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.13 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.14 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.15 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.16 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.17 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.18 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.19 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.20 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.21 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.22 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.23 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.24 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.25 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.26 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.27 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.28 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.29 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.30 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

703.3.31 Location of Braille. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other tactile characters and 3/8 inch (9.5 mm) minimum from raised borders and decorative elements.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised characters or symbols.

EXCEPTIONS:

1. Doors to a toilet room or bathing room for a single occupant accessed only through a private office and not for common use or public use shall be permitted to swing into the clear floor space or clearance provided the swing of the door can be reversed to comply with 703.2.3.

2. In residential dwelling units, the height of the water closet shall be permitted to be 4 inches (100 mm) maximum from the side wall or partition farthest from the water closet. Where located in the side wall or partition, the door opening shall be 4 inches (100 mm) maximum from the side wall or partition farthest from the water closet. Where located in the side wall or partition, the door opening shall be 4 inches (100 mm) maximum from the front partition. The door shall be self-closing. A door pull complying with 604.2.3.2 shall be placed on both sides of the door near the latch. Toilet compartment doors shall not swing into the minimum required compartment area.

603.3 Mirrors. Mirrors located above lavatories or restrooms shall be installed with the bottom edge of the reflecting surface 40 inches (1015 mm) maximum above the finish floor or ground. Mirrors not located above lavatories or restrooms shall be installed with the bottom edge of the reflecting surface 35 inches (890 mm) maximum above the finish floor or ground.

Advisory 603.3 Mirrors. A mirror's full-length mirror can accommodate a greater number of people, including children. In order for mirrors to be usable by people with disabilities and people who are shorter, the top edge of the mirror should be 74 inches (1880 mm) minimum from the floor or ground.

603.4 Coat Hooks and Shelves. Coat hooks shall be located within one of the reach ranges specified in 308. Shelves shall be located 40 inches (1015 mm) minimum and 48 inches (1220 mm) maximum above the finish floor.

604.1 General. Water closets and toilet compartments shall comply with 604.2 through 604.8.

EXCEPTION: Water closets and toilet compartments for children's use shall be permitted to comply with 604.2.

604.2 Location. The water closet shall be positioned with a wall or partition to the rear and to one side. The centerline of the water closet shall be 16 inches (405 mm) minimum to 18 inches (455 mm) maximum from the side wall or partition, except that the water closet shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum from the side wall or partition in the ambulatory accessible toilet compartment specified in 604.8.2. Water closets shall be arranged for a left-hand or right-hand approach.

604.3 Clearances. Clearances around water closets and in toilet compartments shall comply with 604.3.

604.3.1 Size. Clearance around a water closet shall be 60 inches (1525 mm) minimum measured perpendicular from the side wall and 56 inches (1420 mm) minimum measured perpendicular from the rear wall.

604.3.2 Overlap. The required clearance around a water closet shall be permitted to overlap the water closet, associated grab bars, dispenser, sanitary napkin dispenser, coat hooks, shelves, accessible routes, clear floor space and clearances required at other fixtures, and the turning space. No other fixtures or obstructions shall be located within the required water closet clearance.

EXCEPTION: In residential dwelling units, a lavatory complying with 606 shall be permitted on the rear wall 18 inches (455 mm) minimum from the water closet centerline where the clearance at the water closet is 60 inches (1525 mm) minimum measured perpendicular from the rear wall.

Advisory 604.3.2 Overlap. When the door to the toilet room is placed directly in front of the water closet, the water closet cannot overlap the required minimum clearance for the door inside the room.

604.3.3 Grab Bars. Grab bars shall comply with 609. A side-wall grab bar complying with 604.8.2 shall be provided on both sides of the compartment.

604.3.4 Side Wall. The side wall grab bar shall be 42 inches (1065 mm) long minimum, centered on the side wall, and extending 54 inches (1370 mm) minimum from the rear wall.

604.3.5 Rear Wall. The rear wall grab bar shall be 36 inches (915 mm) long minimum, centered on the rear wall, and extending 54 inches (1370 mm) minimum from the rear wall.

604.3.6 Transfer Side. The transfer side grab bar shall be 36 inches (915 mm) long minimum, centered on the transfer side, and extending 54 inches (1370 mm) minimum from the rear wall.

604.3.7 Dispenser. Toilet paper dispensers shall comply with 309.4 and shall be 7 inches (178 mm) minimum and 9 inches (230 mm) maximum in front of the water closet measured to the centerline of the dispenser. The outlet of the dispenser shall be 15 inches (380 mm) minimum and 48 inches (1220 mm) maximum above the finish floor and shall not be located behind grab bars. Dispensers shall not be of a type that controls delivery or that does not allow continuous paper flow.

Advisory 604.3.7 Dispenser. If toilet paper dispensers are installed above the side wall grab bar, the outlet of the toilet paper dispenser must be 48 inches (1220 mm) maximum above the finish floor and the top of the gripping surface of the grab



5/16/2025




2600 E
Wisconsin Rd,
Edinburg, TX
78542

EDINBURG CISD

No.	Description	Date

ADA INFORMATION

G1.2





TEXAS ARCHITECT
FIRM No: BR4247
WWW.CGSARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #:
DRAWN BY:
CHECKED BY:
DATE: 4/28/25

GENERAL
NOTES

S1.1

REINFORCED CONCRETE:

- GENERAL
 - VERIFY ALL DIMENSIONS, COORDINATE WITH ARCHITECTURAL PLANS PRIOR TO CONSTRUCTION AND NOTIFY THE ARCHITECT AND ENGINEER OF ANY DISCREPANCIES PRIOR TO BIDDING, AND/OR CONSTRUCTION.
 - ACI 308 WORK SHALL BE IN ACCORDANCE WITH THE AMERICAN CONCRETE INSTITUTE (ACI) SPECIFICATIONS, ACI 301, ACI 308, AND ACI 117 LATEST EDITIONS. FOOTINGS, BEAMS, WALLS, AND DRILLED PIERS SHALL COMPLY WITH ACI 308, LATEST EDITION.
 - ALL DETAILING, FABRICATION AND ERECTION OF REINFORCING BARS, AND ALL ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI 315 "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE," LATEST EDITION.
 - CLASSES OF CONCRETE
 - REFERENCE 19G1.2 FOR THE MINIMUM 28-DAY COMPRESSIVE STRENGTH (f_c) FOR ALL CLASSES OF CONCRETE.
 - CONCRETE MIX
 - THE GENERAL CONTRACTOR IS RESPONSIBLE FOR THE CONCRETE MIX FOR EACH CLASS OF CONCRETE TO ACHIEVE THE 28-DAY COMPRESSIVE STRENGTH. PREPARE DESIGN MIXES SIGNED AND SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE THE PROJECT IS IN FOR EACH CLASS OF CONCRETE. PROPORTIONED ACCORDING TO ACI 301, FOR BOTH NORMALWEIGHT AND LIGHTWEIGHT CONCRETE DETERMINED BY EITHER LABORATORY TRIAL MIX OR FIELD TEST DATA.
 - FIELD EXPERIENCE OR TRIAL MIXTURES ARE ACCEPTABLE PROVIDED ALL CRITERIA ARE MET:
 - THE CONTRACTOR PROVIDES PROPER DOCUMENTATION OF THE STRENGTH TEST RECORDS NOT MORE THAN 24 MONTHS OLD AND SHALL CLEARLY INDICATE MATERIALS, QUALITY CONTROL PROCEDURES, AND CONDITIONS SIMILAR TO THOSE EXPECTED FOR THE PROJECT. THE CONCRETE MATERIALS INCLUDED IN THE MIX DESIGN SHALL BE THE SAME MATERIALS PROVIDED FOR THE PROJECT, AND SHALL BE PREPARED BY AN INDEPENDENT TESTING LABORATORY APPROVED BY THE OWNER.
 - A MINIMUM OF 30 CONSECUTIVE TESTS OR TWO GROUPS OF CONSECUTIVE TESTS TOTALING TO 30 TESTS.
 - ALL CONSECUTIVE TESTS ARE WITHIN 1000 PSI OF f_c .
 - THE CONTRACTOR SHALL SUBMIT A CALCULATION OF THE SAMPLE STANDARD DEVIATION AND THE REQUIRED AVERAGE COMPRESSIVE STRENGTH, f_{cd} , IN ACCORDANCE TO ACI 318 (EDITION LISTED ON DESIGN CRITERIA) SECTION 8.5.1 AND TABLE 5.3.2.1, RESPECTIVELY.
 - SUMP: REFERENCE 19G1.2 FOR SLUMP; \bar{f} UNLESS NOTED OTHERWISE.
 - ADJUSTMENT TO CONCRETE MIXES: MIX DESIGN ADJUSTMENTS MAY BE REQUESTED BY THE CONTRACTOR WHEN CHARACTERISTICS OF MATERIALS, JOB CONDITIONS, WEATHER, TEST RESULTS, OR OTHER CIRCUMSTANCES WARRANT. AT NO ADDITIONAL COST TO OWNER AND AS ACCEPTED BY THE OWNER, LABORATORY TEST DATA FOR REVISED MIX DESIGN AND TEST RESULTS ARE SUBMITTED TO AND ACCEPTED BY THE OWNER OR OWNER REP. BEFORE USING IN WORK. BOTH THE CONCRETE TESTING AND INSPECTION AGENCY AND THE CONCRETE CONTRACTOR SHALL SATISFY THEMSELVES THAT THE CONCRETE MIX DESIGN WILL PRODUCE A CONCRETE MIX THAT WILL MEET THE SPECIFICATIONS FOR THIS PROJECT. IN ADDITION, THE CONTRACTOR AND CONCRETE FINISHER SHALL VERIFY THAT THE WORKABILITY, FINISH, AND SETTING TIMES ARE APPROPRIATE FOR CONCRETE INSTALLATIONS. PLACEMENT SHALL BE MADE BY CHUTE DIRECTLY FROM THE CONCRETE TRUCKS. IF PUMPING OF THE CONCRETE IS CONTEMPLATED FOR ANY SPECIAL LOCATIONS, THE PROPORTIONS ESTABLISHED ABOVE SHALL NOT BE ALTERED TO THE CAPABILITIES OF THE PUMPING EQUIPMENT. PUMP SHALL NOT BE PRIMED OVER STRUCTURAL CONCRETE LOCATIONS.
 - READY MIX CONCRETE SHALL COMPLY WITH THE REQUIREMENTS OF ASTM C94. DISCHARGE OF THE CONCRETE SHALL BE COMPLETED WITHIN 90 MINUTES OR BEFORE THE DRUM HAS REVOLVED 300 REVOLUTIONS, WHICHEVER COME FIRST.
 - WATER/CEMENT RATIO SHALL BE BASED ON SURFACE DRY MATERIAL. REFERENCE 19G1.2.
 - PORTLAND CEMENT: CONFORM TO ASTM C150. TYPE I OR ONE MANUFACTURER OF CEMENT THROUGHOUT THE PROJECT.
 - FLY ASH: CONFORM TO ASTM C618.
 - COARSE AND FINE AGGREGATES: CONFORM TO ASTM C33 FOR NORMALWEIGHT CONCRETE AND ASTM C330 FOR LIGHTWEIGHT CONCRETE.
 - WATER: CONFORM WITH ASTM C1602.
 - CHEMICAL ADJUTANTS: ALL CONCRETE SHALL CONTAIN CHEMICAL ADJUTANTS TO OBTAIN THE SPECIFIED DESIGN STRENGTH IN ACCORDANCE WITH ASTM C494.
 - AIR-ENTRAINING ADJUTANTS: SHALL CONFORM TO ASTM C260. AIR-ENTRAINING ADJUTANT SHALL NOT BE USED ON INTERIOR CONCRETE.
 - WATER-REDUCING ADJUTMENT: SHALL CONFORM TO ASTM C494, TYPE A AND CONTAIN NOT MORE THAN 0.05% CHLORIDE IONS.
 - WATER-REDUCING, RETARDING ADJUTMENT: SHALL CONFORM TO ASTM C494, TYPE D, AND CONTAIN NOT MORE THAN 0.05% CHLORIDE IONS.
 - HIGH RANGE WATER-REDUCING ADJUTMENT (SUPERPLASTICIZER): SHALL CONFORM TO ASTM C494, TYPE F OR TYPE G AND CONTAIN NOT MORE THAN 0.05% CHLORIDE IONS.
 - WATER-REDUCING, NON-CORROSIVE ACCELERATING ADJUTMENT: SHALL CONFORM TO ASTM C494, TYPE C OR E AND CONTAIN NOT MORE CHLORIDE IONS THAN THAT ARE PRESENT IN MUNICIPAL DRINKING WATER. THE ADJUTMENT MANUFACTURER MUST HAVE LONG-TERM, NON-CORROSIVE TEST DATA FROM AN INDEPENDENT TESTING LABORATORY OF AT LEAST A YEARS DURATION USING AN ACCEPTABLE ACCELERATED CORROSION TEST METHOD SUCH AS THAT USING ELECTRICAL POTENTIAL ELECTRICAL POTENTIAL MEASURES.
 - PROHIBITED ADJUTMENTS: CALCIUM CHLORIDE OR ADJUTMENTS CONTAINING MORE THAN 0.05% CHLORIDE IONS ARE NOT PERMITTED.
- CONSTRUCTION JOINTS
 - NO HORIZONTAL CONSTRUCTION JOINTS WILL BE PERMITTED IN SLABS OR BEAMS BLOCK OUT "BLEEDS SHALL BE DEMOLISHED. VERTICAL CONSTRUCTION JOINTS IN SLABS OR BEAMS ARE TO BE AS SHOWN ON PLANS OR AS APPROVED BY THE ENGINEER.
 - SURFACE OF CONSTRUCTION JOINTS SHALL BE CLEANED AND LANTANCE REMOVED.
 - IMMEDIATELY BEFORE NEW CONCRETE IS PLACED, ALL CONSTRUCTION JOINTS SHALL BE WETTED AND STANDING WATER REMOVED.
 - REFERENCE TYPICAL DETAILS FOR CONSTRUCTION JOINT REINFORCING AND SHEAR KEY REQUIREMENTS.
 - CONSTRUCTION JOINTS IN FLOORS SHALL BE LOCATED WITHIN THE MIDDLE THIRD OF THE SPAN OF SLABS, BEAMS, AND GIRDERS.
 - CONSTRUCTION JOINTS IN GIRDERS SHALL BE OFFSET A MINIMUM DISTANCE OF TWO TIMES THE WIDTH OF THE INTERSECTING BEAMS.
 - BEAMS, GIRDERS, HAUNCHES, DROP PANELS, SHEAR CAPS, AND CAPITALS SHALL BE PLACED MONOLITHICALLY UNLESS NOTED OTHERWISE.
- OPENINGS AND PENETRATIONS
 - ALL OPENINGS IN SLAB (FOR PIPES, DRAINS, ETC.) SHALL BE SEALED WITH SEALANT.
 - UTILITIES THAT PROJECT THROUGH SLAB FLOORS SHALL BE DESIGNED WITH SLEEVES IN ORDER TO PREVENT DAMAGE TO THE LINE SHOULD ANY MOVEMENT OCCUR.
 - ALL OPENINGS AND PENETRATIONS ARE TO BE REINFORCED AROUND THE PERIMETER. REFERENCE THE TYPICAL DETAILS FOR REINFORCING REQUIREMENTS.
- EMBEDMENTS
 - ANCHOR RODS, DOWELS, INSERTS, ETC. SHALL BE SECURELY TIED IN PLACE PRIOR TO PLACING CONCRETE.
 - REFER TO ARCHITECTURAL, MECHANICAL, PLUMBING, AND ELECTRICAL DRAWINGS FOR ALL MOLDS, GROOVES, REGULETS, PIPES, CONDUITS, INSERTS, ETC. TO BE CAST IN CONCRETE. PROVIDE CAST-IN CONCRETE SLEEVES FOR PLUMBING AND ELECTRICAL CONDUITS AND PIPES. NO PIPES OR DUCTS SHALL BE PLACED IN CONCRETE FOOTINGS, BEAMS, COLUMNS, WALLS, OR SLABS UNLESS DETAILED IN STRUCTURAL DRAWINGS OR APPROVED BY THE ENGINEER OF RECORD.
 - CONDUITS ARE PERMITTED TO BE LOCATED BELOW SLAB-ON-GRADE REINFORCING THESE MUST BE LOCATED BELOW THE DESIGN DEPTH OF THE SLAB WITHIN A THICKENED SLAB. COORDINATE INSTALLATION OF BACKWAYS PRIOR TO PLACEMENT.
 - NO LIQUID, GAS, OR VAPOR, EXCEPT WATER NOT EXCEEDING 60 DEGREES FAHRENHEIT NOR 90 PSI PRESSURE SHALL BE PLACED IN THE PIPES UNTIL THE CONCRETE HAS ACHIEVED ITS DESIGN STRENGTH.
 - ALUMINUM CONDUITS, PIPES, OR OTHER INSERTS ARE NOT PERMITTED TO BE EMBEDDED INTO STRUCTURAL CONCRETE.
 - FORMWORK, SHORING, AND BACKSHORING
 - ALL FORMWORK SHALL BE DESIGNED BY THE GENERAL CONTRACTOR IN ACCORDANCE TO THE ACI 347 "GUIDE TO FORMWORK FOR CONCRETE," LATEST EDITION.
 - DESIGN OF FORMWORK SHALL CONSIDER
 - RATE AND METHOD OF PLACING CONCRETE.
 - CONSTRUCTION LOADS, INCLUDING VERTICAL, HORIZONTAL, AND IMPACT LOADS.
 - SPECIAL FORM REQUIREMENTS FOR CONSTRUCTION OF CURVED MEMBERS, SHELLS, FOLDED PLATES, DOMES, ARCHITECTURAL CONCRETE, OR SIMILAR TYPES OF ELEMENTS.
 - FORMS SHALL BE PROPERLY BRACED OR TIED TOGETHER TO MAINTAIN POSITION OF SHAPE.
 - FORMS SHALL BE SUBSTANTIAL AND SUFFICIENTLY TIGHT TO PREVENT LEAKAGE OR BLOWOUTS.
 - FORMS SHALL BE REMOVED SUCH THAT IT DOES IMPAIR THE SAFETY, SERVICEABILITY, AND STRUCTURAL INTEGRITY OF THE STRUCTURE.
 - BEFORE STARTING CONSTRUCTION, THE GENERAL CONTRACTOR IS RESPONSIBLE IN DEVELOPING A PROCEDURE AND SCHEDULE FOR REMOVAL OF SHORES AND INSTALLATION OF RESHORES AND FOR CALCULATING THE LOADS TRANSFERRED TO THE STRUCTURE DURING THE PROCESS.
 - NO CONSTRUCTION LOADS SHALL BE SUPPORTED ON, ANY SHORING REMOVED FROM, ANY PART OF THE STRUCTURE UNDER CONSTRUCTION EXCEPT SHORING HAS SUFFICIENT STRENGTH TO SUPPORT, SAFELY, ITS SELF-WEIGHT AND LOADS PLACED THEREON.
 - SUFFICIENT STRENGTH OF THE STRUCTURE BEING CONSIDERED IS OBTAINED WHEN THE CONCRETE STRENGTH HAS REACHED ITS DESIGN STRENGTH THROUGH APPROVED TESTING.
 - CONCRETE TESTING
 - CONCRETE SHALL BE TESTED IN ACCORDANCE TO ASTM C172, ASTM C31, ASTM C38, ASTM D3685, AND ACI 214R, ALL LATEST EDITION.
 - FREQUENCY OF SAMPLES FOR STRENGTH TESTING OF EACH CLASS OF CONCRETE SHALL BE:
 - ONCE EACH DAY A GIVEN CLASS IS PLACED.
 - ONCE FOR EACH 150 CYD OF EACH CLASS PLACED EACH DAY.
 - FOR SLABS OR WALLS LESS THAN OR EQUAL TO 9 3/4" THICK, SAMPLING SHALL BE ONCE FOR EACH 5000 SQ FT OF SLAB OR WALL SURFACE AREA (ONE SIDE ONLY) PLACED EACH DAY. FOR SLABS OR WALLS GREATER THAN 9 3/4" THICK, SAMPLING SHALL BE ONCE FOR EACH 2500 SQ FT OF SLAB OR WALL SURFACE AREA (ONE SIDE ONLY) PLACED EACH DAY.
 - CONCRETE TESTING SHALL BE THREE SETS OF CYLINDERS. ONE SET CONSISTS OF THREE 4 BY 8 IN CYLINDERS TESTED FOR COMPRESSION AT 7 DAYS AND THREE 4 BY 8 IN CYLINDERS AT 28 DAYS. 1 CYLINDER AT 56 DAYS.
 - WHERE THE TOTAL VOLUME OF CONCRETE FOR A GIVEN CLASS OF CONCRETE WOULD BE LESS THAN FIVE TESTS, PROVIDE A TEST FOR EACH BATCH.
 - LABORATORY AND FIELD TECHNICIANS SHALL BE CERTIFIED IN ACCORDANCE WITH THE REQUIREMENTS OF ACI "CONCRETE FIELD TESTING TECHNICIAN GRADE 1" CERTIFICATION PROGRAM OR THE REQUIREMENTS OF ASTM C1097 OR AN EQUIVALENT PROGRAM.
 - TEST REPORTS SHOULD BE PROMPTLY DISTRIBUTED TO THE OWNER, ARCHITECT, ENGINEER, GENERAL CONTRACTOR, SUB-CONTRACTORS, SUPPLIERS, AND BUILDING OFFICIAL TO ALLOW EITHER COMPLIANCE OR THE NEED FOR CORRECTIVE ACTION.
 - STRENGTH LEVEL OF AN INDIVIDUAL CLASS OF CONCRETE SHALL MEET THE FOLLOWING CRITERIA:
 - THE AVERAGE OF THREE CONSECUTIVE STRENGTH TESTS SHALL BE EQUAL TO OR EXCEED THE DESIGN STRENGTH, f_c .
 - THE AVERAGE OF THE STRENGTHS OF EACH TEST SHALL NOT FALL BELOW THE DESIGN STRENGTH, f_c , BY MORE THAN 500 PSI FOR $f_c \leq 5000$ PSI OR BY 0.1% FOR $f_c > 5000$ PSI.
 - IF THE CRITERIA ABOVE IS NOT MET, THREE CORE DRILLED SAMPLES IN THE AREA OF QUESTION SHALL BE TAKEN. AT THE EXPENSE OF THE GENERAL CONTRACTOR, FOR EACH STRENGTH TEST THAT FAILS TO MEET THE CRITERIA, TESTING OF CORE DRILLED SAMPLES SHALL BE IN ACCORDANCE TO ASTM C42.
 - CORE DRILLED SAMPLES SHALL BE TESTED NO EARLIER THAN 48 HOURS AND NOT LATER THAN 7 DAYS AFTER CURING.

REINFORCED CONCRETE (CONT):

- PLACEMENT OF CONCRETE
 - READY-MIXED CONCRETE SHALL BE MIXED AND DELIVERED IN ACCORDANCE TO ASTM C94.
 - CONCRETE SHALL BE CONVEYED FROM MIXER TO PLACE OF FINAL DEPOSIT BY METHODS THAT WILL PREVENT SEPARATION OR LOSS OF MATERIALS. CONCRETE SHALL BE DEPOSITED AT OR NEAR ITS FINAL POSITION BY THE METHODS, TECHNIQUES, AND OTHER MEANS AND METHODS.
 - DO NOT ALLOW CONCRETE TO FREE FALL MORE THAN 3 FEET DURING PLACEMENT.
 - ALL CONCRETE SHALL BE THOROUGHLY CONSOLIDATED DURING PLACEMENT IN ACCORDANCE TO ACI 308R, LATEST EDITION.
 - MECHANICALLY VIBRATE ALL CONCRETE DURING PLACEMENT TO AVOID AIR ENTRAPMENTS.
 - NO CONCRETE PLACEMENT IS PERMITTED WHEN THE TEMPERATURE OF FRESH CONCRETE IS GREATER THAN OR EQUAL TO 95°F.
 - NO CONCRETE PLACEMENT IS PERMITTED DURING RAIN FALL.
 - COLD WEATHER REQUIREMENTS:
 - WHEN THE AMBIENT TEMPERATURE IS BELOW 50°F, PLACEMENT OF CONCRETE SHALL BE IN ACCORDANCE TO ACI 308R.
 - ADEQUATE EQUIPMENT SHALL BE PROVIDED FOR HEATING CONCRETE MATERIALS AND PROTECTING CONCRETE DURING FREEZING OR NEAR-FREEZING WEATHER.
 - ALL CONCRETE MATERIAL AND ALL REINFORCING, FORMS, FILLERS, AND GROUND WITH WHICH CONCRETE IS TO COME IN CONTACT SHALL BE FREE OF FROST.
 - HOT WEATHER REQUIREMENTS:
 - WHEN THE AMBIENT TEMPERATURE EQUALS OR EXCEEDS 80°F, PLACEMENT OF CONCRETE SHALL BE IN ACCORDANCE TO ACI 308R.
 - PROPER ATTENTION SHALL BE GIVEN TO CONCRETE MIX, PRODUCTION METHODS, HANDLING, PLACING, PROTECTION, CURING TO PREVENT EXCESSIVE CONCRETE TEMPERATURES OR WATER EVAPORATION THAT COULD IMPAIR THE REQUIRED DESIGN STRENGTH.
 - NON-TOXIC EVAPORATION RETARDERS ARE ACCEPTABLE PROVIDED THE PRODUCT DOES NOT IMPAIR THE REQUIRED DESIGN STRENGTH WHEN USED. THE GENERAL CONTRACTOR MUST EXERCISE PROPER SAFETY MEASURES.
 - ALL EXPOSED CONCRETE SHALL HAVE A SMOOTH FINISH SURFACE. EXPOSED CONCRETE SURFACES WITH SPALLS, CHIPS, CRACKS, HONEYCOMBS, DISCOLORATION, AND OTHER IMPERFECTIONS SHALL BE PATCHED WITH A FAST-SETTING, READY TO USE, CEMENTITIOUS POLYMER-MODIFIED REPAIR MORTAR THAT SHALL MEET ALL THE FOLLOWING CRITERIA:
 - MINIMUM COMPRESSIVE STRENGTH = 5000 PSI @ 28 DAYS IN ACCORDANCE WITH ASTM C109.
 - MINIMUM FLEXURAL STRENGTH = 1100 PSI @ 28 DAYS IN ACCORDANCE WITH ASTM C293.
 - MINIMUM BOND STRENGTH = 1800 PSI @ 28 DAYS IN ACCORDANCE WITH ASTM C582.
 - COLOR = CONCRETE GRAY.
 - WET MIX DENSITY ≤ 110 PCF.
 - TOLERANCES:
 - ALL CONCRETE TOLERANCES SHALL COMPLY WITH ACI 117, "SPECIFICATIONS FOR TOLERANCES FOR CONCRETE CONSTRUCTION AND MATERIALS," LATEST EDITION.
 - ALL SLAB-ON-GRADES AND SUSPENDED FLOOR SLABS SHALL BE TESTED FOR FLOOR FLATNESS AND FLOOR LEVELNESS IN ACCORDANCE TO ASTM E1155 UTILIZING THE F-NUMBER METHOD. THE SLAB-ON-GRADE AND SUSPENDED FLOOR SLABS MEASURED F-NUMBERS SHALL MEET THE FOLLOWING CLASSIFICATION:
 - SPECIFIED OVERALL FLOOR FLATNESS (SOPF): 25
 - SPECIFIED OVERALL FLOOR LEVELNESS (SOLF): 20
 - MINIMUM LOCAL FLOOR FLATNESS (MLFF): 0.60/SOFT
 - MINIMUM LOCAL FLOOR LEVELNESS (MLFL): 0.60/SOFT
 - F-NUMBERS SHALL BE MEASURED WITHIN 72 HOURS OF PLACING THE SLAB.
 - WHERE DEFICIENCIES ARE DETECTED, REMEDIATION TO THE DEFICIENT AREA WILL BE REQUIRED AT THE EXPENSE OF THE GENERAL CONTRACTOR. REMEDIAL PROCEDURES SUCH AS, BUT NOT LIMITED TO, GRINDING OR THE USE OF A SELF-LEVELING UNDERLAYMENT SHALL BE DETERMINED BY THE CONTRACTOR TO BRING THE DEFICIENT AREA IN COMPLIANCE WITH MINIMUM TOLERANCES.
 - IN ALL INSTANCES, THE MINIMUM SLAB THICKNESS, BEAM DEPTHS AND WIDTHS, COLUMN DIMENSIONS, SHALL BE OBTAINED, COORDINATE SLAB FINISHES WITH ARCHITECTURAL PLANS.
- PLACEMENT OF REINFORCEMENT
 - ALL REINFORCING STEEL SHALL BE ASTM A615 GRADE 60 UNLESS NOTED OTHERWISE. REFERENCE "REINFORCING STEEL," NOTES FOR ADDITIONAL INFORMATION.
 - SLAB-ON-GRADE:
 - REINFORCEMENT SHALL BE CONTINUOUS ACROSS THE ENTIRE CONCRETE SURFACE UNLESS NOTED OTHERWISE.
 - PROVIDE 2 BARS, SAME SIZE AND SPACING AND IN THE APPLICABLE DIRECTION WHERE THE SLAB STEPS DOWN MORE THAN 1". THE 2 BARS SHALL LAP THE MAIN SLAB REINFORCING STEEL AS NEEDED.
 - GRADE BEAMS, CONTINUOUS WALL, FOOTINGS, AND SPREAD FOOTINGS:
 - REINFORCEMENT SHALL BE CONTINUOUS ACROSS THE ENTIRE PROFILE UNLESS NOTED OTHERWISE.
 - PROVIDE CORNER BARS, TOP AND BOTTOM, AT ALL BEAM CORNERS AND DEAD END BEAM INTERSECTIONS. REFERENCE APPLICABLE DETAILS FOR ADDITIONAL INFORMATION. BARS TO EQUAL SIZE AND QUANTITY OF THE NOTED BARS STEEL BARS UNLESS NOTED OTHERWISE.
 - EXTEND THE SLAB REINFORCING STEEL, PERPENDICULAR TO BEAM, TO THE TOP OUTSIDE REINFORCING BAR OF THE PERIMETER BEAMS. START THE SLAB REINFORCING STEEL, PARALLEL, TO THE BEAM, NOT MORE THAN 6" FROM THE TOP INSIDE REINFORCING BAR OF PERIMETER BEAMS.
 - VERTICAL REINFORCEMENT SHALL BE TIED AND FIXED IN POSITION AT THE TOP AND BOTTOM AND AT INTERMEDIATE LOCATIONS, SPACED NOT GREATER THAN 18 INCHES ON CENTER.
 - DRILLED PIERS:
 - REINFORCEMENT SHALL BE CONTINUOUS ACROSS THE ENTIRE PROFILE UNLESS NOTED OTHERWISE.
 - SUSPENDED SLAB (ONE-WAY):
 - REINFORCEMENT SHALL BE CONTINUOUS ACROSS THE ENTIRE CONCRETE SURFACE. DESIGN REINFORCING IS PLACED PARALLEL TO THE DIRECTION OF SPAN. TEMPERATURE STEEL IS PROVIDED PERPENDICULAR TO THE DIRECTION OF THE SPAN.
 - WHERE LAP SPLICES OF BARS ARE REQUIRED, LOCATE BOTTOM BAR LAP SPLICES OVER CONCRETE BEAMS OR GIRDERS, AND LOCATE TOP BAR LAP SPLICES AT MIDSPAN IN BETWEEN BEAMS.
 - REFERENCE TYPICAL DETAILS FOR ADDITIONAL REQUIREMENTS.
 - SUSPENDED SLAB (TWO-WAY):
 - TOP AND BOTTOM REINFORCING MATS SHALL BE CONTINUOUS EACH WAY UNLESS NOTED OTHERWISE.
 - ADDITIONAL BARS ARE SHOWN ON THE DRAWINGS.
 - WHERE LAP SPLICES ARE REQUIRED, LOCATE BOTTOM BAR LAP SPLICES CENTERED TO THE COLUMN STRIPS, AND TOP BAR LAP SPLICES CENTERED TO THE MIDDLE STRIPS IN EACH DIRECTION.
 - REFERENCE DETAILS FOR ADDITIONAL REQUIREMENTS.
 - BEAMS AND GIRDERS:
 - REFERENCE REINFORCING SCHEDULE FOR LONGITUDINAL BAR PLACEMENT. BARS ARE TO BE CONTINUOUS UNLESS NOTED OTHERWISE.
 - REFERENCE TYPICAL DETAILS FOR BAR LAP SPLICES. LOCATE LAP SPLICES OF BOTTOM BARS CENTERED OVER SUPPORTS, AND LOCATE TOP BAR LAP SPLICES CENTERED AT MIDSPAN IN BETWEEN SUPPORTS.
 - REFERENCE DETAILS FOR ADDITIONAL REQUIREMENTS.
 - COLUMNS:
 - PROVIDE CONTINUOUS LONGITUDINAL REINFORCING EQUALLY SPACED.
 - WHEN REQUIRED, LOCATE LAP SPLICES LONGITUDINAL REINFORCING WITH A CLASS B TENSION LAP SPLICE.
 - REFERENCE DETAILS FOR ADDITIONAL REQUIREMENTS.
 - WALLS:
 - PROVIDE CONTINUOUS REINFORCING IN BOTH DIRECTIONS AND IN EACH FACE WHERE APPLICABLE.
 - AT HORIZONTAL CONSTRUCTION JOINTS (CONSTRUCTION LIFTS), VERTICAL BARS MUST PROJECT THE LAP SPLICE LENGTH AS SCHEDULED AS A MINIMUM LENGTH. THE GENERAL CONTRACTOR MUST COORDINATE BAR PLACEMENTS TO AVOID OVER-REINFORCING THE CONCRETE WALL.
 - REFERENCE DETAILS FOR ADDITIONAL INFORMATION.
 - DOWELS:
 - WALLS, PLASTERS, AND COLUMNS SHALL BE DOWELED TO THE SUPPORTING FOOTINGS WITH REINFORCEMENT AS SCHEDULED OR OF THE SAME SIZE, GRADE AND AT THE SAME SPACING AS THE VERTICAL REINFORCEMENT IN THE WALLS, PLASTERS, OR COLUMNS UNLESS NOTED OTHERWISE.

CLASSES OF CONCRETE MATRIX

CONCRETE USAGE	MINIMUM COMPRESSIVE STRENGTH, f_c	CONCRETE WEIGHT	EXPOSURE CLASS	MAXIMUM WATER/CEMENT RATIO	MAXIMUM AGGREGATE SIZE (IN)	MAXIMUM SLUMP (IN)	REMARKS
SHALLOW FOUNDATIONS							
SPREAD FOOTINGS	3000 PSI @ 28 DAYS	NWC	C1	0.5	1"	5"	
WALL FOOTINGS	3000 PSI @ 28 DAYS	NWC	C1	0.5	1"	5"	
SLAB-ON-GRADE	3000 PSI @ 28 DAYS	NWC	C1	0.5	1"	5"	
MISCELLANEOUS							
HOUSEKEEPING PADS	3000 PSI @ 28 DAYS	NWC	C1	0.5	1"	5"	
ALL OTHER CONCRETE	3000 PSI @ 28 DAYS	NWC	C1	0.5	1"	5"	

NOTES:

- ALL CONCRETE COMPRESSIVE STRENGTHS NOTED IN THE TABLE ABOVE ARE THE MINIMUM COMPRESSIVE STRENGTH, f_c , AT 28-DAYS UNLESS NOTED OTHERWISE.
- ALL MIXES SHALL HAVE A MINIMUM OF 5 SACKS (470 LBS) OF CEMENTITIOUS MATERIAL PER CUBIC YARD REGARDLESS OF STRENGTH OBTAINED.
- ALL CONCRETE SHALL BE CONSIDERED TO BE IN EXPOSURE F0, S0, P0, AND C0 ACCORDING TO ACI 318 UNLESS NOTED OTHERWISE IN TABLE ABOVE OR IN THE STRUCTURAL DRAWINGS.

1. CLASSES OF CONCRETE MATRIX SCHEDULE

NTS

REINFORCED CONCRETE (CONT):

- TOPPING SLABS:
 - PROVIDED WELDED WIRE REINFORCING 6X6-W2X9/29 IN ALL TOPPING SLABS UNLESS NOTED OTHERWISE.
- HOUSEKEEPING PADS:
 - PROVIDED #3 AT 12" ON CENTER EACH WAY IN ALL HOUSEKEEPING PADS THAT SUPPORT MECHANICAL EQUIPMENT.
- VAPOR RETARDER
 - REFERENCE DRAWINGS FOR LOCATION AND EXTENTS OF VAPOR RETARDERS. FOR SLAB-ON-GRADE FOUNDATIONS, A VAPOR RETARDER IS TO BE INSTALLED OVER APPROVED SELECT FILL UNLESS NOTED OTHERWISE.
 - FOR ALL CONDITIONS, THE VAPOR RETARDER SHALL CONFORM TO ASTM E1745, CLASS A AND SHALL HAVE A MINIMUM WATER VAPOR PERMEANCE OF 0.01 PERMEAS WHEN TESTED IN ACCORDANCE WITH ASTM E96. THE VAPOR RETARDER SHALL NOT BE LESS THAN 15 MILS THICK.
 - PRE-APPROVED PRODUCTS:
 - STEGO WRAP 15 MIL VAPOR BARRIER (CLASS A).
 - OTHERS PROPOSED BY SUBMITTAL PROCESS.
- INSTALLATION:
 - LAY SHEETS SMOOTHLY, STRETCH AND WEIGHT EDGES, LAP JOINTS AND SEAL WITH TAPE AS SPECIFIED BY THE VAPOR RETARDER MANUFACTURER. TURN THE RETARDER UP AT WALLS AND AT ALL PIPES, ABUTMENTS, ETC., AND TAPE AND SEAL AT PENETRATIONS AND AT EDGES AS SPECIFIED BY THE VAPOR RETARDER MANUFACTURER.
- PATCHING:
 - PATCH ALL PUNCTURES WITH A MINIMUM OVERLAP OF 6" IN ALL DIRECTIONS AND TAPE AROUND THE ENTIRE PERIMETER OF REPAIR.
- PRE-INSTALLATION CONFERENCE
 - AT LEAST 30 DAYS PRIOR TO THE START OF THE CONCRETE CONSTRUCTION SCHEDULE, THE CONTRACTOR SHALL CONDUCT A MEETING TO REVIEW THE PROPOSED MIX DESIGNS AND TO DISCUSS THE REQUIRED METHODS AND PROCEDURES TO ACHIEVE THE REQUIRED CONCRETE CONSTRUCTION. THE CONTRACTOR SHALL SEND A PRE-INSTALLATION CONFERENCE AGENDA TO ALL ATTENDEES 20 DAYS PRIOR TO THE SCHEDULED DATE OF THE CONFERENCE.
 - THE CONTRACTOR SHALL REQUIRE RESPONSIBLE REPRESENTATIVES OF EVERY PARTY CONCERNED WITH THE CONCRETE WORK TO ATTEND THE CONFERENCE, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - GENERAL CONTRACTOR'S SUPERINTENDENT
 - LABORATORY RESPONSIBLE FOR CONCRETE MIXES AND/OR FIELD QUALITY CONTROL
 - READY-MIX CONCRETE PRODUCER
 - CONCRETE SUB-CONTRACTOR
 - MINUTES OF THE MEETING SHALL BE RECORDED, TYPED AND PRINTED BY THE CONTRACTOR AND DISTRIBUTED TO ALL CONCERNED PARTIES, INCLUDING THE OWNER'S REPRESENTATIVE, THE ARCHITECT, AND THE STRUCTURAL ENGINEER WITHIN FIVE DAYS OF THE MEETING.
- CONCRETE SUB-CONTRACTOR QUALIFICATION
 - THE CONCRETE SUB-CONTRACTOR SHALL INCLUDE IN THEIR BID PACKAGE TO THE GENERAL CONTRACTOR SUFFICIENT DATA THAT CLEARLY INDICATES THE CONCRETE CONTRACTORS' ABILITY TO SUCCESSFULLY PERFORM THE WORK AND TO ACHIEVE THE TOLERANCES SPECIFIED IN THIS SECTION.
- CONCRETE CURING
 - CONCRETE SHALL BE MAINTAINED ABOVE 50°F AT ALL TIMES.
 - CONCRETE, OTHER THAN HIGH-EARLY STRENGTH CONCRETE, SHALL BE IN MOIST CONDITION FOR AT LEAST 7 DAYS.
 - HIGH-EARLY STRENGTH CONCRETE SHALL BE IN MOIST CONDITION FOR AT LEAST 3 DAYS.
 - EXTERIOR CURING: ALL EXTERIOR CONCRETE SLABS SHALL BE CURED USING A LIQUID MEMBRANE-FORMING CURING COMPOUND. THE LIQUID MEMBRANE-FORMING CURING COMPOUND SHALL MEET THE REQUIREMENTS OF ASTM C1315 WITH A MAXIMUM VOLATILE ORGANIC CONTENT (VOC) OF 700 g/L.
 - INTERIOR CURING: ALL INTERIOR CONCRETE SLABS SHALL BE CURED USING A REDUCED ODOR, DISSIPATING LIQUID MEMBRANE-FORMING CURING COMPOUND THAT IS FORMULATED FROM HYDROCARBON RESINS. THE DISSIPATING LIQUID MEMBRANE-FORMING CURING COMPOUND SHALL MEET THE REQUIREMENTS OF ASTM C309 WITH A MAXIMUM VOLATILE ORGANIC CONTENT (VOC) OF 350 g/L. APPLY AT 400 SF/GALLON.
 - CURING COMPOUNDS SHALL BE PLACED WITHIN 4 HOURS AFTER PLACEMENT OF CONCRETE.
 - FOR POLISHED SLAB FINISHES, PROVIDE BURLAP MEMBRANES DURING ENTIRE CONSTRUCTION OF THE BUILDING. DO NOT PROVIDE CURING COMPOUND.
- CONTRACTION JOINTS IN SLAB-ON-GRADE
 - FORM 18" WEATHERED-PLANE CONTRACTION JOINTS SPACED NOT FURTHER THAN 15'-0" ON CENTER EACH WAY. SECTION CONCRETE INTO AREAS AS INDICATED IN THE DRAWINGS.
 - CONSTRUCT CONTRACTION JOINTS FOR A DEPTH EQUAL TO, TO AT LEAST 1/4 OF THE CONCRETE THICKNESS.
 - SAVED JOINTS: ALL SAW CUTTING SHALL BE ACCOMPLISHED WITH A SOFT-CUT SAW AS SOON AS THE SLAB WILL SUPPORT THE WEIGHT OF THE SAW AND OPERATOR.
 - CONCRETE DUST SHALL BE REMOVED COMPLETELY AND IMMEDIATELY.
 - ALL CONTRACTION JOINTS SHALL BE CAULKED WITH AN EFFECTIVE SEALANT THAT CAN BOND TO THE CONCRETE, IS IMPERMEABLE, AND ABLE TO WITHSTAND THERMAL EXPANSION AND CONTRACTION.
- CONCRETE PROTECTION
 - SLAB PROTECTION:
 - FOR ALL MOTORIZED AND HYDRAULIC EQUIPMENT PREVENT FLUID LEAKS.
 - PROVIDE NON-MARKING TIRES ON RUBBER TIED VEHICLES OR EQUIP RUBBER TIRES WITH TIRE BOOTS MADE OF NYLON FABRIC.
 - PROVIDE MATS AT ALL ENTRANCES TO PREVENT MUD STAINS.
 - COVER SLAB PRIOR TO PAINTING. ALL SPLLS ARE TO BE CLEANED WITH SOAP AND WATER.
- CONCRETE COVER
 - REINFORCING STEEL COVERAGE SHOULD CONFORM TO THE REQUIREMENTS OF THE ACI 318 (EDITION IN THE DESIGN CRITERIA) SECTION 7.7 AND THE DETAILS.
 - INCREASE COVER TO MAINTAIN THE MINIMUM SPECIFIED WHERE REINFORCING STEEL INTERSECTS FOR DIFFERENT MEMBER TYPES.
 - THE REINFORCING STEEL DETAILER SHALL ADJUST REINFORCING STEEL COVERAGE AT INTERSECTING STRUCTURAL MEMBERS AS REQUIRED TO ALLOW CLEARANCE FOR INTERSECTING REINFORCING BAR LAYERS WITH MINIMUM SPECIFIED COVER.
 - MINIMUM CONCRETE COVER FOR REINFORCING AS FOLLOWS:
 - ALL CONCRETE CAST AND PERMANENTLY EXPOSED TO EARTH..... 3"
 - CONCRETE EXPOSED TO EARTH OR WEATHER:
 - #6 THROUGH #18..... 2"
 - #6, W10 OR D31, AND SMALLER..... 1-1/2"
 - CONCRETE NOT EXPOSED TO WEATHER OR IN CONTACT WITH GROUND:
 - #18, WALLS, JOISTS..... 1-1/2"
 - #14 THROUGH #16..... 3/4"
 - #11 AND SMALLER..... 3/4"
 - BEAMS, COLUMNS..... 1-1/2"

POST-INSTALLED ANCHORS:

- GENERAL
 - POST-INSTALLED ANCHORS SHALL ONLY BE USED WHERE SPECIFIED ON THE DRAWINGS.
 - THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE EOR PRIOR TO INSTALLING POST-INSTALLED ANCHORS IN PLACE OF MISSING OR MISPLACED CAST-IN-PLACE ANCHORS.
 - CARE SHALL BE TAKEN IN PLACING POST-INSTALLED ANCHORS TO AVOID CONFLICTS WITH EXISTING REINFORCING STEEL.
 - HOLES SHALL BE DRILLED AND CLEANED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
- SUBSTITUTIONS
 - SUBSTITUTION REQUESTS FOR PRODUCTS OTHER THAN THOSE SPECIFIED BELOW SHALL BE SUBMITTED BY THE CONTRACTOR TO THE EOR ALONG WITH CALCULATIONS THAT ARE PREPARED AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
 - THE CALCULATIONS SHALL DEMONSTRATE THE SUBSTITUTED PRODUCT IS CAPABLE OF ACHIEVING THE EQUIVALENT PERFORMANCE VALUES (MINIMUM) OF THE SPECIFIED PRODUCT USING THE APPROPRIATE DESIGN PROCEDURE AND/OR STANDARD(S) AS REQUIRED BY CODE.
- SPECIAL INSPECTION
 - REFERENCE "SPECIAL INSPECTION AND MATERIAL TESTING" FOR SPECIAL INSPECTION REQUIREMENTS FOR POSTINSTALLED ANCHORS.
- SPECIAL INSPECTOR SHALL PROVIDE CONTINUOUS SPECIAL INSPECTION FOR ALL MECHANICAL AND ADHESIVE ANCHORS PER THE APPLICABLE EVALUATION REPORT.
- INSTALLATION TRAINING/PRE-INSTALLATION CONFERENCE
 - CONTACT MANUFACTURER'S REPRESENTATIVE FOR THE INITIAL TRAINING AND INSTALLATION OF ANCHORS AND FOR PRODUCT RELATED QUESTIONS AND AVAILABILITY PRIOR TO INSTALLING ALL POST-INSTALLED ANCHORS.
- CONCRETE ANCHORS
 - MECHANICAL ANCHORS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI 308.2 AND ICCES AC108 FOR CRACKED AND UNCRACKED CONCRETE RECOGNITION. PRE-APPROVED MECHANICAL ANCHORS INCLUDE:
 - SIMPSON STRONG-TIE:
 - SIMPSON STRONG-TIE "TITEN-HD" AND "TITEN-HD ROD HANGER" (ICC-ES ESR-2713)
 - SIMPSON STRONG-TIE "STRONG-BOLT" (ICC-ES ESR-1771)
 - SIMPSON STRONG-TIE "STRONG-BOLT 2" (ICC-ES ESR-3037)
 - SIMPSON STRONG-TIE "TORO CUT" (ICC-ES ESR-2705)
 - ADHESIVE ANCHORS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI 308.4 AND ICCES AC308 FOR CRACKED AND UNCRACKED CONCRETE RECOGNITION. PRE-APPROVED ADHESIVE ANCHORING SYSTEM INCLUDE:
 - SIMPSON STRONG-TIE:
 - SIMPSON STRONG-TIE "AT-XP" ADHESIVE (ICC-ES AC308)
 - SIMPSON STRONG-TIE "SET-XP" ADHESIVE (ICC-ES ESR-2508)
- POWDER ACTUATED FASTENERS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICCES AC108. PRE-APPROVED POWDER ACTUATED FASTENERS INCLUDE:
 - SIMPSON STRONG-TIE:
 - SIMPSON STRONG-TIE "POWER-DRIVEN FASTENERS" (ICC-ES ESR-2138)
- MASONRY ANCHORS
 - ANCHORAGE TO SOLID-GROUTED CONCRETE MASONRY:
 - CONCRETE SHALL BE TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICCES AC101 OR AC106. PRE-APPROVED MECHANICAL ANCHORS INCLUDE:
 - SIMPSON STRONG-TIE:
 - SIMPSON STRONG-TIE "TITEN-HD" (ICC-ES ESR-1056)
 - SIMPSON STRONG-TIE "STRONG-BOLT 2" (APMO-ES ER-0240)
 - SIMPSON STRONG-TIE "WEDGE-ALL" (ICC-ES ESR-1596)
 - ADHESIVE ANCHORS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICCES AC08. PRE-APPROVED ADHESIVE ANCHORING SYSTEM INCLUDE:
 - SIMPSON STRONG-TIE:
 - SIMPSON STRONG-TIE "SET-XP" ADHESIVE (ICC-ES ESR-2508)
 - ANCHORAGE TO HOLLOW CONCRETE MASONRY/UNREINFORCED CLAY BRICK MASONRY:
 - MECHANICAL ANCHORS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICCES AC101 OR AC106. PRE-APPROVED MECHANICAL ANCHORS INCLUDE:
 - SIMPSON STRONG-TIE:
 - SIMPSON STRONG-TIE "TITEN-HD" (ICC-ES ESR-1056)
 - ADHESIVE ANCHORS WITH SCREEN TUBES SHALL BE TESTED AND QUALIFIED IN ACCORDANCE WITH ICCES AC08 OR AC09, AS APPROPRIATE. THE APPROPRIATE SCREEN TUBE SHALL BE USED AS RECOMMENDED BY THE ADHESIVE MANUFACTURER. PRE-APPROVED ADHESIVE ANCHORS WITH SCREEN TUBES INCLUDE:
 - SIMPSON STRONG-TIE:
 - SIMPSON STRONG-TIE "SET-XP" ADHESIVE (ICC-ES ESR-2508)
 - ANCHORAGE TO HOLLOWMUD-LT-WHY THE MASONRY:
 - ADHESIVE ANCHORS WITH SCREEN TUBES SHALL BE TESTED AND QUALIFIED IN ACCORDANCE WITH ICCES AC08 OR AC09, AS APPROPRIATE. THE APPROPRIATE SCREEN TUBE SHALL BE USED AS RECOMMENDED BY THE ADHESIVE MANUFACTURER. PRE-APPROVED ADHESIVE ANCHORS WITH SCREEN TUBES INCLUDE:
 - HILTI:
 - HILTI "HIT-HY 70" MASONRY ADHESIVE (ICC-ES ESR-3442)

REINFORCING STEEL:

- GENERAL
 - DEFORMED BAR REINFORCEMENT SHALL CONFORM TO THE FOLLOWING GRADES OF ASTM A615 GRADE 60 ON THE DRAWINGS OR IN NOTES.
 - DETAILING OF REINFORCEMENT SHALL BE IN ACCORDANCE WITH CHAPTER 26 OF ACI 318.
 - REINFORCING STEEL REQUIRED TO BE WELDED SHALL CONFORM TO ASTM A706.
 - WELDED WIRE REINFORCEMENT SHALL CONFORM TO ASTM A1064.
 - ALL REINFORCEMENT SHALL BE SECURELY TIED IN PLACE BEFORE CONCRETE AND/OR GROUT.
- SUPPORTS FOR REINFORCEMENT
 - SUPPORT FOR REINFORCEMENT SHALL INCLUDE BOLSTERS, CHAIRS, SPACERS, AND OTHER DEVICES FOR SPACING, SUPPORTING, AND FASTENING REINFORCING BARS AND WELDED WIRE REINFORCEMENT IN PLACE.
 - BAR SUPPORTS SHALL BE PROVIDED IN ACCORDANCE WITH THE PROVISIONS OF "BAR SUPPORT SPECIFICATIONS" AS THE LATEST EDITION OF "MANUAL OF STANDARD PRACTICE" BY CONCRETE REINFORCING STEEL INSTITUTE (CRSI).
 - SLAB-ON-GRADE: USE PRECAST CONCRETE BAR SUPPORTS (DOBIES) OR CHAIRS DESIGNED FOR SOIL-SUPPORTED SLABS SPACED AT 36 INCHES ON CENTER FOR #3 BARS AND 48 INCHES ON CENTER FOR #4 AND ABOVE.
 - SPREAD FOOTINGS AND GRADE BEAMS: USE PRECAST CONCRETE BAR SUPPORTS (DOBIES) OR CHAIRS DESIGNED FOR SOIL-SUPPORTED SLABS.
 - PIERS: USE PRECAST CONCRETE BAR SUPPORTS (DOBIES), CRSI CLASS 1 WHEELS, AND BOLSTERS.
 - SUSPENDED SLABS, BEAMS, AND GIRDERS: PROVIDE CRSI CLASS 1 SUPPORTS WITH LEGS.
- DETAILING
 - REINFORCING STEEL DETAILING, BENDING AND PLACING SHALL BE IN ACCORDANCE WITH THE CONCRETE REINFORCING STEEL INSTITUTE (CRSI) "MANUAL OF STANDARD PRACTICE," LATEST EDITION.
 - BARS DETAILED AS CONTINUOUS SHALL BE LAPPED AT SPLICES.
 - REFERENCE APPLICABLE SCHEDULES FOR LAPS AT BAR SPLICES.
- PLACEMENT OF WELDED WIRE REINFORCING
 - WELDED WIRE REINFORCING SHALL BE CONTINUOUS ACROSS THE ENTIRE CONCRETE SURFACE AND NOT INTERRUPTED BY BEAMS OR GIRDERS.
 - LAPS OF WELDED WIRE REINFORCING AT SPLICES SHALL BE AS INDICATED IN THE SCHEDULE.
- NON-PERMITTED ITEMS
 - WELDING OF CROSSING BARS AND TACK WELDING OF REINFORCEMENT SHALL NOT BE PERMITTED.
 - WELDING OF REINFORCING STEEL IS NOT PERMITTED, UNLESS NOTED OTHERWISE.
- SHOP DRAWINGS
 - CONTRACTOR SHALL SUBMIT REINFORCING STEEL SHOP DRAWINGS FOR REVIEW FABRICATION SHOP DRAWINGS SHALL



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #:
DRAWN BY:
CHECKED BY:
DATE: 4/28/25

GENERAL
NOTES

S1.2

GENERAL NOTES

VERIFICATION AND INSPECTION OF STRUCTURAL STEEL WELDING				
SPECIAL INSPECTION REQUIRED	VERIFICATION AND INSPECTION TASK	SPECIAL INSPECTOR QCI QAI	REFERENCE STANDARD	IBC REFERENCE
YES	1. INSPECTION TASK PRIOR TO WELDING: a. WELDING PROCEDURES CERTIFICATIONS (WPS) AVAILABLE	P	P	
YES	b. MANUFACTURER CERTIFICATIONS FOR WELDING CONSUMABLES AVAILABLE	PP		
YES	c. MATERIAL IDENTIFICATION (TYPE/GRADE)	OO		
YES	d. WELDER IDENTIFICATION SYSTEM	OO		
YES	e. FIT-UP OF GROOVE WELDS (INCLUDING JOINT GEOMETRY) 1) JOINT PREPARATION 2) DIMENSIONS (ALIGNMENT, ROOT OPENING, ROOT FACE, BEVEL) 3) CLEANNESS (CONDITION OF STEEL SURFACES) 4) TACKLING (TACK WELD QUALITY AND LOCATION) 5) BACKING TYPE AND FIT (IF APPLICABLE)	OO	AISC 360-10 TABLE N5.4-1, AWS D1.1	1705.2.1
YES	f. CONFIGURATION AND FINISH OF ACCESS HOLES	OO		
YES	g. FIT-UP OF FILLET WELDS 1) DIMENSIONS (ALIGNMENT, GAPS AT ROOT) 2) CLEANNESS (CONDITION OF STEEL SURFACES) 3) TACKLING (TACK WELD QUALITY AND LOCATION)	OO		
YES	h. CHECK WELDING EQUIPMENT	O-		
YES	i. INSPECTION TASK DURING WELDING: a. USE OF QUALIFIED WELDERS	OO		
YES	b. CONTROL AND HANDLING OF WELDING CONSUMABLES 1) PACKING 2) EXPOSURE CONTROL	OO		
YES	c. NO WELDING OVER CRACKED TACK WELDS	OO		
YES	d. ENVIRONMENTAL CONDITIONS 1) WIND SPEED WITHIN LIMITS 2) PRECIPITATION AND TEMPERATURE	OO		
YES	e. WPS FOLLOWED 1) SETTINGS ON WELDING EQUIPMENT 2) TRAVEL SPEED 3) SELECTED WELDING MATERIALS 4) SHIELDING GAS TYPE/FLOW RATE 5) PREHEAT APPLIED 6) INTERPASS TEMPERATURE MAINTAINED (MIN/MAX) 7) PROPER POSITION (F, V, H, OH)	OO	AISC 360-10 TABLE N6.4-2, AWS D1.1	1705.2.1
YES	f. WELDING TECHNIQUES 1) INTERPASS AND FINAL CLEANING 2) EACH PASS WITHIN PROFILE LIMITATIONS 3) EACH PASS MEETS QUALITY REQUIREMENTS	OO		
YES	3. INSPECTION TASK AFTER WELDING: a. WELDS CLEANED	OO		
YES	b. SIZE, LENGTH AND LOCATION OF WELDS	PP		
YES	c. WELD MEET VISUAL ACCEPTANCE CRITERIA 1) CRACK PROHIBITION 2) WELD/BASE METAL FUSION 3) CRATER CROSS SECTION 4) WELD PROFILES 5) WELD SIZE 6) UNDERCUT 7) POROSITY	PP	AISC 360-10 TABLE N5.4-3, AWS D1.1	1705.2.1
YES	d. ARC STRIKES	PP		
YES	e. AREA	PP		
YES	f. REMOVED AND WELD TACKS REMOVED	PP		
YES	g. REPAIR ACTIVITIES	PP		
YES	h. DOCUMENT ACCEPTANCE OR REJECTION OF WELD JOINT OR MEMBER	PP		

- NOTES:
- QCI = FABRICATORS OR ERECTORS QUALITY CONTROL INSPECTOR RESPONSIBLE FOR WORK PERFORMED IS IN COMPLIANCE WITH THE SHOP DRAWINGS, ERECTION DRAWINGS, REFERENCE SPECIFICATIONS, CODES AND STANDARDS.
 - QAI = THE OWNER'S APPROVED AGENCY'S QUALITY ASSURANCE INSPECTOR (SPECIAL INSPECTOR) RESPONSIBLE FOR INSPECTION OF FABRICATED ITEMS, INSPECTION OF THE ERECTED STEEL SYSTEM, REVIEW TEST REPORTS AND CERTIFICATIONS, ITEMS NOTED IN THE TABLE ABOVE, AND FURNISHES INSPECTIONS, REPORTS, AND NONDESTRUCTIVE TESTING (NDT) REPORTS.
 - O = OBSERVE THESE ITEMS IN A RANDOM BASIS. OPERATIONS NEED NOT BE DELAYED PENDING THESE INSPECTIONS.
 - P = PERFORM THE TASK FOR EACH WELDED JOINT OR MEMBER.
 - THE QAI IS NOT REQUIRED TO INSPECT FABRICATED ITEMS IF THE STEEL FABRICATOR IS DEEMED AN APPROVED FABRICATOR.
 - WHERE A TASK IS NOTED TO BE PERFORMED BY BOTH THE QCI AND QAI, IT IS PERMITTED TO COORDINATE THE INSPECTION FUNCTION BETWEEN THE QCI AND QAI SO THAT THE INSPECTION FUNCTION IS PERFORMED BY ONLY ONE PARTY.
 - ALL WELD WELDING, COMPLETE AND PARTIAL JOINT PENETRATION WELDS SHALL BE SUBJECTED TO NONDESTRUCTIVE TESTING (NDT) IN ACCORDANCE WITH AWS D1.1. ACCEPTANCE CRITERIA SHALL BE IN ACCORDANCE WITH THE AWS D1.1.
 - ACCEPTABLE NONDESTRUCTIVE TESTING (NDT) METHODS AS PER THE AISC 360 SPECIFICATION ARE AS FOLLOWS:
a. ULTRASONIC TESTING (UT)
b. MAGNETIC PARTICLE TESTING (MT)
c. PENETRANT TESTING (PT)
d. RADIOGRAPHIC TESTING (RT)
 - THE SPECIAL INSPECTOR SHALL BE RESPONSIBLE FOR DETERMINING THE APPROPRIATE NDT METHOD FOR EACH WELD.
 - ALL NDT PERFORMED SHALL BE DOCUMENTED INTO A REPORT AND SHALL INCLUDE THE FOLLOWING:
a. LOCATION OF THE TESTED WELD
b. FIELD MARK
c. LOCATION OF THE PIECE

VERIFICATION AND INSPECTION OF STEEL FRAMING				
SPECIAL INSPECTION REQUIRED	VERIFICATION AND INSPECTION TASK	SPECIAL INSPECTOR QCI QAI	REFERENCE STANDARD	IBC REFERENCE
YES	1. VERIFY FABRICATED STEEL IS IN COMPLIANCE WITH THE SHOP DRAWINGS	PO		
YES	2. VERIFY ERECTED STEEL IS IN COMPLIANCE WITH THE ERECTION DRAWINGS	PO		
YES	3. INSPECTION DURING PLACEMENT OF ANCHOR RODS AND OTHER EMBEDMENTS SUPPORTING STRUCTURAL STEEL FOR COMPLIANCE WITH THE CONTRACT DOCUMENTS	-P	AISC 360-10 N5.7	1705.2.1
YES	4. VERIFY DIAMETER, GRADE, TYPE AND LENGTH OF THE ANCHOR ROD OR EMBEDDED ITEM AND THE EXTENT OR DEPTH OF EMBEDMENT INTO CONCRETE PRIOR TO PLACEMENT OF CONCRETE	-P		

- NOTES:
- QCI = FABRICATORS OR ERECTORS QUALITY CONTROL INSPECTOR RESPONSIBLE FOR WORK PERFORMED IS IN COMPLIANCE WITH THE SHOP DRAWINGS, ERECTION DRAWINGS, REFERENCE SPECIFICATIONS, CODES AND STANDARDS.
 - QAI = THE OWNER'S APPROVED AGENCY'S QUALITY ASSURANCE INSPECTOR (SPECIAL INSPECTOR) RESPONSIBLE FOR INSPECTION OF FABRICATED ITEMS, INSPECTION OF THE ERECTED STEEL SYSTEM, REVIEW TEST REPORTS AND CERTIFICATIONS, ITEMS NOTED IN THE TABLE ABOVE, AND FURNISHES INSPECTIONS, REPORTS, AND NONDESTRUCTIVE TESTING (NDT) REPORTS.
 - O = OBSERVE THESE ITEMS IN A RANDOM BASIS. OPERATIONS NEED NOT BE DELAYED PENDING THESE INSPECTIONS.
 - P = PERFORM THE TASK FOR EACH STEEL ELEMENT.
 - THE QAI IS NOT REQUIRED TO INSPECT FABRICATED ITEMS IF THE STEEL FABRICATOR IS DEEMED AN APPROVED FABRICATOR.
 - WHERE A TASK IS NOTED TO BE PERFORMED BY BOTH THE QCI AND QAI, IT IS PERMITTED TO COORDINATE THE INSPECTION FUNCTION BETWEEN THE QCI AND QAI SO THAT THE INSPECTION FUNCTION IS PERFORMED BY ONLY ONE PARTY.
 - AS A MINIMUM, THE DIAMETER, GRADE, TYPE AND LENGTH OF THE ANCHOR RODS OR EMBEDDED ITEM AND THE EXTENT OR DEPTH OF EMBEDMENT INTO THE CONCRETE SHALL BE VERIFIED PRIOR TO PLACEMENT OF CONCRETE.

VERIFICATION AND INSPECTION OF STRUCTURAL STEEL BOLTING				
SPECIAL INSPECTION REQUIRED	VERIFICATION AND INSPECTION TASK	SPECIAL INSPECTOR QCI QAI	REFERENCE STANDARD	IBC REFERENCE
YES	1. INSPECTION TASK PRIOR TO BOLTING: a. MANUFACTURER'S CERTIFICATIONS AVAILABLE FOR FASTENER MATERIALS	OP		
YES	b. FASTENERS MARKED IN ACCORDANCE WITH ASTM REQUIREMENTS	OO		
YES	c. PROPER FASTENERS SELECTED FOR THE JOINT DETAIL (GRADE, TYPE, BOLT LENGTH IF THREADS ARE TO BE EXCLUDED FROM SHEAR PLANE)	OO		
YES	d. PROPER BOLTING PROCEDURE SELECTED FOR JOINT DETAIL	O	O	AISC 360-10 TABLE N5.6-1
YES	e. CONNECTING ELEMENTS, INCLUDING THE APPROPRIATE FAYING SURFACE CONDITION AND HOLE PREPARATION, IF SPECIFIED, MEET APPLICABLE REQUIREMENTS	OO		
YES	f. PRE-INSTALLATION VERIFICATION TESTING BY INSTALLATION PERSONNEL OBSERVED AND DOCUMENTED FOR FASTENER ASSEMBLIES AND METHODS USED	PO		
YES	g. PROPER STORAGE PROVIDED FOR BOLTS, NUTS, WASHERS AND OTHER FASTENER COMPONENTS	OO		
YES	2. INSPECTION TASK DURING BOLTING: a. FASTENER ASSEMBLIES, OF SUITABLE CONDITION, PLACED IN ALL HOLES AND WASHERS (IF REQUIRED) ARE POSITIONED AS REQUIRED	OO		
YES	b. JOINT BROUGHT TO THE SNUG-TIGHT POSITION CONDITION PRIOR TO THE PRETENSIONING OPERATION	OO		AISC 360-10 TABLE N5.6-2
YES	c. FASTENER COMPONENT NOT TURNED BY THE WRENCH PREVENTED FROM ROTATING	OO		
YES	d. FASTENERS ARE PRETENSIONED IN ACCORDANCE WITH THE RCSC SPECIFICATION, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID POINT TOWARD THE FREE EDGES	OO		
YES	3. INSPECTION TASK AFTER BOLTING: a. DOCUMENT ACCEPTANCE OR REJECTION OF BOLTED CONNECTIONS	PP		AISC 360-10 TABLE N5.6-3

- NOTES:
- QCI = FABRICATORS OR ERECTORS QUALITY CONTROL INSPECTOR RESPONSIBLE FOR WORK PERFORMED IS IN COMPLIANCE WITH THE SHOP DRAWINGS, ERECTION DRAWINGS, REFERENCE SPECIFICATIONS, CODES AND STANDARDS.
 - QAI = THE OWNER'S APPROVED AGENCY'S QUALITY ASSURANCE INSPECTOR (SPECIAL INSPECTOR) RESPONSIBLE FOR INSPECTION OF FABRICATED ITEMS, INSPECTION OF THE ERECTED STEEL SYSTEM, REVIEW TEST REPORTS AND CERTIFICATIONS, ITEMS NOTED IN THE TABLE ABOVE, AND FURNISHES INSPECTIONS, REPORTS, AND NONDESTRUCTIVE TESTING (NDT) REPORTS.
 - O = OBSERVE THESE ITEMS IN A RANDOM BASIS. OPERATIONS NEED NOT BE DELAYED PENDING THESE INSPECTIONS.
 - P = PERFORM THE TASK FOR EACH BOLTED CONNECTION.
 - THE QAI IS NOT REQUIRED TO INSPECT FABRICATED ITEMS IF THE STEEL FABRICATOR IS DEEMED AN APPROVED FABRICATOR.
 - WHERE A TASK IS NOTED TO BE PERFORMED BY BOTH THE QCI AND QAI, IT IS PERMITTED TO COORDINATE THE INSPECTION FUNCTION BETWEEN THE QCI AND QAI SO THAT THE INSPECTION FUNCTION IS PERFORMED BY ONLY ONE PARTY.

VERIFICATION AND INSPECTION OF WIND-RESISTING COMPONENTS				
SPECIAL INSPECTION REQUIRED	VERIFICATION AND INSPECTION TASK	INSPECTION FREQUENCY CONTINUOUS / PERIODIC	REFERENCE STANDARD	IBC REFERENCE
YES	1. ROOF CLADDING	X	-	
YES	2. WALL CLADDING	-	X	1705.10.3

- NOTES:
- PERIODIC SPECIAL INSPECTION OF WIND-RESISTING COMPONENTS IS REQUIRED IF ONE OF THE FOLLOWING CRITERIA IS MET:
a. IN WIND EXPOSURE B, WHERE $V_{ult} \geq 120$ MPH
b. IN WIND EXPOSURE C OR D, WHERE $V_{ult} \geq 110$ MPH

VERIFICATION AND INSPECTION OF SOILS				
SPECIAL INSPECTION REQUIRED	VERIFICATION AND INSPECTION TASK	INSPECTION FREQUENCY CONTINUOUS / PERIODIC	REFERENCE STANDARD	IBC REFERENCE
YES	1. VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY	-	X	-
YES	2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIALS	-	X	-
YES	3. PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS	-	X	-
YES	4. VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL	X	-	-
YES	5. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIALS	-	X	-

- NOTES:
- SPECIAL INSPECTION AND TESTING PROCEDURES OF EXISTING SOIL CONDITIONS, EXCAVATION, FILL, PLACEMENT, AND LOAD-BEARING REQUIREMENTS SHALL BE BASED ON THE APPROVED GEOTECHNICAL REPORT AND THE CONTRACT DOCUMENTS.

VERIFICATION AND INSPECTION OF CONCRETE CONSTRUCTION				
SPECIAL INSPECTION REQUIRED	VERIFICATION AND INSPECTION TASK	INSPECTION FREQUENCY CONTINUOUS / PERIODIC	REFERENCE STANDARD	IBC REFERENCE
YES	1. INSPECTION OF REINFORCING STEEL, INCLUDING PRESTRESSING TENDONS, AND PLACEMENT	-	X	ACI 318, 318.7.1-7.7
YES	2. INSPECTION OF REINFORCING STEEL WELDING IN ACCORDANCE WITH TABLE 1705.2.2, ITEM 2d	-	X	AWS D1.4 ACI 318, 332
YES	3. INSPECTION OF ANCHORS CAST IN CONCRETE WHERE ALLOWABLE LOADS HAVE BEEN INCREASED OR WHERE STRENGTH DESIGN IS USED	-	X	ACI 318, 8.1.3, 21.2.8
YES	4. INSPECTION OF ANCHORS POST-INSTALLED IN HARDEN CONCRETE MEMBERS: a. SPECIAL INSPECTOR CERTIFIED ADHESIVE ANCHOR INSTALLER b. ADHESIVE ANCHOR INSTALLATION REPORT INDICATING CONFORMANCE TO THE MANUFACTURER'S PRINTED (INSTALLATION INSTRUCTIONS (MPI)) c. INSTALLATION OF MECHANICAL ANCHORS d. POST-INSTALLED ANCHOR INSTALLERS CERTIFICATIONS AVAILABLE	X	-	ACI 318, APPENDIX D
YES	5. VERIFYING USE OF REQUIRED DESIGN MIX	-	X	ACI 318, 5.2.4.5.4
YES	6. AT THE TIME FRESH CONCRETE IS SAMPLED TO FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE	X	-	ASTM C172, ASTM C31, ACI 318, 5.8.5.8
YES	7. INSPECTION OF CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES	X	-	ACI 318, 5.9, 5.10
YES	8. INSPECTION FOR MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES	-	X	ACI 318, 5.11.5-13
NO	9. INSPECTION OF PRESTRESSED CONCRETE: a. APPLICATION OF PRESTRESSING FORCES b. GROUTING OF BONDED PRESTRESSING TENDONS IN THE SEISMIC FORCE-RESISTING SYSTEM	X	-	ACI 318, 18.20
YES	10. ERECTION OF PRECAST CONCRETE MEMBERS	-	X	ACI 318, 18.18
NO	11. VERIFICATION OF CAST-IN-PLACE CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS	-	X	ACI 318, 6.2
YES	12. INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED	-	X	ACI 318, 6.1.1

VERIFICATION AND INSPECTION OF STEEL CONSTRUCTION OTHER THAN STRUCTURAL STEEL				
SPECIAL INSPECTION REQUIRED	VERIFICATION AND INSPECTION TASK	SPECIAL INSPECTOR QCI QAI	REFERENCE STANDARD	IBC REFERENCE
YES	1. INSPECTION OR EXECUTION TASKS PRIOR TO DECK PLACEMENT: a. VERIFY COMPLIANCE OF MATERIALS (DECK AND ALL DECK ACCESSORIES) WITH CONSTRUCTION DOCUMENTS, INCLUDING PROFILES, MATERIAL PROPERTIES, AND BASE METAL THICKNESS	PP		SX QAI/QC TABLE 1.1
YES	b. DOCUMENT ACCEPTANCE OR REJECTION OF DECK AND ACCESSORIES DECK	P	P	
YES	2. INSPECTION OR EXECUTION TASKS AFTER DECK PLACEMENT: a. VERIFY COMPLIANCE OF DECK AND ALL ACCESSORIES INSTALLATION WITH CONSTRUCTION DECK DOCUMENTS	P	P	
YES	b. VERIFY DECK MATERIALS ARE REPRESENTED BY THE MILL CERTIFICATIONS THAT COMPLY WITH THE CONSTRUCTION DOCUMENTS	-	P	SX QAI/QC TABLE 1.2
YES	c. DOCUMENT ACCEPTANCE OR REJECTION OF INSTALLATION OF DECK AND DECK ACCESSORIES	P	P	
YES	3. INSPECTION OR EXECUTION TASKS PRIOR TO WELDING: a. WELDING PROCEDURE SPECIFICATIONS (WPS) AVAILABLE	O	O	
YES	b. MANUFACTURER CERTIFICATIONS FOR CONSUMABLES AVAILABLE WELDING	O	O	SX QAI/QC TABLE 1.3
YES	c. MATERIAL IDENTIFICATION (TYPE/GRADE)	O	O	
YES	d. CHECK WELDING EQUIPMENT	O	O	
YES	e. INSPECTION OR EXECUTION TASKS DURING WELDING: a. USE OF QUALIFIED WELDERS	O	O	
YES	b. CONTROL AND HANDLING OF WELDING CONSUMABLES	O	O	SX QAI/QC TABLE 1.4
YES	c. ENVIRONMENTAL CONDITIONS (WIND SPEED, MOISTURE, TEMPERATURE)	O	O	
YES	d. WPS FOLLOWED	O	O	
YES	e. INSPECTION OR EXECUTION TASKS AFTER WELDING: a. VERIFY SIZE AND LOCATION OF WELDS, INCLUDING SUPPORT, SIDE LAP AND PERIMETER WELDS	P	P	SX QAI/QC TABLE 1.5
YES	b. WELDS MEET VISUAL ACCEPTANCE CRITERIA	P	P	
YES	c. VERIFY REPAIR ACTIVITIES	P	P	
YES	d. DOCUMENT ACCEPTANCE OR REJECTION OF WELDS	P	P	
YES	6. INSPECTION OR EXECUTION TASKS PRIOR TO MECHANICAL FASTENING: a. MANUFACTURER INSTALLATION INSTRUCTIONS AVAILABLE FOR MECHANICAL FASTENERS	O	O	SX QAI/QC TABLE 1.6
YES	b. PROPER TOOLS AVAILABLE FOR FASTENER INSTALLATION	O	O	
YES	c. PROPER STORAGE FOR MECHANICAL FASTENERS	O	O	
YES	7. INSPECTION OR EXECUTION TASKS DURING MECHANICAL FASTENING: a. FASTENERS ARE POSITIONED AS REQUIRED	O	O	SX QAI/QC TABLE 1.7
YES	b. FASTENERS ARE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS	O	O	
YES	8. INSPECTION OR EXECUTION TASKS AFTER MECHANICAL FASTENING: a. CHECK SPACING, TYPE, AND INSTALLATION OF SUPPORT FASTENERS	P	P	
YES	b. CHECK SPACING, TYPE, AND INSTALLATION OF SIDE-LAP FASTENERS	P	P	SX QAI/QC TABLE 1.8
YES	c. CHECK SPACING, TYPE, AND INSTALLATION OF PERIMETER FASTENERS	P	P	
YES	d. VERIFY REPAIR ACTIVITIES	P	P	
YES	e. DOCUMENT ACCEPTANCE OR REJECTION OF FASTENERS MECHANICAL	P	P	

- NOTES:
- QCI= INSTALLER'S QUALITY CONTROL INSPECTOR RESPONSIBLE FOR CONFIRMING THAT THE MATERIAL PROVIDED AND WORK PERFORMED MEET THE REQUIREMENTS OF THE CONSTRUCTION DOCUMENTS, INSTALLATION DRAWINGS, SHOP DRAWINGS, DESIGN DOCUMENTS, AND REFERENCE STANDARDS.

QAI= THE OWNER'S APPROVED AGENCY'S QUALITY ASSURANCE INSPECTOR (SPECIAL INSPECTOR) RESPONSIBLE FOR INSPECTION OF MATERIALS, INSTALLATION, FABRICATION, ERECTION OR PLACEMENT OF COMPONENTS AND CONNECTIONS AND CONFIRM COMPLIANCE WITH CONSTRUCTION DOCUMENTS AND REFERENCE STANDARDS.


O= OBSERVE THESE ITEMS ON AN INTERMITTENT BASIS. OPERATIONS NEED NOT BE DELAYED PENDING THESE INSPECTIONS.

P= PERFORM THESE TASKS PRIOR TO FINAL ACCEPTANCE FOR EACH ITEM OR ELEMENT.


- WHERE A TASK IS NOTED TO BE PERFORMED BY BOTH THE QCI AND QAI, IT IS PERMITTED TO COORDINATE THE INSPECTION FUNCTION BETWEEN THE QCI AND QAI SO THAT THE INSPECTION FUNCTION IS PERFORMED BY ONLY ONE PARTY.

PRE-MANUFACTURED SUPERSTRUCTURE :

- DESIGN CRITERIA
INTERNATIONAL BUILDING CODE (IBC) 2021 EDITION
ASCE 7-16
BUILDING CODE FOR THE CITY OF CON EDINBURG, TEXAS
MAXIMUM ALLOWABLE HORIZONTAL DRIFT OF STRUCTURE = H/400
WHERE H = MEAN HEIGHT OF STRUCTURE
DESIGN WIND SPEED = 105 MPH, EXPOSURE "C"
MINIMUM COLLATERAL LOAD = 10 PSF PLUS ROOF TOP UNITS
- A PROFESSIONAL STRUCTURAL ENGINEER REGISTERED IN THE STATE OF TEXAS SHALL BE RESPONSIBLE FOR THE DESIGN OF THE PREFABRICATED METAL BUILDING MEMBERS AND THEIR CONNECTIONS. THIS WORK SHALL ALSO INCLUDE ALL MEMBERS AND BRACES REQUIRED TO BRACE MASONRY WALLS.
- ALL DRAWINGS SHALL BE SEALED BY A PROFESSIONAL ENGINEER AND SHALL BE SUBMITTED FOR RECORD PURPOSES UPON REQUEST.
- THE SUPPLIER SHALL SUBMIT A SEALED LETTER STATING DESIGN CRITERIA FOR ALL WORK AND CERTIFYING THAT ALL DESIGNS ARE IN COMPLIANCE WITH APPLICABLE CODES.
- ALL ANCHOR BOLTS SHALL BE DESIGNED BY THE METAL BUILDING SUPPLIER AND SUPPLIED BY THE CONTRACTOR. ALL ANCHOR BOLTS SHALL CONFORM TO ASTM A36. SUBMIT MILL CERTIFICATES FOR ALL BOLTS. ALL BOLTS FOR STRUCTURAL CONNECTIONS OF BEAMS, COLUMNS, PURLINS, COLUMNS, BRACES, ETC. SHALL BE OF AMERICAN ORIGIN. NO EXCEPTIONS. SUBMIT MILL CERTIFICATES FOR ALL BOLTS.
- ALL A325 BOLTS SHALL BE FULLY TENSIONED USING THE TURN OF THE NUT METHOD.
- PROVIDE PINNED BASE CONNECTION FROM COLUMN TO FOUNDATION.
- ALL BOLTS IN THE METAL BUILDING SHALL BE INSPECTED BY THE TESTING LAB TO CONFIRM PROPER TENSION. THE TESTING LAB SHALL INSPECT EACH AND EVERY BOLT ON THE PROJECT USING A TORQUE WRENCH.
- SUBMIT WRITTEN REPORTS TO THE ARCHITECT.
- THE MANUFACTURER'S ENGINEER MUST PERFORM SITE OBSERVATIONS DURING THE COURSE OF THE METAL BUILDING CONSTRUCTION TO CONFIRM THAT THE WORK IS PROGRESSING IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND SHOP DRAWINGS. THE CONTRACTOR SHALL MAKE ALL NON-COMPLIANT ITEMS ACCEPTABLE TO THE ENGINEER PRIOR TO CONTINUING WITH ANY FINISH WORK. AT THE END OF THE JOB, THE MANUFACTURER'S REGISTERED TEXAS P.E. MUST SUBMIT A SEALED LETTER TO THE OWNER AND ARCHITECT STATING THAT THE DESIGN AND CONSTRUCTION OF THE METAL BUILDING IS IN COMPLIANCE WITH THE CONTRACT DOCUMENTS AND ALL APPLICABLE CODES.
- THIS FOUNDATION HAS BEEN DESIGNED USING ASSUMED REACTIONS FROM THE PRE-ENGINEERED BUILDING COMPONENTS AND IS FOR BID PURPOSES ONLY. THE CONTRACTOR SHALL SUBMIT BASE CONNECTION DETAILS (SIZE AND THICKNESS BASE PLATE AND DIAMETER AND LENGTH ANCHOR BOLTS) AND REACTIONS OF THE BUILDING FRAMES TO THE ENGINEER PRIOR TO CONSTRUCTION SO THE DESIGN ASSUMPTIONS CAN BE VERIFIED. DEPTH OF ANCHOR BOLTS SHALL BE SUFFICIENT.
- ANY ADDITIONAL COST OF FOUNDATION WORK REQUIRED BY REVISIONS OF THE FOUNDATION DESIGN AFTER PRE-ENGINEERED BUILDING REACTIONS ARE SUBMITTED SHALL BE BY OTHERS.



CHLH
ENGINEERING, LLC
TBP# FIRM No. F-8719
701 S. 15th STREET McALLEN, TX. 78501
(956) 687-5560



FOUNDATION NOTES:

- SEE SHEET S1.0, S1.1, S1.2 & S1.3 FOR GENERAL NOTES.
- FOR TYPICAL DETAILS SEE SHEETS SD1.0 & SD1.1
- CONTRACTOR/SUBCONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL DIMENSIONS WITH ARCHITECTURAL PLANS BEFORE COMMENCING ANY WORK. THE CONTRACTOR AND OR SUBCONTRACTOR SHALL REPORT ANY DISCREPANCIES TO THE ARCHITECT AND ENGINEER BEFORE THE WORK HAS BEGUN.
- REFER TO ARCHITECTURAL PLANS FOR ADDITIONAL DIMENSIONS.
- REFER TO ARCHITECTURAL PLANS FOR FLOOR DRAIN LOCATIONS.
- SLOPE SLAB TO DRAINS, SEE ARCHITECTURAL PLANS FOR SLOPE.
- REFER TO ARCHITECTURAL PLANS FOR FLOOR FINISHES. ENGINEER IS NOT RESPONSIBLE FOR TYPE OF FLOOR FINISHES.
- PROVIDE SLAB CONTRACTION JOINTS PER TYPICAL DETAIL.
- THE TESTING LABORATORY SHALL BE THE OWNER REPRESENTATIVE TO CONTROL THE PLACEMENT OF COMPACTED FILL. THE TESTING LABORATORY SHALL APPROVE THE SUBGRADE PREPARATION, THE FILL MATERIALS, THE METHOD OF PLACEMENT AND COMPACTION, AND COMPACTION, AND SHALL INDICATE ON THERE REPORT THE ELEVATION OF THE COMPACTED SUBGRADE.
- ALL EARTHWORK AND GRADING SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEERING STUDY. THE STRINGENT REQUIREMENTS BETWEEN THESE SUBGRADE NOTES AND GEOTECHNICAL ENGINEERING STUDY SHALL GOVERN AND EXECUTED BY THE CONTRACTOR.
- IN THE EVENT FOUNDATION EXCAVATIONS ARE CARRIED TO A DEPTH GREATER THAN REQUIRED, THE ADDITIONAL DEPTH SHALL BE FILLED WITH THE SAME CONCRETE AS THAT USED FOR FOOTING AT NO ADDITIONAL EXPENSE TO THE OWNER. NO UNCONTROLLED FILL WILL BE PERMITTED.
- THE FOOTING EXCAVATIONS SHALL BE KEPT FREE FROM LOOSE MATERIAL AND STANDING WATER.
- THE FOUNDATION EXCAVATIONS SHOULD BE OBSERVED BY THE TESTING LABORATORY PRIOR TO STEEL OR CONCRETE PLACEMENT TO ASSESS THAT THE FOUNDATION MATERIALS ARE CAPABLE OF SUPPORTING THE DESIGN LOADS AND ARE CONSISTENT WITH THE MATERIALS DISCUSSED IN THE STUDY. THIS IS ESPECIALLY IMPORTANT TO IDENTIFY THE ACCEPTABILITY OF THE SUBGRADE OR FILL MATERIAL UNDER THE FOOTING. SOFT OR LOOSE SOIL ZONES ENCOUNTERED AT THE BOTTOM OF THE FOOTING OR BEAM EXCAVATIONS SHOULD BE EXCAVATIONS SHOULD BE REMOVED TO THE LEVEL OF COMPETENT SOIL AS DIRECTED BY THE TESTING LABORATORY. CAVITIES FORMED AS A RESULT OF EXCAVATION OF SOFT OR LOOSE SOIL ZONES SHOULD BE BACKFILLED WITH LEAN CONCRETE OR SELECT FILL AS DETERMINED BY THE TESTING LABORATORY.
- CARE SHOULD BE TAKEN TO SHAPE THE BUILDING AREAS SUCH THAT WATER WILL NOT POND AROUND THE STRUCTURE DURING CONSTRUCTION AND CAUSE THE NEAR SURFACE CLAYS TO SWELL. THE PROPOSED STRUCTURE SHALL BE ISOLATED FROM ANY MOISTURE SOURCE WHICH MIGHT ALSO CAUSE SWELLING OF THE CLAYS AFTER COMPLETION OF THE CONSTRUCTION.
- WHEN THE STRUCTURE IS COMPLETE, THE GROUND SURFACE SHOULD SLOPE AWAY FROM THE STRUCTURE AND DOWN SPOUTS SHOULD CARRY RUNOFF WATER SEVERAL FEET FROM THE BUILDING, PREFERABLY INTO PAVED AREAS OR SEWERS, BEFORE DISCHARGING.
- DO NOT PLANT, OR LEAVE IN PLACE, DEEP ROOTED TREES WITHIN CLOSE PROXIMITY TO THE PERIMETER OF THE STRUCTURE. DEEP ROOTED TREES HAVE POTENTIAL TO REMOVE MOISTURE FROM BENEATH THE BUILDING IF PLANTED CLOSE ENOUGH TO ALLOW THE ROOT BULB EXTEND NEAR OR BENEATH THE BUILDING.
- AIR CONDITIONING CONDENSER DRAIN LINES TO DISCHARGE WATER A MINIMUM OF 5 FEET FROM THE PERIMETER OF THE STRUCTURE. THE DISCHARGE AREA SHALL HAVE SUFFICIENT SLOPE AWAY FROM THE STRUCTURE TO PREVENT STANDING WATER.
- THE FINAL ONE (1) FOOT OF FILL OUTSIDE THE BUILDING AREA SHOULD CONSIST OF A COHESIVE CLAYEY (CL) SOIL. FILL CAN NOT BE ALLOWED TO DRY OUT DURING OR AFTER COMPACTION.
- NOTE THAT SOME LEVELS OF RISK ARE ASSOCIATED WITH ALL FOUNDATION SYSTEMS AND THERE IS NO SUCH THING AS A "ZERO RISK" FOUNDATION. IT ALSO SHOULD BE NOTED THAT THE FOUNDATION PROVIDED IS NOT DESIGNED TO RESIST SOIL MOVEMENT AS A RESULT OF SEWER/PLUMBING LEAKS, EXCESSIVE IRRIGATION, NON UNIFORM IRRIGATION, POOR DRAINAGE, AND WATER PONDING NEAR THE FOUNDATION SYSTEM.
- CONSTRUCTION FOLLOWING WET WEATHER PERIODS WILL LIKELY ENCOUNTER DIFFICULTIES DUE TO THE WET OR SOFT SURFACE SOILS BECOMING A GENERAL HINDRANCE TO EQUIPMENT DUE TO RUTTING AND PUMPING OF THE SOIL SURFACE. IF THE SUBGRADE CANNOT BE ADEQUATELY COMPACTED TO MINIMUM DENSITIES AS DESCRIBED ABOVE, ONE OF THE FOLLOWING MEASURES WILL BE REQUIRED:
 - REMOVAL AND REPLACEMENT WITH SELECT FILL
 - CHEMICAL TREATMENT OF THE SOIL TO DRY SOIL AND INCREASE THE STABILITY OF THE SUBGRADE
 - DRYING BY NATURAL MEANS.
- ALL FOOTINGS TO HAVE #5s AT 12" O.C. EACH WAY TOP AND BOTTOM REINFORCING.
- FOLLOWING ARE THE SIZES OF THE REQUIRED FOOTINGS:
 - INDICATES A 5'-6" x 5'-6" x 3'-0" DEEP CEE FOOTING
 - INDICATES A 6'-6" x 6'-6" x 3'-0" DEEP TEE FOOTING

SLAB ON GRADE	
THICKNESS	5 INCHES
REINFORCING (EACH WAY)	#4 AT 14" O.C.
REINFORCING LOCATION	MID DEPTH
VISQUEEN	15 MIL
CONCRETE CHAIRS (NOT PLASTIC CHAIRS ALLOWED)	3'-0" O.C. EACH WAY

1 FOUNDATION PLAN
SCALE: 3/16"=1'-0"



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542


CLIENT:
EDINBURG CISD

No.	Description	Date

PROJECT #:
DRAWN BY:
CHECKED BY:
DATE: 4/28/25

FOUNDATION
PLAN

S2.0



CHLH
ENGINEERING, LLC
TBPE FIRM No. F-8719
701 S. 15th STREET McALLEN, TX. 78501
(956) 687-5560



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date


PROJECT #:
DRAWN BY:
CHECKED BY:
DATE: 4/28/25

ROOF
FRAMING
PLAN


S3.0

METAL BUILDING NOTES:

1. THE DESIGN AND CONSTRUCTION OF THE METAL BUILDING IS THE RESPONSIBILITY OF THE SUPPLIER. THE PLAN SHOWN IS SCHEMATIC ONLY.
2. VERIFY SIZE AND LOCATION OF ALL SUPPORTED ITEMS WITH MANUFACTURER AND ARCH'L DRAWINGS. PRIOR TO FABRICATING STEEL. PROVIDE ALL FRAMING INCLUDING SUB PURLINS AND ROD HANGERS BETWEEN '2" PURLINS AS REQ'D.
3. THE CONTRACTOR SHALL VERIFY THE SIZE, LOCATION AND NUMBER OF MECH'L UNITS SUPPORTED BY THE METAL BUILDING STRUCTURE PRIOR TO ORDERING THE METAL BUILDING. SUPPORT FRAMING SHALL BE PROVIDED FOR ALL UNITS WHETHER THEY ARE SHOWN ON THIS DRAWING OR NOT.



1 ROOF FRAMING PLAN
SCALE: 3/16"=1'-0"



CHLH
ENGINEERING, LLC
TBPE FIRM No. F-8719
701 S. 15th STREET MCALLEN, TX. 78501
(956) 687-5560



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL


2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #:
DRAWN BY:
CHECKED BY:
DATE: 4/28/25

ALTERNATE
ROOF
FRAMING
PLAN
ALTERNATE
S3.1




CHLH
ENGINEERING, LLC
TBPE FIRM No. F-8719
701 S. 15th STREET McALLEN, TX. 78501
(956) 687-5560


METAL BUILDING NOTES:

1. THE DESIGN AND CONSTRUCTION OF THE METAL BUILDING IS THE RESPONSIBILITY OF THE SUPPLIER. THE PLAN SHOWN IS SCHEMATIC ONLY.
2. VERIFY SIZE AND LOCATION OF ALL SUPPORTED ITEMS WITH MANUFACTURER AND ARCH'L DRAWINGS. PRIOR TO FABRICATING STEEL, PROVIDE ALL FRAMING INCLUDING SUB PURLINS AND ROD HANGERS BETWEEN "Z" PURLINS AS REQ'D.
3. THE CONTRACTOR SHALL VERIFY THE SIZE, LOCATION AND NUMBER OF MECH'L UNITS SUPPORTED BY THE METAL BUILDING STRUCTURE PRIOR TO ORDERING THE METAL BUILDING. SUPPORT FRAMING SHALL BE PROVIDED FOR ALL UNITS WHETHER THEY ARE SHOWN ON THIS DRAWING OR NOT.


1 ALTERNATE
ROOF FRAMING PLAN
SCALE: 3/16"=1'-0"




1 EXTERIOR GRADE BEAM
SCALE: NOT TO SCALE




2 INTERIOR GRADE BEAM
SCALE: NOT TO SCALE




3 FOOTING AT COLUMN
SCALE: NOT TO SCALE




4 PLAN VIEW, TRUST BARS
SCALE: NOT TO SCALE




5 PLAN VIEW
SCALE: NOT TO SCALE




6 PLAN VIEW
SCALE: NOT TO SCALE



7 CONSTRUCTION / CONTRACTION JOINT
SCALE: NOT TO SCALE





8 CONTROL JOINT
SCALE: NOT TO SCALE



9 STANDARD HOOKS
SCALE: NOT TO SCALE


DIAMETER OF BENDS	
STIRRUPS AND TIES	4 db FOR #3 THRU #5 BARS
	6 db FOR #6 THRU #8 BARS
ALL OTHERS	6 db FOR #3 THRU #8 BARS
	8 db FOR #9 THRU #11 BARS
	10 db FOR #14 THRU #18 BARS




10 TYP. REINF. @ INT. OF CONC. FTG'S.
SCALE: NOT TO SCALE

FOOTING SCHEDULE					
TYPE	A	B	C	D	REINFORCING
C5		5'-6"	5'-6"	3'-0"	#5'S @ 12" O.C. E.W. TOP & BOT.
T6		6'-6"	6'-6"	3'-0"	#5'S @ 12" O.C. E.W. TOP & BOT.

- NOTES: 1. D = FOOTING DEPTH BELOW FINISH FLOOR
2. FOOTING DIMENSIONS ARE FOR BIDDING PURPOSES ONLY. ACTUAL DIMENSIONS MAY VARY.
3. PROVIDE UNIT PRICES (ON A CUBIC YARD BASIS) FOR REINFORCED (#6'S @ 8" OC EW TOP & BOT.) WIDENED BEAM CONCRETE FOOTINGS



11 FOOTING AT COLUMN
SCALE: NOT TO SCALE



CHLH
ENGINEERING, LLC
TBE FIRM No. F-8719
701 S. 15th STREET McALLEN, TX. 78501
(956) 687-5560



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542




CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #:
DRAWN BY:
CHECKED BY:
DATE: 4/28/25

FOUNDATION
DETAILS

SD1.0



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542


CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #:
DRAWN BY:
CHECKED BY:
DATE: 4/28/25

FRAMING
DETAILS



SD2.0




CHLH
ENGINEERING, LLC
TBPE FIRM No. F-8719
701 S. 15th STREET McALLEN, TX. 78501
(956) 687-5560



2 ENLARGE SITE PLAN
3/64" = 1'-0"



1 SITE PLAN
1" = 300'-0"



4 ENLARGE SITE DEMOLITION PLAN
A3.0 1" = 40'-0"

GENERAL NOTES:

1. OWNER WILL PROVIDE SOILS TESTS PRIOR TO FOUNDATION WORKS.
2. PROVIDE SIDEWALK AS PART OF BASE BID.
3. FOR UTILITIES, RE: MEP & CIVIL
4. WARNING:
CONTACT AEP FOR ELECTRICAL SERV. & CITY OF EDINBURG FOR WATER & SEWER UTILITIES.
CONTRACTOR TO VERIFY EXISTING UTILITIES
5. ALL CONSTRUCTION AND MATERIALS FOR DRAINAGE, GRADING AND PAVING TO BE IN ACCORD WITH "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION".
6. CONTRACTOR IS RESPONSIBLE FOR ALL HORIZONTAL AND VERTICAL CONTROL FOR CONSTRUCTION.
7. CONTRACTOR IS RESPONSIBLE FOR PAYING ANY FEES FOR PERMITS AS REQUIRED FOR THIS CONSTRUCTION
8. CONTRACTOR TO SET CONTROL GRADES AT 25' INTERVALS ALONG ALL PAVING FLOW LINES
9. ANY DAMAGE TO EXISTING UTILITIES BY CONTRACTOR TO BE FIXED
10. PROVIDE JOB SIGN RE:
11. ALL SOIL PLACED ONTO SITE IS TO BE COMPACTED TO 80% DENSITY, EXCEPT UNDER ANY PAVING COMPACTION IS TO BE 95%, U.N.O.
12. ALL PIPES SLEEVES SHALL BE SCH 40 PVC. AND FURNISHED IN PLACE BY THE CONTRACTOR BEFORE PAVING.
13. 6" CONC. CURB & 12" GUTTER
14. CONTRACTOR TO PROVIDE A STAGING AREA TO PROVIDE FENCING FOR CONSTRUCTION AREA

SITE NOTES:

1. MAXIMUM SLOPE AT SIDEWALK IS NOT TO EXCEED 1:20 (5%) ALONGSIDE AND 1:50 (2%) ACROSS.
2. SITE DRAINAGE SHALL NOT BE DIRECTED TOWARD ADJACENT PROPERTIES.
3. BUILDING PAD ELEVATION TO BE SET BASED ON THE AREA SURVEY AND THE APPLICABLE FLOOD ZONE.
4. VERIFY LOCATION OF SITE IMPROVEMENTS IN RELATION TO BUILDING, PROPERTIES TO BUILDING, PROPERTY LINES AND EASEMENTS.

ADA NOTES:

1. ALL SIDEWALKS AND COVERED WALKWAYS SHALL HAVE 1:50 MAXIMUM CROSS SLOPE SIDEWALKS OR COVERED WALKWAYS THAT MUST HAVE SLOPES GREATER THAN 1:20 SHALL HAVE HANDRAILS ON BOTH SIDES. HANDRAILS SHALL BE 34" TO TOP A.F.F. THERE SHALL BE NO ABRUPT CHANGE IN ELEVATION ALONG ACCESSIBLE ROUTES AT SIDEWALKS AND COVERED WALKWAYS.
2. CURB RAMP SLOPE SHALL BE 1:20 MAXIMUM WITH 1:10 FLARED SIDES AND SHALL BE TEXTURED. PAINT WITH A LIGHT REFLECTIVE PAINT. PARALLEL CURB RAMP SLOPE SHALL BE 1:12 MAXIMUM & TEXTURED. PAINT WITH A LIGHT REFLECTIVE PAINT. ALL CURB RAMP HAVE A LANDING AT TOP & BOTTOM. LANDINGS SHALL HAVE A 1:50 MAXIMUM SLOPE IN ANY DIRECTION.
3. STRIPED ACCESS AISLES AND ACCESSIBLE PARKING SHALL HAVE A MAXIMUM CROSS SLOPE IN ALL DIRECTIONS OF 1:50. ALL GRADING SHALL BE DONE TO DRAIN WATER AWAY FROM BUILDINGS.
4. ALL EXTERIOR ALCOVES SHALL HAVE A 1:50 MAXIMUM SLOPE AND SHALL HAVE NO DROPS AT DOORS NOR AT CONNECTION SIDEWALKS.
5. REFER TO CIVIL DRAWINGS. CONTRACTOR IS RESPONSIBLE FOR CONTRACTING ARCHITECT IN CASE OF DISCREPANCIES AND COORDINATING WITH CIVIL ENGINEER PRIOR TO PROCEEDING.
6. ALL EXTERIOR DOORS SHALL HAVE A LEVEL AREA IN FRONT OF THE DOOR WITH A 1:50 MAXIMUM SLOPE IN ALL DIRECTIONS. THE AREA SHALL BE A MINIMUM OF 5 FT. IN THE DIRECTIONS OF TRAVEL BY THE WIDTH OF THE SIDEWALK.
- 7.



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CGSARCHITECT.COM

SEAL:



EDINBURG HIGH
SCHOOL
ECISD HIGH
SCHOOL
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:

ECISD


REVISION:

No.	Description	Date

PROJECT #: 25-030101
DRAWN BY: D.L.
CHECKED BY: CG3
DATE: Issue Date

SITE PLAN

A0.1



KEY NOTES:

- 3 5/8" METAL STUD FURRING WALL WITH 1/2" T1-11 PANEL OR EQUAL PLYWOOD SHEATHING TO 8'-0" AFF TYPICAL, PAINTED, PROVIDE CAP AT TOP OF FURRING WALL
- WRESTLING MAT ACCORDING TO NCAA REGULATIONS 42' X 42', BY OWNER
- CONCRETE SPLASH BLOCKS


ROOM SCHEDULE					
ROOM NAME	FLOOR FINISH	BASE FINISH	WALL FINISH	CEILING FINISH	COMMENTS
MULTIPURPOSE AREA	F-1	B-1	W-1	C-1	

ROOM FINISH SCHEDULE: BASIS OF DESIGN OR EQUAL

- FLOOR:** F-1 SEALED CONCRETE FLOOR, TRANSPARENT
- BASE:** B-1 4" RUBBER BASE, ROPPE 700 SERIES 4" THERMOPLASTIC RUBBER WALL COVE BASE
- WALL:** W-1 T1-11 PANEL OR EQUAL PLYWOOD SHEATHING TO 8'-0" AFF TYPICAL, PAINTED, FINAL COLOR SELECTED BY OWNER
- CEILING:** C-1 OPEN STRUCTURE, ONLY STRUCTURAL FRAME PAINTED

FLOOR PLAN GENERAL NOTES


- THE CONTRACTOR SHALL CAREFULLY REVIEW THE DRAWINGS, SPECIFICATIONS, DIMENSIONS AND SITE CONDITIONS PRIOR TO BEGINNING ANY WORK AND REPORT ANY INCONSISTENCIES OR DISCREPANCIES TO THE ARCHITECT IMMEDIATELY FOR RESOLUTION DURING THE Q&A PERIOD OF THE BID PHASE, AND AT THE LATEST BEFORE BEGINNING CONSTRUCTION.
- THE DRAWINGS AND SPECIFICATIONS ARE CORRELATIVE AND HAVE EQUAL AUTHORITY AND PRIORITY. BASE DISAGREEMENTS IN THEMSELVES OR IN EACH OTHER ON THE MOST EXPENSIVE COMBINATION OF QUANTITY AND QUALITY OF WORK INDICATED.
- ITEMS SPECIFICALLY MENTIONED IN THE SPECIFICATIONS BUT NOT SHOWN ON THE DRAWINGS OR ITEMS SHOWN ON THE DRAWINGS BUT NOT SPECIFICALLY MENTIONED IN THE SPECIFICATIONS SHALL BE PROVIDED AS IF THEY WERE BOTH SPECIFIED AND SHOWN IN THE DRAWINGS.
- ALL MINOR DETAILS OF WORK WHICH ARE NOT SPECIFICALLY SHOWN ON THE DRAWINGS, AS WELL AS SUCH ITEMS WHICH ARE NOT SPECIFICALLY MENTIONED IN THE SPECIFICATIONS, BUT ARE NECESSARY FOR THE PROPER COMPLETION OF THE WORK, SHALL BE CONSIDERED AS INCIDENTAL AND AS BEING PART OF AND INCLUDED WITH THE WORK FOR WHICH PRICES ARE GIVEN IN THE PROPOSAL AND NO EXTRA COMPENSATION SHALL BE ALLOWED FOR THE PERFORMANCE THEREOF.
- ALL FLOOR PLAN DIMENSIONS ARE TO FINISH FACE OF WALL. DO NOT SCALE DRAWINGS. WHERE DIMENSIONS ARE NOTED "AS CLEAR" DIMENSION SHALL BE FROM FINISH TO FINISH.
- CASEWORK, PLUMBING FIXTURES, TOILET PARTITIONS, AND OTHER FIXTURES AND EQUIPMENT ARE DIMENSIONED FROM FINISHED SURFACES UNLESS NOTED OTHERWISE.
- ALL SPACES WITH FLOOR DRAINS - SLOPE NOT TO EXCEED 2% (ONE - IN - FIFTY) IN ANY DIRECTION. COORDINATE ALL FLOOR DRAINS WITH PLUMBING DRAWINGS PRIOR TO ANY ROUGH-IN AND CONCRETE PLACEMENT.
- DIMENSIONS NOTED AS "FIELD VERIFY" SHALL BE CHECKED AT THE SITE BY THE CONTRACTOR AND REVIEWED WITH THE ARCHITECT BEFORE INCORPORATING INTO THE WORK.
- DIMENSIONS NOTED AS "CLEAR" REQUIRE SPECIFIC COORDINATION BETWEEN DISCIPLINES AND/OR MANUFACTURERS.
- ALL FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. ALL FLOOR FINISH ELEVATION CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS AS SPECIFIED.
- OPEN EXTERIOR JOINTS AROUND DOOR AND WINDOW FRAMES, BETWEEN WALLS AND FOUNDATION, BETWEEN WALLS AND ROOF, BETWEEN WALL PANELS, AT WALL AND ROOF PENETRATIONS AND ANY OTHER BUILDING ENVELOPE PENETRATION SHALL BE SEALED, CAULKED AND/OR WEATHER-STRIPPED TO PREVENT OR LIMIT AIR, MOISTURE AND VAPOR PENETRATION. USE ONLY SPECIFIED MANUFACTURER APPROVED MATERIALS AS DIRECTED BY MATERIAL MANUFACTURERS.
- EFFECTIVELY ISOLATE ALL DISSIMILAR METALS/ MATERIALS TO PREVENT CORROSION BY ELECTROLYTIC ACTION OR OTHER CAUSES AS RECOMMENDED BY THE RESPECTIVE PRODUCT MANUFACTURER OR SUPPLIER.
- PROPERLY TERMINATE ALL MATERIALS WITH APPROPRIATE TRIM, FLASHING, SEALANT, EXPANSION CONTROL, ETC. AS INDICATED ON DRAWINGS OR AS REQUIRED FOR PROPER INSTALLATION AS ACCEPTED BY STANDARD BUILDING PRACTICE.
- COORDINATE AND PROVIDE APPROPRIATE BLOCKING IN WALLS AS REQUIRED TO SECURE ALL EQUIPMENT, HANDRAILS, CASEWORK, ETC. AS REQUIRED. WOOD BLOCKING SHALL MEET CODE REQUIREMENTS.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR CEILING TYPES AND HEIGHTS. COORDINATE ALL LIGHT FIXTURES, MECHANICAL DIFFUSERS, NOTIFICATION DEVICES, ETC. WITH M.E.P. DRAWINGS. NOTIFY ARCHITECT OF ANY DISCREPANCIES FOR RESOLUTION.
- COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. ALL HOUSEKEEPING PADS SHALL BE A MINIMUM OF 4" TALL REINF. W/ #3 BARS AT 15" O.C.B.W. AND PROVIDE 1" (45- DEGREE) CHAMFERED EDGES UNLESS NOTED OTHERWISE.
- ALL INTERIOR DOORS IN STUD WALL ASSEMBLIES SHALL BE SET A MINIMUM OF 4" OFF THE PERPENDICULAR ADJACENT WALL ON THE HINGE SIDE OF THE DOOR UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY CONFLICTS FOR RESOLUTION.
- SET ALL EXTERIOR DOOR THRESHOLDS IN FULL BED OF MANUFACTURER APPROVED SEALANT IN ACCORDANCE WITH MANUFACTURER INSTALLATION INSTRUCTIONS.
- REFER TO CODES AND CONVENTIONS SHEET FOR MOUNTING HEIGHTS OF FIXTURES AND EQUIPMENT AS SCHEDULED. REFER TO THE TEXAS DEPARTMENT OF LICENSING AND REGULATIONS, ARCHITECTURAL BARRIERS DIVISION TEXAS ACCESSIBILITY STANDARDS FOR ALL MOUNTING HEIGHTS NOT LISTED AND FOR FURTHER CLARIFICATION AS NEEDED.
- PROVIDE ROOM SIGNAGE AND DIRECTIONAL SIGNAGE AS PART OF BASE BID. REFER TO THE TEXAS DEPARTMENT OF LICENSING AND REGULATIONS, ARCHITECTURAL BARRIERS DIVISION TEXAS ACCESSIBILITY STANDARDS FOR ALL MOUNTING HEIGHTS NOT LISTED AND FOR FURTHER CLARIFICATION AS NEEDED.



1 LEVEL 1 FLOOR PLAN
3/16" = 1'-0"



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM



**ECISD HIGH SCHOOL
ATHLETIC MULTI-USE
BUILDING
ECISD CSP 25-74**

**EDINBURG
HIGH SCHOOL**

2600 E
Wisconsin Rd,
Edinburg, TX
78542


CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

**FLOOR PLAN
BASE BID**

A2.0



- KEY NOTES:**
- A CONCRETE FLAT WORK FLOOR AT CANOPY EXTENSION (ALTERNATE #2)
 - B 12' HIGH CHAIN LINK FENCE AT CANOPY EXTENSION (ALTERNATE #3)
 - C 8' HIGH CHAIN LINK DOUBLE SWING GATE AT CANOPY EXTENSION (ALTERNATE #3) REFER TO SHEET A7.0

- FLOOR PLAN GENERAL NOTES**
- THE CONTRACTOR SHALL CAREFULLY REVIEW THE DRAWINGS, SPECIFICATIONS, DIMENSIONS AND SITE CONDITIONS PRIOR TO BEGINNING ANY WORK AND REPORT ANY INCONSISTENCIES OR DISCREPANCIES TO THE ARCHITECT IMMEDIATELY FOR RESOLUTION DURING THE Q&A PERIOD OF THE BID PHASE, AND AT THE LATEST BEFORE BEGINNING CONSTRUCTION.
 - THE DRAWINGS AND SPECIFICATIONS ARE CORRELATIVE AND HAVE EQUAL AUTHORITY AND PRIORITY. BASE DISAGREEMENTS IN THEMSELVES OR IN EACH OTHER ON THE MOST EXPENSIVE COMBINATION OF QUANTITY AND QUALITY OF WORK INDICATED.
 - ITEMS SPECIFICALLY MENTIONED IN THE SPECIFICATIONS BUT NOT SHOWN ON THE DRAWINGS OR ITEMS SHOWN ON THE DRAWINGS BUT NOT SPECIFICALLY MENTIONED IN THE SPECIFICATIONS SHALL BE PROVIDED AS IF THEY WERE BOTH SPECIFIED AND SHOWN IN THE DRAWINGS.
 - ALL MINOR DETAILS OF WORK WHICH ARE NOT SPECIFICALLY SHOWN ON THE DRAWINGS, AS WELL AS SUCH ITEMS WHICH ARE NOT SPECIFICALLY MENTIONED IN THE SPECIFICATIONS, BUT ARE NECESSARY FOR THE PROPER COMPLETION OF THE WORK, SHALL BE CONSIDERED AS INCIDENTAL AND AS BEING PART OF AND INCLUDED WITH THE WORK FOR WHICH PRICES ARE GIVEN IN THE PROPOSAL AND NO EXTRA COMPENSATION SHALL BE ALLOWED FOR THE PERFORMANCE THEREOF.
 - ALL FLOOR PLAN DIMENSIONS ARE TO FINISH FACE OF WALL. DO NOT SCALE DRAWINGS. WHERE DIMENSIONS ARE NOTED "AS CLEAR" DIMENSION SHALL BE FROM FINISH TO FINISH.
 - CASEWORK, PLUMBING FIXTURES, TOILET PARTITIONS, AND OTHER FIXTURES AND EQUIPMENT ARE DIMENSIONED FROM FINISHED SURFACES UNLESS NOTED OTHERWISE.
 - ALL SPACES WITH FLOOR DRAINS - SLOPE NOT TO EXCEED 2% (ONE - IN - FIFTY) IN ANY DIRECTION. COORDINATE ALL FLOOR DRAINS WITH PLUMBING DRAWINGS PRIOR TO ANY ROUGH-IN AND CONCRETE PLACEMENT.
 - DIMENSIONS NOTED AS "FIELD VERIFY" SHALL BE CHECKED AT THE SITE BY THE CONTRACTOR AND REVIEWED WITH THE ARCHITECT BEFORE INCORPORATING INTO THE WORK.
 - DIMENSIONS NOTED AS "CLEAR" REQUIRE SPECIFIC COORDINATION BETWEEN DISCIPLINES AND/OR MANUFACTURERS.
 - ALL FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. ALL FLOOR FINISH ELEVATION CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS AS SPECIFIED.
 - OPEN EXTERIOR JOINTS AROUND DOOR AND WINDOW FRAMES, BETWEEN WALLS AND FOUNDATION, BETWEEN WALLS AND ROOF, BETWEEN WALL PANELS, AT WALL AND ROOF PENETRATIONS AND ANY OTHER BUILDING ENVELOPE PENETRATION SHALL BE SEALED, CAULKED AND/OR WEATHER-STRIPPED TO PREVENT OR LIMIT AIR, MOISTURE AND VAPOR PENETRATION. USE ONLY SPECIFIED MANUFACTURER APPROVED MATERIALS AS DIRECTED BY MATERIAL MANUFACTURERS.
 - EFFECTIVELY ISOLATE ALL DISSIMILAR METALS/ MATERIALS TO PREVENT CORROSION BY ELECTROLYTIC ACTION OR OTHER CAUSES AS RECOMMENDED BY THE RESPECTIVE PRODUCT MANUFACTURER OR SUPPLIER.
 - PROPERLY TERMINATE ALL MATERIALS WITH APPROPRIATE TRIM, FLASHING, SEALANT, EXPANSION CONTROL, ETC. AS INDICATED ON DRAWINGS OR AS REQUIRED FOR PROPER INSTALLATION AS ACCEPTED BY STANDARD BUILDING PRACTICE.
 - COORDINATE AND PROVIDE APPROPRIATE BLOCKING IN WALLS AS REQUIRED TO SECURE ALL EQUIPMENT, HANDRAILS, CASEWORK, ETC. AS REQUIRED. WOOD BLOCKING SHALL MEET CODE REQUIREMENTS.
 - REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR CEILING TYPES AND HEIGHTS. COORDINATE ALL LIGHT FIXTURES, MECHANICAL DIFFUSERS, NOTIFICATION DEVICES, ETC. WITH M.E.P. DRAWINGS. NOTIFY ARCHITECT OF ANY DISCREPANCIES FOR RESOLUTION.
 - COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. ALL HOUSEKEEPING PADS SHALL BE A MINIMUM OF 4' TALL REINF. W/ #3 BARS AT 15" O.C.B.W. AND PROVIDE 1" (45- DEGREE) CHAMFERED EDGES UNLESS NOTED OTHERWISE.
 - ALL INTERIOR DOORS IN STUD WALL ASSEMBLIES SHALL BE SET A MINIMUM OF 4" OFF THE PERPENDICULAR ADJACENT WALL ON THE HINGE SIDE OF THE DOOR UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY CONFLICTS FOR RESOLUTION.
 - SET ALL EXTERIOR DOOR THRESHOLDS IN FULL BED OF MANUFACTURER APPROVED SEALANT IN ACCORDANCE WITH MANUFACTURER INSTALLATION INSTRUCTIONS.
 - REFER TO CODES AND CONVENTIONS SHEET FOR MOUNTING HEIGHTS OF FIXTURES AND EQUIPMENT AS SCHEDULED. REFER TO THE TEXAS DEPARTMENT OF LICENSING AND REGULATIONS, ARCHITECTURAL BARRIERS DIVISION TEXAS ACCESSIBILITY STANDARDS FOR ALL MOUNTING HEIGHTS NOT LISTED AND FOR FURTHER CLARIFICATION AS NEEDED.
 - PROVIDE ROOM SIGNAGE AND DIRECTIONAL SIGNAGE AS PART OF BASE BID. REFER TO THE TEXAS DEPARTMENT OF LICENSING AND REGULATIONS, ARCHITECTURAL BARRIERS DIVISION TEXAS ACCESSIBILITY STANDARDS FOR ALL MOUNTING HEIGHTS NOT LISTED AND FOR FURTHER CLARIFICATION AS NEEDED.

1
A3.0


LEVEL 1 FLOOR PLAN
ALTERNATE

3/16" = 1'-0"

N
←



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM



ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:



No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25


FLOOR PLAN
ALTERNATE

A2.0A


1. **WALL:** MBCI, PBU, FINAL COLOR SELECTION BY OWNER
SMOOTH, 24 GAUGE.
2. **ROOF:** MBCI, PBU, FINAL COLOR SELECTION BY OWNER
SMOOTH, 24 GAUGE.



1. PROVIDE ALL REQUIRED UTILITY / STRUCTURAL COMPONENTS AND/OR CONNECTIONS FOR THE FUNCTIONAL USE OF ALL CONTRACTOR SUPPLIED EQUIPMENT OR APPLIANCES, REGARDLESS OF ANY OMISSIONS OR INCONSISTENCIES ENCOUNTERED IN THE CONSTRUCTION DOCUMENTS.
2. THE WORD 'PROVIDE' SHALL MEAN 'FURNISH AND INSTALL COMPLETE AND READY TO USE.'
3. IF DISCREPANCIES APPEAR BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER QUALITY, QUANTITY, AND PRICE SHALL SUPERSEDE.
4. THE GENERAL CONTRACTOR AND SUBCONTRACTORS SHALL BECOME FAMILIAR WITH THE PROJECT AND THE ON-SITE / OFF-SITE CONDITIONS PRIOR TO BIDDING OR COMMENCING WORK.
5. ROOF SLOPES SHOWN ON DRAWING ARE GENERAL AND CONCEPTUAL ONLY. PROVIDE POSITIVE DRAINAGE TO ALL GUTTERS. VERIFY IN SHOP DRAWINGS. REFER TO STRUCTURAL DOCUMENTS FOR EXACT TOS/BOD ELEVATIONS.
6. PROVIDE CRICKETS (1/2" FT. MIN. SLOPE) AT HIGH SIDE OF ALL MECHANICAL UNITS SMOKE VENTS, EXHAUST FANS & OTHER MISC. ROOF PENETRATIONS. TO SHED WATER AROUND & TO ENSURE POSITIVE ROOF DRAINAGE.
7. ALL EXPOSED FLASHING, COPING (IF APPLICABLE) AND THEIR ACCESSORIES SHALL BE AS SPECIFIED. PAINT ALL METAL FLASHING THAT IS NOT PRE-FINISHED (TYP) AND VISIBLE FROM THE GROUND.
8. ALL PITCH PANS SHALL BE SOLDERED CLAD METAL AND RECEIVE EITHER MECHANICAL OR ATTACHED GOOSENECK OR METAL BONNETS. METAL BONNETS SHALL BE SECURED WITH CLAMPING RING AND SEALANT. SPECIAL CARE GIVEN TO WASH ALL METAL PRIOR TO INSTALLATION.
9. PROVIDE NEW CONCRETE SPLASH BLOCKS AT ALL DOWNSPOUT DISCHARGE LOCATIONS.
10. ALL EQUIPMENT CURBS TO BE SET OR RAISED AS NECESSARY TO MAINTAIN 10" MINIMUM HEIGHT ABOVE FINISHED ROOF SURFACE.
11. MECHANICAL, ELECTRICAL, AND PLUMBING ROOF EQUIPMENT SHOWN ON THIS PLAN IS FOR GENERAL ARCHITECTURAL INFORMATION ONLY. REFER TO M.E.P. DOCUMENTS FOR ROOFTOP EQUIPMENT NOT SHOWN, AND FOR ADDITIONAL REQUIREMENTS AND COORDINATION.
12. REFER TO M.E.P. DOCUMENTS FOR THE PIPE SUPPORT LOCATIONS, TYPE, AND DETAILS. PAD SHALL BE MIN 2" WIDER THAN SUPPORT IN ALL DIRECTIONS.
13. GUTTERS SHALL BE PRE-FINISHED GALVANIZED STEEL, SIZE PER ROOF PLAN. UNO. PROVIDE PRE-FINISHED 1/4"x1 1/2" GALVANIZED STEEL BENT PLATE BRACKETS AND PRE-FINISHED 1" GALVANIZED STEEL SPACERS AT 36" O.C. MAX. STAGGER WITH EACH OTHER AT 18" O.C.
14. PROVIDE PRE-FINISHED GUTTER E-J'S 30'-0" O.C. MAX.
15. DOWNSPOUTS SHALL BE 4"x6" PRE-FINISHED GALVANIZED STEEL UNO AS INDICATED ON ROOF PLAN. PROVIDE PRE-FINISHED 2" GALVANIZED STEEL HANGERS AT 36" O.C. COORDINATE LOCATION WITH ARCHITECT PRIOR TO INSTALLATION.



SEAL:



**ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74**

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:

EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

**ROOF PLAN
BASE BID**

A2.1



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CGSARCHITECT.COM



ECISD HIGH SCHOOL
ATHLETIC MULTI-USE BUILDING
ECISD CSP 25-74

EDINBURG HIGH SCHOOL

2600 E Wisconsin Rd,
Edinburg, TX 78542

CLIENT:
EDINBURG CISD


REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25


ROOF PLAN
ALTERNATE

A2.1A



GENERAL ROOF NOTES:

1. PROVIDE ALL REQUIRED UTILITY / STRUCTURAL COMPONENTS AND/OR CONNECTIONS FOR THE FUNCTIONAL USE OF ALL CONTRACTOR SUPPLIED EQUIPMENT OR APPLIANCES, REGARDLESS OF ANY OMISSIONS OR INCONSISTENCIES ENCOUNTERED IN THE CONSTRUCTION DOCUMENTS.
2. THE WORD 'PROVIDE' SHALL MEAN 'FURNISH AND INSTALL COMPLETE AND READY TO USE.'
3. IF DISCREPANCIES APPEAR BETWEEN THE DRAWINGS AND THE SPECIFICATIONS, THE HIGHER QUALITY, QUANTITY, AND PRICE SHALL SUPERSEDE.
4. THE GENERAL CONTRACTOR AND SUBCONTRACTORS SHALL BECOME FAMILIAR WITH THE PROJECT AND THE ON-SITE / OFF-SITE CONDITIONS PRIOR TO BIDDING OR COMMENCING WORK.
5. ROOF SLOPES SHOWN ON DRAWING ARE GENERAL AND CONCEPTUAL ONLY. PROVIDE POSITIVE DRAINAGE TO ALL GUTTERS. VERIFY IN SHOP DRAWINGS. REFER TO STRUCTURAL DOCUMENTS FOR EXACT TOS/BOD ELEVATIONS.
6. PROVIDE CRICKETS (1/2"/FT. MIN. SLOPE) AT HIGH SIDE OF ALL MECHANICAL UNITS SMOKE VENTS, EXHAUST FANS & OTHER MISC. ROOF PENETRATIONS, TO SHED WATER AROUND & TO ENSURE POSITIVE ROOF DRAINAGE.
7. ALL EXPOSED FLASHING, COPING (IF APPLICABLE) AND THEIR ACCESSORIES SHALL BE AS SPECIFIED. PAINT ALL METAL FLASHING THAT IS NOT PRE-FINISHED (TYP) AND VISIBLE FROM THE GROUND.
8. ALL PITCH PANS SHALL BE SOLDERED CLAD METAL AND RECEIVE EITHER MECHANICALLY ATTACHED GOOSENECK OR METAL BONNETS. METAL BONNETS SHALL BE SECURED WITH CLAMPING RING AND SEALANT. SPECIAL CARE GIVEN TO WASH ALL METAL PRIOR TO INSTALLATION.
9. PROVIDE NEW CONCRETE SPLASH BLOCKS AT ALL DOWNSPOUT DISCHARGE LOCATIONS.
10. ALL EQUIPMENT CURBS TO BE SET OR RAISED AS NECESSARY TO MAINTAIN 10" MINIMUM HEIGHT ABOVE FINISHED ROOF SURFACE.
11. MECHANICAL, ELECTRICAL, AND PLUMBING ROOF EQUIPMENT SHOWN ON THIS PLAN IS FOR GENERAL ARCHITECTURAL INFORMATION ONLY. REFER TO M.E.P. DOCUMENTS FOR ROOFTOP EQUIPMENT NOT SHOWN, AND FOR ADDITIONAL REQUIREMENTS AND COORDINATION.
12. REFER TO M.E.P. DOCUMENTS FOR THE PIPE SUPPORT LOCATIONS, TYPE, AND DETAILS. PAD SHALL BE MIN 2" WIDER THAN SUPPORT IN ALL DIRECTIONS.
13. GUTTERS SHALL BE PRE-FINISHED GALVANIZED STEEL, SIZE PER ROOF PLAN. UNO. PROVIDE PRE-FINISHED 1/4"x1 1/2" GALVANIZED STEEL BENT PLATE BRACKETS AND PRE-FINISHED 1" GALVANIZED STEEL SPACERS AT 36" O.C. MAX. STAGGER WITH EACH OTHER AT 18" O.C.
14. PROVIDE PRE-FINISHED GUTTER EJS 30'-0" O.C. MAX.
15. DOWNSPOUTS SHALL BE 4"x6" PRE-FINISHED GALVANIZED STEEL UNO AS INDICATED ON ROOF PLAN. PROVIDE PRE-FINISHED 2" GALVANIZED STEEL HANGERS AT 36" O.C. COORDINATE LOCATION WITH ARCHITECT PRIOR TO INSTALLATION.



RCP GENERAL NOTES

1. ALL CEILINGS ARE 10'-0" AFF UNO COORDINATE CEILING HEIGHT WITH ARCHITECT PRIOR TO INSTALLATION.
2. ALL REFLECTED CEILING PLAN DIMENSIONS ARE FROM FINISHED FACE TO FINISHED FACE
3. ALL CEILING GRIDS ARE CENTERED ON ROOM OR CORRIDOR, UNO
4. ALL FIXTURES SHOWN AT CEILING GRID TO BE CENTERED IN BOTH DIRECTIONS WITHIN THE TILE. CENTER ALL CEILING MOUNTED ITEMS WITH CEILING ELEMENTS, IN GYP. SOFFITS AND BETWEEN OTHER CEILING MOUNTED FIXTURES
5. COORDINATED ACCESS PANEL LOCATIONS WITH LOCATION OF OTHER CEILING MOUNTED ITEMS.
6. REFER TO ELECTRICAL AND MECHANICAL DRAWINGS FOR FIXTURE TYPES.
7. ALL AREAS OPEN TO STRUCTURE ARE TO BE PAINTED. COORDINATE PAINT COLOR WITH ARCHITECT.
8. ALL EXPOSED CONDUITS, PIPING, DUCTWORK AND MECHANICAL SYSTEMS TO BE PAINTED TO MATCH THE ADJACENT SURFACE UNO
9. COORDINATE LOCATION OF CAN LIGHTS WITH ARCHITECT PRIOR TO INSTALLATION

RCP LEGEND

OPEN TO STRUCTURE AND INSULATION ABOVE. ALL EXPOSED STRUCTURE TO BE PAINTED



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM



**ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74**

**EDINBURG
HIGH SCHOOL**

2600 E
Wisconsin Rd,
Edinburg, TX
78542


CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

**REFLECTED
CEILING PLAN
BASE BID**

A2.3



RCP GENERAL NOTES

1. ALL CEILINGS ARE 10'-0" AFF UNO COORDINATE CEILING HEIGHT WITH ARCHITECT PRIOR TO INSTALLATION.
2. ALL REFLECTED CEILING PLAN DIMENSIONS ARE FROM FINISHED FACE TO FINISHED FACE
3. ALL CEILING GRIDS ARE CENTERED ON ROOM OR CORRIDOR, UNO
4. ALL FIXTURES SHOWN AT CEILING GRID TO BE CENTERED IN BOTH DIRECTIONS WITHIN THE TILE. CENTER ALL CEILING MOUNTED ITEMS WITH CEILING ELEMENTS, IN GYP, SOFFITS AND BETWEEN OTHER CEILING MOUNTED FIXTURES
5. COORDINATED ACCESS PANEL LOCATIONS WITH LOCATION OF OTHER CEILING MOUNTED ITEMS.
6. REFER TO ELECTRICAL AND MECHANICAL DRAWINGS FOR FIXUTRE TYPES.
7. ALL AREAS OPEN TO STRUCTURE ARE TO BE PAINTED. COORDINATE PAINT COLOR WITH ARCHITECT.
8. ALL EXPOSED CONDUITS, PIPING, DUCTWORK AND MECHANICAL SYSTEMS TO BE PAINTED TO MATCH THE ADJACENT SURFACE UNO
9. COORDINATE LOCATION OF CAN LIGHTS WITH ARCHITECT PRIOR TO INSTALLATION

RCP LEGEND

NO CEILING
OPEN TO STRUCTURE ABOVE.



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL: 5/16/2025

ECISD HIGH SCHOOL
ATHLETIC MULTI-USE BUILDING
ECISD CSP 25-74

EDINBURG HIGH SCHOOL

2600 E Wisconsin Rd,
Edinburg, TX 78542

CLIENT:
EDINBURG CISD


REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

REFLECTED CEILING PLAN
ALTERNATE

A2.3A



BASES OF DESIGN

1. **WALL:** MBCI, PBU, FINAL COLOR SELECTED BY OWNER SMOOTH, 24 GAUGE.
2. **ROOF:** MBCI, PBU, FINAL COLOR SELECTED BY OWNER SMOOTH, 24 GAUGE.



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:



**ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74**

**EDINBURG
HIGH SCHOOL**

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:

EDINBURG CISD




REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

**EXTERIOR
ELEVATIONS
BASE BID**

A3.0



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL: 5/16/2025



ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

EXTERIOR
ELEVATIONS
ALTERNATE

A3.0A



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CGSARCHITECT.COM

SEAL: 5/16/2025



ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD



REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

BUILDING
SECTIONS
BASE BID

A4.0





TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL: 5/16/2025



ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542


CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date


PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

BUILDING
SECTIONS
ALTERNATE


A4.0A




2
A2.0A
BUILDING SECTION
ALTERNATE
1/4" = 1'-0"



1
A4.0A
STORAGE AREA
ALTERNATE
1/2" = 1'-0"




1 Section 1 - Callout 1
A4.0 3/4" = 1'-0"



2 Section 2 - Callout 1
A4.0 3/4" = 1'-0"



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM



ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

WALL
SECTIONS AND
DETAILS BASE
BID

A4.1


DOOR HARDWARE:

DH1: DOORS:
6 - HINGES
1 - CENTER MULLION REMOVABLE
2 - THRESHOLDS
2 - PANIC DEVICE BAR TYPE
1 - DOOR LATCH / STRIKE
1 - DOOR LATCH STRIKE
2 - EXTERIOR PULL W/ KEYED CYLINDER AT ONE DOOR (OUTSIDE) PULL
1 - WEATHER STRIPPING FOR DOUBLE DOOR
1 - RAIN GUARD FOR DOUBLE DOOR
2 - DOOR HOLD OPEN


DH2: DOORS:
3 - HINGES
1 - DEADBOLT KEYED ONE SIDE (OUTSIDE)
1 - DEADBOLT LATCH
1 - SET PUSH/ PULL
1 - KICK PLATE
1 - PANIC DEVICE BAR TYPE

DOOR HARDWARE GENERAL NOTES:

1. KEYS AS PER OWNER KEYING SYSTEM.
2. DOOR HARDWARE COLOR TO MATCH EXISTING.
3. ALL HARDWARE TO BE MEDIUM TO HEAVY DUTY





DOOR FRAME TYPES



DOOR TYPES


DOOR SCHEDULE

DOOR SCHEDULE							
MARK	LOCATION		TYPE DESCRIPTION	SIZE	DOOR MATERIAL	DOOR FRAME	DOOR HARDWARE
	FROM	TO		WIDTH x HEIGHT			
100	EXTERIOR	MULTIPURPOSE 100	B	3'-0" x 7'-0"	HOLLOW METAL	HOLLOW METAL	DH2
101	EXTERIOR	MULTIPURPOSE 100	C	10'-0" x 10'-0"	METAL	METAL	-
102	EXTERIOR	MULTIPURPOSE 100	A	3'-0" x 7'-0" DOUBLE	HOLLOW METAL	HOLLOW METAL	DH1
103	EXTERIOR	MULTIPURPOSE 100	B	3'-0" x 7'-0"	HOLLOW METAL	HOLLOW METAL	DH2
104	EXTERIOR	MULTIPURPOSE 100	C	10'-0" x 10'-0"	METAL	METAL	-



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:



**ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
ECISD CSP 25-74**

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD


REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

**DOOR
SCHEDULE**

A7.0



DUCT AND AIR DEVICE NECK SCHEDULE	
DUCT SIZE	CFM RANGE
6"ø	UP TO 120
8"ø	125 - 220
10"ø	225 - 340
12"ø	345 - 500
14"ø	505 - 820

MECHANICAL LEGEND	
SYMBOL	DESCRIPTION
(N)	NEW
(E)	EXISTING
(R)	RELOCATED
—	EXISTING TO REMAIN
✕	EXISTING TO REMOVE
—	NEW
PHWP	PRIMARY HOT WATER PUMP
HWC	HEATING WATER CONVERTER
ST	STEAM TRAP
CRU	CONDENSATE RETURN UNIT
Ⓣ	THERMOSTAT
ⓓ	HUMIDISTAT
ⓕ	FIRESTAT
ⓓ	IONIZATION DETECTOR
ⓓ	SMOKE DAMPER
ⓓ	SMOKE DETECTOR
ⓓ	VOLUME DAMPER
ⓓ 8"ø 200 CFM	DIFFUSER TYPE, NECK SIZE, CFM
ⓓ	SIDE WALL SUPPLY OR RETURN
ⓓ	SUPPLY
ⓓ	RETURN
ⓓ	EXHAUST
ⓓ	FIRE DAMPER
ⓓ	SPLITTER DAMPER - DIMENSION AS NOTED ON DRAWING
ⓓ	ELBOW WITH TURNING VANES
ⓓ	OPPOSED BLADE DAMPER
ⓓ	MOTORIZED DAMPER
ⓓ	FLEXIBLE DUCT CONN. TO RECTANGULAR DUCT WITH SPIN-IN CONNECTOR
UCD 1"	UNDERCUT DOOR 1"
RE- 1/M-2.9	REFER TO DETAIL #1 ON DRAWING M-2.9
— CHS —	CHILLED WATER SUPPLY
— CHR —	CHILLED WATER RETURN
— HWS —	HOT WATER SUPPLY
— HWR —	HOT WATER RETURN
— S-15 —	STEAM 15 PSIG SUPPLY
— C-15 —	CONDENSER 15 PSIG RETURN
CD —	CONDENSATE DRAIN

GENERAL NOTES - MECHANICAL

- ALL WORK DONE ON THESE DRAWINGS SHALL BE DONE IN STRICT ACCORDANCE WITH THE BASE BUILDING DOCUMENTS. REFER TO BASE BUILDING DOCUMENTS FOR ALL DETAILS AND SPECIFICATIONS.
- CONTRACTOR SHALL COMPLY WITH ALL STATE, LOCAL, AND FEDERAL CODES AND AUTHORITIES HAVING JURISDICTION.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE VERIFIED EXISTING JOBSITE CONDITIONS DURING THE BIDDING PERIOD, SO HE WILL HAVE OBTAINED THE SCOPE OF MECHANICAL WORK INVOLVED AS A RESULT OF ARCHITECTURAL MODIFICATIONS TO THE EXISTING STRUCTURE. THE SCOPE OF THE WORK SHALL INCLUDE MATERIALS AND DUCTWORK CONSISTING OF DEVICES, EQUIPMENT OR APPARATUS WHICH MUST BE REROUTED, RELOCATED OR REMOVED EITHER TEMPORARILY OR PERMANENTLY, OR WHICH MUST BE PROVIDED SO THAT THE INDICATED REMODELING MAY BE ACCOMPLISHED. NOT ALL EXISTING CONDITIONS ARE NECESSARILY INDICATED ON THE DRAWINGS.
- CONTRACTOR SHALL COORDINATE WITH STRUCTURAL CONDITIONS AT THE SITE AND PROVIDE ALL CLEARANCES AS INDICATED.
- CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL ELECTRICAL POWER REQUIREMENTS.
- PROVIDE SLOTS, CEILING DIFFUSERS AND RETURN AIR GRILLES ACCORDING TO BASE BUILDING STANDARD.
- FOR EXACT LOCATION OF ALL DIFFUSERS AND REGISTERS, REFER TO ARCHITECTURAL REFLECTED CEILING PLAN.
- ALL EXISTING AIR DEVICES AND EQUIPMENT TO BE RELOCATED OR REUSED MUST BE CLEANED, PAINTED, AND ALL DAMAGED PARTS MUST BE REPAIRED OR REPLACED.
- PROVIDE SPIN-IN FITTING WITH LOCKING QUADRANT BUTTERFLY DAMPER FOR ALL ROUND FLEXIBLE DUCT CONNECTIONS TO RECTANGULAR DUCT.
- REFRIGERANT PIPING TO BE SIZED BY MANUFACTURER. INSULATE WITH 3/4" ARMAFLEX INSULATION. EXTERIOR INSULATION SHALL BE COATED WITH MANUFACTURER'S RECOMMENDED SEALANT. PROVIDE PIPE SADDLES AT HANGERS.
- STEEL SCHEDULE 40 UNINSULATED ON PIPING IN INTERIOR OF BUILDING ALL PIPES, COILS, AND FITTINGS SHALL BE RATED FOR PSIG AS NOTED ON THE PLANS.
- PROVIDE ROUND FLEXIBLE DUCT, MAXIMUM LENGTH TO BE 6'-0" LONG, SAME DIAMETER AS DIFFUSER NECK. EXTEND ROUND SHEETMETAL DUCT AS REQUIRED.
- ALL NEW ROUND DUCTS SHALL BE EXTERNALLY INSULATED WITH 1-1/2" THICK FIBERGLASS INSULATION WITH VAPOR BARRIER.
- SEAL ALL JOINTS IN DUCTWORK WITH EC-800 OR HARDCAST IRON GRIP.
- CONTRACTOR SHALL SEAL ALL INACTIVE DUCT TAPS AIR TIGHT.
- ALL DUCTWORK SHALL BE SHEETMETAL, LINED WITH 1" THICK FIBERGLASS INSULATION. ALL NEW EXHAUST DUCTWORK SHALL BE UNLINED SHEETMETAL. ALL NEW DUCTWORK SHALL BE FABRICATED TO THE LATEST EDITION OF SMACNA. DUCT SIZES ARE CLEAR INSIDE DIMENSIONS.
- MOUNT THERMOSTATS AT SAME ELEVATION AS LIGHT SWITCHES. COORDINATE WITH ARCHITECT PRIOR TO CONSTRUCTION.
- ALL CONDENSATE DRAINS SHALL BE GALVANIZED STEEL OR COPPER. CONDENSATE DRAIN LINES SHALL BE INSULATED WITH 3/8" THICK INSULATION.
- PROVIDE NEW PLEATED, NON WOVEN FARR 30/30 FILTER FOR ALL NEW AND EXISTING FAN COIL UNITS, AIR HANDLING UNITS, HEAT PUMPS AND HOT WATER COILS.

MECHANICAL LEGEND

SYMBOL	DESCRIPTION
ⓓ 250	AIR DEVICE, SUPPLY CFM IF APPLICABLE
ⓓ	SUPPLY DIFFUSER
ⓓ	RETURN AIR OR EXHAUST GRILLE
ⓓ	THERMOSTAT
ⓓ	NEW DUCTWORK
ⓓ	MANUAL VOLUME DAMPER
ⓓ	SPLITTER DAMPER, DIMENSION AS SHOWN
ⓓ	SCHEDULED DIFFUSER FLEX DUCT RIGID EXTENSION FROM SPIN-IN SPIN-IN FITTING WITH VOLUME DAMPER TRUNK DUCT
ⓓ	EXISTING DUCTWORK
RE: #1/M200	REFER TO DETAIL #1 ON DRAWING M200



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

MECHANICAL
LEGEND


M0.0

5/16/25

ISSUED FOR PERMIT

VME
ENGINEERING

1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25




1
M1.0

MECHANICAL SITE PLAN - EDINBURG HIGH

Scale: 1/64" = 1'-0"



5/16/25



ISSUED FOR PERMIT



1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

**ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74**

**EDINBURG
HIGH SCHOOL**

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:

EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

**MECHANICAL
SITE PLAN**

M1.0



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:


EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

MECHANICAL
FLOOR PLAN -
TYPICAL BLDG.




ISSUED FOR PERMIT



1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25

M1.1



MECHANICAL GENERAL NOTES

- CONTRACTOR SHALL BALANCE EACH SPACE WITH THE CFM SHOWN ON PLAN. NOTE NOT ALL SPACES HAVE SAME CFM SHOWN ON RTU SCHEDULE.
- NEW PIPING AND DUCTWORK SHOWN ON PLAN ARE SCHEMATIC ONLY. CONTRACTOR SHALL COORDINATE WITH OTHER TRADES FOR PIPING AND DUCTWORK ROUTING. OFFSET AND RUN PIPING, DUCTWORK INSIDE THE STRUCTURE IF REQUIRED. PROVIDE ANY EXTRA PIPING, DUCTWORK, FITTINGS, INSULATIONS AND OTHER ACCESSORIES IN ORDER TO COMPLETE THE INSTALLATION.
- COORDINATE LOCATIONS ROOF OPENINGS AND SIZES OF WALL OPENINGS WITH ARCHITECT AND STRUCTURE ENGINEERS.
- EQUIPMENT SIZES, DIMENSIONS AND REQUIRED CONNECTIONS SHALL BE VERIFIED WITH THE VENDOR DRAWINGS BEFORE FABRICATION OF DUCTWORK, PIPING.
- DUCT SIZES SHOWN ON PLANS ARE CLEAR INSIDE AIR STREAM DIMENSIONS. DUCTWORK SHALL BE SHEET METAL.
- CONTRACTOR SHALL COORDINATE ALL ELECTRICAL REQUIREMENTS FOR ALL HVAC EQUIPMENT PRIOR TO INSTALLATION.

MECHANICAL KEYED NOTES

- RTU ON FLOOR PROVIDE 6" CONCRETE PAD. COORDINATE INSTALLATION WITH SIDE OPENINGS AND REQUIRED CLEARANCES. PROVIDE PROPER SUPPORT. FIELD COORDINATE LOCATION WITH STRUCTURE AND OFFSET AS REQUIRED. PROVIDE FLEXIBLE CONNECTIONS ON SUPPLY AND RETURN DUCT
- PROVIDE 7 DAY PROGRAMMABLE THERMOSTAT. INSTALL SMOKE DETECTORS WHERE REQUIRED BY FIRE MARSHALL. THERMOSTAT SHALL BE COMPATIBLE WITH ALL OF THE UNITS ACCESSORIES AND PROGRAMMING. CONSULT WITH HVAC MANUFACTURER FOR RECOMMENDED THERMOSTAT. IF SCHOOL HAS CONTROLS PROVIDE CONNECTION POINTS TO CONTROL SYSTEMS.
- PROVIDE FILTERED RETURN AIR GRILLED AS SCHEDULED ON DOOR/WALL/CEILING. SIZE IS INDICATED ON PLAN.
- PROVIDE 6" CONCRETE PAD FOR ACCU.
- PROVIDE RELIEF HOOD ON ROOF. PROVIDE 14" ROOF CURB. PROVIDE RELIEF DAMPER SET AT 0.05". COORDINATE WITH ROOF SLOPE. PROVIDE DUCT SAME SIZE AS OPENING AND TERMINATE 12" BELOW ROOF INSULATION. PROVIDE WIRE MESH AT END.
- PROVIDE PROTECTIVE SLEEVE TO EXPOSED DUCT. PAINT OR COVER TO BE WHITE.
- PROVIDE TRANSITION FROM RTU OPENING TO DUCT INDICATED ON PLANS. PROVIDE FLEXIBLE CONNECTION.
- RUN DUCT AS HIGH AS POSSIBLE. MINIMUM 12" A.F.F. NOZZLES TO HAVE MORE FLOW TOWARDS MIDDLE OF BUILDING.
- PROVIDE EXHAUST FAN ON ROOF. PROVIDE 14" ROOF CURB. COORDINATE WITH ROOF SLOPE. PROVIDE DUCT SAME SIZE AS EXHAUST OPENING. ROUTE TO 24" BELOW ROOF INSULATION. PROVIDE WIRE MESH AT END. FAN TO BE ON WHEN RESPECTIVE RTU OUTSIDE AIR IS OPEN AND OFF WHEN OUTSIDE AIR DAMPER IS CLOSED. PROVIDE NECESSARY RELAYS OR CONTACTOR FOR PROPER CONTROL.

REFERENCE CODES

- 2018 INTERNATIONAL BUILDING CODE.
- 2018 INTERNATIONAL FIRE CODE.
- 2018 INTERNATIONAL MECHANICAL CODE
- 2018 INTERNATIONAL PLUMBING CODE
- 2017 NATIONAL ELECTRICAL CODE
- 2015 INTERNATIONAL ENERGY CONSERVATION CODE

1
M1.1

MECHANICAL FLOOR PLAN - TYPICAL BLDG.

Scale: 3/16" = 1'-0"

AIR DEVICE SCHEDULE			
MARK	MFR. & MODEL	TYPE	REMARKS
F	TITUS 350FLF1	SIDEWALL RETURN AIR GRILLE	ALUMINUM CONSTRUCTION WITH FRAME FOR SURFACE MOUNT. 3/4" BLADE SPACING, DOUBLE DEFLECTION WITH FRONT BLADES PARALLEL TO LONG DIMENSION.
NOTES: 1. REFER TO ARCHITECTURAL DRAWINGS FOR FINISH. 2. REFER TO MECHANICAL FLOOR PLAN FOR NECK SIZES.			

EXHAUST FAN SCHEDULE	
MARK	EF-1,2
SERVES	MULTIPURPOSE
TYPE/DRIVE	BELT
CFM	600
EXT. S.P. (IN. W.G.)	0.50
HORSEPOWER	1/4
RPM (MAX.)	1,010
SONES (MAX.)	0.6
VOLTS/PHASE/HERTZ	120/1/60
MANUFACTURER	GREENHECK
MODEL NUMBER	GB-091
NOTES	1,2
NOTES: 1. PROVIDE WITH BACKDRAFT DAMPER. 2. INTERLOCK FAN WITH SWITCH RTU OUTSIDE AIR.	

ROOFTOP UNIT SCHEDULE (ELECTRIC HEAT)		
FAN AND MOTOR DATA	MARK	RTU- 12.5 Ton
	SERVES	AREA
	SUPPLY AIR (CFM)	4000
	OUTSIDE AIR (CFM)	600
	MINIMUM HP (MOTOR)	5
	DRIVE	VFD
	EXT. SP. (IN W.G.)	0.8
COOLING	TOTAL COOLING (MBH)	144.3
	SENSIBLE COOLING (MBH)	105.4
	ENTERING AIR TEMP. DB/WB (F)	78.5/64.8
	LEAVING AIR TEMP. DB/WB (F)	54.4/52.6
	AMBIENT TEMP. (F)	100
HEATING	TOTAL HEATING (KW) / STAGES	18
	ENTERING AIR TEMP. DB (F)	60
	LEAVING AIR TEMP. DB (F)	74.2
ELECTRIC	VOLTS/PHASE/HERTZ	480/3/60
	MCA	45.8
	MOCP	50
GENERAL	MANUFACTURER	JOHNSON CONTROLS
	MODEL	KB150E18R4BDBCL6E1
	NOMINAL TONS	12.5
	I.E.E.R./E.E.R. (ARI)	16.0 IEER/ 12.2 EER
	WEIGHT (LBS)	1,415
	NOTES	1,2,3,5,6,7,8,9,10,11
NOTES:		
1. PROVIDE SINGLE POINT ELECTRICAL CONNECTION.		
2. PROVIDE FACTORY MOUNTED CONDENSER COIL GUARD.		
3. PROVIDE DUAL ENTHALPY ECONOMIZER.		
4. PROVIDE WITH FACTORY INSTALLED HOT GAS REHEAT DEHUMIDIFICATION.		
5. PROVIDE WITH CO2 DEMMAND CONTROL VENTILATION.		
6. PROVIDE WITH FACTORY INSTALLED SIMPLICITY CONTROLLER WITH BACNET INTERFACE.		
7. PROVIDE WITH UNIT POWERED ELECTRIC GFCI OUTLET.		
8. PROVIDE FACTORY SPACE TEMP SENSOR AND HUMIDITY SENSOR.		
9. PROVIDE FACTORY INSTALLED VFD FOR SINGLE ZONE VAV OPERATION.		
10. PROVIDE WITH 18" HIGH FACTORY ROOF CURB. PROVIDE TX PE WIND LOAD RATED ATTACHMENT DESIGN AND CALCULATIONS.		
11. CONTACT TEXAS AIRSYSTEMS FOR PRICING AND AVAILABILITY AT (956)566-9540 OR CARLOS.CASTANEDA@TEXASAIRSYSTEMS.COM		



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD


REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25


MECHANICAL
SCHEDULES

M2.0

5/16/25




ISSUED FOR PERMIT




ENGINEERING


1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25




1 FLOOR MOUNTED RTU DETAIL
NOT TO SCALE




2 OA INTAKE OR EXHAUST RELIEF HOOD
NOT TO SCALE




3 TYP. MEP INSTALLATION DETAIL
NOT TO SCALE



4 OVAL OR ROUND DUCT MOUNTING
NOT TO SCALE



5 OVAL OR ROUND DUCT HANGER
NOT TO SCALE



6 CENTRIFUGAL ROOF EXHAUST FAN
NOT TO SCALE



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH SCHOOL
ATHLETIC MULTI-USE BUILDING
25-74

EDINBURG HIGH SCHOOL

2600 E Wisconsin Rd,
Edinburg, TX 78542

CLIENT:
EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

5/16/25

ISSUED FOR PERMIT

1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25

MECHANICAL DETAILS

M3.0



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:


EDINBURG CISD

REVISION:


No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

MECHANICAL
SPECS



ISSUED FOR PERMIT



1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25

M4.0

SECTION 15050 – MECHANICAL SPECIFICATIONS

PART I - GENERAL-MECHANICAL

1-1 DESCRIPTION

All work on these Drawings shall be done in strict accordance with these Specifications. The Work included under this Contract shall consist of the furnishing and installation of all equipment and material necessary and required to form the complete and functioning system in all of its various phases, all as shown on the accompanying drawings and/or described in these Specifications.

1-2 WARRANTY

The Contractor shall guarantee the work for a period of one year beyond date of final acceptance. During that period, the Contractor shall repair or replace, at his own expense, any faults or imperfections that may arise due to defects in material and workmanship, including the loss of refrigerant and/or oil due to leaks. Defects shall include but not be limited to noisy operation, loose or missing parts, or noticeable deterioration of finish. During the period, the Contractor shall actually perform all service work required, including the servicing of air filters. All air conditioning compressors shall have parts and labor guarantees for a period of not less than 5 years beyond the date of final acceptance.

1-3 PROJECT CONDITIONS

The Contractor shall visit the Site of the Work and fully understand the conditions that affect the work, or the cost thereof, understand the existing utilities from which services will be supplied, verify locations of utility services, determine requirements for connections, and determine in advance that equipment and materials proposed for installation fit into the confines indicated.

1-4 PERMITS AND FEES

The Contractor shall arrange and pay for all permits, fees, test, and all inspections as required by Governmental Authorities.

1-5 COORDINATION WITH FIELD CONDITIONS

The Contract Documents are schematic in nature in that they are only to establish "Scope" and a minimum level of quality. All duct or pipe or equipment locations as indicated on the Documents do not indicate every transition, offset, or exact location. All transitions, offsets, and exact locations shall be established by actual field measurements, coordination with the structural, architectural and reflected ceiling plans. All transitions, offsets, and relocations as required by actual field conditions shall be performed by the Contractor at no additional cost to the Owner.

1-6 SUBMITTALS

Contractor shall provide six sets of Shop Drawings and Submittals on all Mechanical equipment, insulation, air devices, ductwork (flexible and rigid), and thermostats. Any deviations from the specified items shall be listed on the cover sheet and clearly identified for all deviations. The Contractor shall provide two copies of Owner's Manual to the Architect upon completion of the work.

1-7 QUALITY ASSURANCE

All Work shall be performed in accordance with all State, Local, and Federal Codes and all Authorities and Jurisdiction.

1-8 EQUIPMENT IDENTIFICATION

All Mechanical equipment shall be identified by means of nameplates permanently attached to the equipment. Nameplates shall be engraved laminated plastic or etched metal.

1-9 TESTING AND BALANCING

Testing and balance shall be provided by the Mechanical Sub-Contractor, with the services of an independent Test and Balance Agency. The Test and Balance Company shall specialize in such work, and be a member of Associated Air Balance Council (AABC). The forms used shall be based on recommendations of AABC. Upon completion of the Balancing and Testing, the Balancing Contractor shall compile the test data in report forms, and forward five copies to the Architect for evaluation. The final report shall contain logged results of all tests, including such data as:

Tabulation of air volume at each outlet. (Balanced to within 5% design).

Outside dry bulb and wet bulb temperatures.

Inside dry bulb and wet bulb temperatures in each conditioned space room or area.

Actual fan capacities, RPM's and static pressures. Motor current and voltage readings at each fan.

Entering and leaving air temperatures, DB and WB.

PART II - DUCTWORK-MECHANICAL

2-1 METAL DUCTWORK

All ductwork shall be properly suspended or supported from the building structure. Hangers shall be galvanized steel straps or hot-dipped galvanized rod with thread pointed after installation. Strap hanger shall be attached to the bottom of the ductwork. The spacing, size and angle shall be in accordance with the recommendations of latest edition of SMACNA space hangers as required to support ducts without sagging.

Ventlock No. 699 "Test Plugs" shall be provided in ductwork at all openings in ductwork required for testing and balancing.

2-2 DUCTWORK MATERIALS

Exposed Ductwork Materials: Where ductwork is indicated to be exposed to view in occupied spaces, provide materials which are free from visual imperfections including pitting, seam marks, roller marks, stains and discolorations, and other imperfections, including those which would impair painting.

Sheet Metal: Except as otherwise indicated, fabricate ductwork from galvanized sheet, steel complying with ASTM A527, lockforming quality, with 900 zinc coating in accordance with ASTM A 525, and mill phosphatized for exposed locations.

Stainless Steel Sheet: Where indicated, provided stainless steel complying with ASTM A167; Type 316; with No. 4 finish where exposed to view in occupied spaces, No. 1 finish elsewhere. Protect finished surfaces with mill-applied adhesive protective paper, maintained through fabrication and installation.

Aluminum Sheet: Where indicated, provide aluminum sheet complying with ASTM B209, Alloy 5003, Temper H14.

- A. Non combustible and conforming to UL 181, Class 1 air duct materials.
- B. Flexible ducts: Flexmaster U.S.A. Inc. Type 3M or approved equal, corrosive resistance galvanized steel formed and Mechanically locked to inner fabric with 1 inch thick insulation when flexible ducts are located in conditioned spaces and with R-5 insulation when located in unconditioned spaces. Flexible duct shall have reinforced metalized outer jacket comply with UL 181, Class 1 air duct.
- C. Sealants: Hard-Cast "Iron Grip" or approved equal, non-hardening, water resistant, fire retentive and shall not be a solvent curing product. Sealants shall be compatible with mating materials, liquid used alone or with tape or heavy mastic.
- D. Ductwork Support Materials: Except as otherwise indicated, provide hot-dipped galvanized steel fasteners, anchors, rods, straps, trim and angles for support of ductwork.
 - 1. For exposed stainless steel ductwork, provide matching stainless steel support materials.
 - 2. For aluminum ductwork, provide aluminum support materials.

2-1-2 LOW PRESSURE DUCTWORK

- A. Fabricate and support in accordance with latest SMACNA low pressure duct construction standards and ASHRAE handbooks, except as indicated. Provide duct material, gages, reinforcing, and sealings for operating pressures indicated.
- B. Size round ducts installed in place of rectangular ducts in accordance with ASHRAE table of equivalent rectangular and round ducts. No variation of duct configuration or sizes permitted except by approved shop drawings. Obtain engineer's approval prior to using round duct in lieu of rectangular duct.
- C. Construct Ts, bends, and elbows with radius of not less than 1-1/2 times width of duct centerline. Where not possible and where rectangular elbows are used, provide airfoil-turning vanes. Where acoustical lining is indicate, provide turning vanes of perforated metal with glass fiber insulation.

- D. Increase duct sizes gradually, not exceeding 15 degrees divergence wherever possible. Divergence upstream of equipment shall not exceed 30 degrees; convergence downstream shall not exceed 45 degrees.
- E. Use crimp joints with bead for joining round duct sizes 6 inch and under with crimp in direction of airflow.
- F. Use double nuts and lock washers on threaded rod supports.

2-1-3 CASINGS

- A. Fabricate casings in accordance with SMACNA low pressure duct construction standards and SMACNA high pressure duct construction standard and construct for operating pressures indicated.
- B. Mount floor mounted casings on 4 inch high concrete curbs. At floor, rivet panels on 8 inch centers to angles. Where floors are acoustically insulated, provide liner of 18 gage galvanized expanded metal mesh supported at 12 inch centers, turned up 12 inches at sides with sheet metal shields.
- C. Reinforce doorframes with steel angles tied to horizontal and vertical plenum supporting angles. Install hinged access doors where indicated or required for access to equipment for cleaning and inspection. Provide clear wire glass observation ports, minimum 6x6 inch size.
- D. Fabricate acoustic casings with reinforcing turned inward. Front 16 gage back facing and 22 gage perforated front facing with 3/32 inch diameter holes on 5/32 inch centers. Construct panels 3 inches thick packed with 4.5 lb./cubic foot minimum glass fiber media, on inverted channels of 16 gage.

2-1-4 KITCHEN HOOD EXHAUST DUCTWORK

- A. Fabricate in accordance with SMACNA low pressure duct construction standards, high pressure duct construction standards, and NFPA 96.
- B. Construct of 16 gage carbon steel or 18 gage stainless steel, using continuous external welded joints.

2-1-5 EXECUTION

- A. Obtain Manufacturer's inspection and acceptance of fabrication and installation of ductwork at beginning of installation.
- B. Provide openings in ductwork where required to accommodate thermometers and controllers. Provide Pilot tube openings where required for testing of systems, complete with metal con with spring drive or screw to ensure airtight air leakage where openings are provided in insulated ductwork, install insulation material inside a metal ring.
- C. Locate ducts with sufficient space around equipment to allow normal operating and maintenance activities.
- D. Connect terminal units to medium or high pressure ducts with four feet maximum length of flexible duct. Do not use flexible duct to change direction.
- E. Connect diffusers or transfer boxes to low pressure ducts with 6 feet maximum, 4 feet minimum, length of flexible duct. Hold in place with strap or clamp.
- F. During construction provide temporary closures of metal or taped polyethylene on open ductwork to prevent constructing dust from entering ductwork system.
- G. The interior surface of all ductwork shall be smooth. No sheet metal parts, tabs, angles, or anything else may project into the ducts for any reason, except as specified to be so. All seams and joints shall be external.
- H. All ductwork located exposed on roof shall be "Crowned" to prevent water from ponding. Reference insulation for additional requirements.
- I. Where ducts pass through floors, provide structural walls for duct support. Where ducts pass through walls in exposed areas, install suitable sheet metal enclosures as covers.
- J. All angles shall be carried around all four sides of the duct or group of ducts. Angles shall overlap corners and be welded or riveted.
- K. All ductwork shall be fabricated in a manner to prevent the seams or joints being cut for the installation of grilles, registers, or ceiling outlets.

2-1-6 INSTALLATION OF FLEXIBLE DUCTS

- A. Maximum length: For any duct run using flexible ductwork, do not exceed 6'-0" extended length.
- B. Installation: Install in accordance with Section 3 of SMACNA's, "HVAC duct construction standards, metal and flexible".
- C. Provide spin-in fitting for all round flexible duct connections to rectangular duct. Spin-in fittings shall factory fabricated, and include an air extractor scoop and a balancing butterfly damper with a locking quadrant and handle. Balancing shall be at the spin-in fitting and not at the air distribution device.

2-1-7 DUCTWORK HANGERS AND SUPPORTS

- A. All ductwork shall be properly suspended or supported from the building structure. Hangers shall be galvanized steel straps or hot-dipped galvanized rod with threads pointed after installation. Strap hanger shall be attached to the bottom of the ductwork. Provide a minimum of two screws one at the bottom and one in the side of each strap on metal ductwork. The spacing, size and installation of hangers shall be in accordance with the recommendations of the latest SMACNA Edition.
- B. All duct risers shall be supported by angles or channels secured to the sides of the ducts at each floor with sheet metal screws or rivets. The floor supports may also be secured to ducts by rods, angles or flat bar to the duct joint or reinforcing. Structural steel supports for duct risers shall be provided under this division.

2-2 DUCT INSULATION

All insulation shall be installed in accordance with the Manufacturer's recommendations and printed installation instructions.

All items required for a complete and proper installation are not necessarily indicated on the Plans or in the Specifications. Provide all items required as per manufacturer's requirements.

All toilet exhaust ductwork shall be unlined sheet metal with all joints sealed. Duct dimensions shown on Plans are clear inside dimensions.

2-2-1 EXTERNAL DUCT INSULATION

- A. Fasten all longitudinal and circumferential laps with outward clinching staples 3" on center. On rectangular ducts over 24" wide apply as above and hold insulation in place on bottom side with mechanical pins and clips on 12" centers.
- B. Seal all joints, fastener penetrations and other breaks in vapor barrier with 3 inch wide strips of white glass fabric embedded between two coats of vapor barrier mastic, chiders GP-30 or approved equal.
- C. All external duct insulation shall be Johns Manville Type 75 fiberglass duct wrap insulation with reinforced aluminum facing or approved equal.
- D. External duct wrap is required on all outside air ducts and supply air ducts that are not internally insulated. Duct wrap shall be provided as follows:
 - 1. 1 1/2" thick, 1/0 PCF density minimum when ducts are located in conditioned spaces.
 - 2. 2" thick with a minimum installed R-value of 5 when ducts are located in unconditioned spaces, such as ceiling plenum space.

2-2-2 DUCT LINER

- A. Duct liner shall be kept clean and dry during transportation, storage and installation. Care should be taken to protect the liner from exposure to the elements or damage from mechanical abuse.
- B. All portions of duct designed to receive duct liner shall be completely covered with liner as specified. The smooth block, acrylic-coated surfaces with flexible glass cloth reinforcement shall face the airstream. All duct liner shall be cut to assure tight, overlapped corner joints. The top pieces shall be supported by the sidepieces. Duct liner shall be installed following the guidelines in the NAIMA "Duct Liner Installation Standard".
- C. The duct liner shall be tested according to erosion test method in UL 181 and shall be guaranteed to withstand velocities in the duct system up to 5000 FPM without surface erosion.
- D. Duct liner shall be adhered to the sheet metal with full coverage of an approved adhesive that conforms to ASTM C 816, and all exposed trailing edges and transverse joints shall be coated with permacoate factory-applied or field-applied edge coating and shall be neatly butted without gaps. Shop or field cuts shall be liberally coated with Johns Manville Superseal® Duct butter and edge treatment or approved adhesive.
- E. Metal nosings shall be securely installed over transversely oriented liner edges facing the airstream at forward discharge and at any point where lined duct is preceded by unlined duct.

When velocity exceeds 4000 FPM (20.3 M/SEC), use metal nosing on every leading edge. Nosing may be formed on duct or be channel or zee attached by screws, rivets or welds.

The liner shall further be secured with graham welding pins and washers on not more than 16 inch centers both vertical and horizontal surfaces, and the pins and washers shall be pointed up with adhesive.

Duct liner shall be Johns Manville Lincoacoustic RC fiberglass duct liner with factory-applied edge coating or approved equal. The liner shall meet the life safety standards as established by NFPA 90A and 90B, FHC 25/50 and limited combustibility and the air stream surface coating should contain an immobilized, EPA-registered, anti microbial agent so it will not support microbial growth as tested in accordance with ASTM G21 and G22, the duct liner shall conform to the requirements of ASTM C 423 using a Type "A" mounting, and a thermal conductivity no higher than .025 BTUIN/(HRFT2F) at 75°F mean temperature.

Duct liner is required on all return air ductwork, return air boots and supply air ductwork downstream of the terminal units. Duct liner shall be provided as follows:

- 1. 1" thick, 1.5 PCF density minimum when ducts are located in conditioned spaces.

- 2. 1 1/2" thick with a minimum installed R-value of 5 when ducts are located in unconditioned spaces, such as ceiling plenum space.
- 3. 2" thick with a minimum installed R-value of 8 when ducts are located outdoors.

- J. Line supply and return ductwork at connection of HVAC unit to a point of 15 feet upstream and downstream of the equipment with John Manville, Incoacoustic RC with an R-value of 5 or approved equal for thermal insulation and noise control. The liner shall meet the safety standards as indicated above with IRC not less than 0.75 as tested per ASTM C423 using a Type "A" mounting at thermal conductivity no higher than 0.24 BTUIN/(HRFT2F) at 75°F mean temperature. Atmos with full cover coat of cement, duct dimensions up to 16 inches, provide stick clips or screws and cap for dimension over 16 inches, space 16 inches O.C. maximum. Provide sheet metal liner cap over all leading edges of internal insulation exposed to air stream.

2-2-3 EXPOSED DUCTWORK LOCATED INDOORS

- A. Duct routed exposed shall be internally lined as specified.
- B. Round and [flat oval] duct routed exposed shall be double wall with solid inner liner and 1" thick layer of fiberglass insulation as manufactured by United McGill Company model no. Acousti-27 or approved equal.

2-2-4 EXPOSED DUCT LOCATED OUTDOORS

- A. All duct located outdoors shall be internally lined as specified and also shall have a 2" thick, 6lb. density rigid board external duct insulation, finished with a white weatherproofed canvas material.

2-2-5 AIR DEVICE AND MISCELLANEOUS DUCT INSULATION

- A. The backside of all supply air devices shall be insulated with taped and sealed 1 1/2 inch thick external duct wrap.
- B. The Contractor shall install an additional layer of 1 1/2 inch thick external fiberglass duct wrap on any portion of the supply air, return air, outside air, or exhaust air system that has condensation forming during any period of operation. The insulation shall be taped and sealed and located until all evidence of the condensation had been eliminated at no additional cost to the owner.

2-2-6 KITCHEN GREASE HOOD EXHAUST DUCT

- A. All kitchen range hood exhaust duct shall be enclosed with 2 hours fire rated enclosure.
- B. The duct enclosure shall be sealed around the duct at the points of penetration.
- C. The enclosure shall be separated from the duct by at least 3 inches and not more than 12 inches.
- D. Cleanout openings at exhaust duct with access openings at the fire rated enclosure and access doors shall be provided at each duct offset and as required for proper operation and maintenance.
- E. As an alternate method, the Contractor may use the "3M fire barrier 1000 N/5 silicone sealant", Johns Manville firetemp wrap SL2 or approve equals in lieu of the fire rated enclosure, providing the product used shall meet UL requirements and be approved by the local authority having jurisdiction. This application shall follow the Manufacturers' strict installation instructions and guidelines.
- F. Insulation and all other requirements shall be provided per local codes.

PART III: EQUIPMENT - MECHANICAL

3-1 AIR DISTRIBUTION

- A. Air distribution devices shall be selected at a maximum of 25 noise criteria and at a maximum of 0.06" W.G. total pressure drop. Approved Manufacturers are Metalaire, Titus, and Krueger.
- B. The backside of all supply air devices not located in a return air plenum shall be insulated with taped and sealed 1-1/2" thick one lb. density fiberglass insulation with vapor barrier.

3-2 PIPING

- A. All condensate drains shall be galvanized steel or copper with 1/2" thick amflex insulation.
- B. Refrigerant piping shall be copper ACR tubing, fittings shall be wrought copper steamlined sweat fitting.
- C. All condenser water piping shall be Type L hard drawn copper tubing, fittings shall be ANSI/ASME B16.23 cast brass, or ANSI/ASME B16.29 solder wrought copper, joints shall be ANSI/AMS A5.9, BCUIP silver braze.

3-3 SOUND AND VIBRATION CONTROL

- A. Provide vibration isolation supports for equipment, piping, and ductwork to prevent transmission of vibration and noise to the building structure that may cause discomfort to the occupants.
- B. All items required for a complete and proper installation are not necessarily indicated on the plans or in the Specification. Provide all items required as per Manufacturers requirements and install as per Manufacturers recommendations and instructions.
- C. All vibration isolators shall be designed and treated for resistance to corrosion.

3-4 FANS

- A. The following Manufacturers are approved subject to Specification Compliance: Greenheck, Cook, Bredert, ACME, Penn.
- B. All fans shall be tested in accordance with latest AMCA Fan Test Code shall bear AMCA certified rating seal.
- C. All fans with v-belt drives shall have statically and dynamically balanced adjustable sheaves with drive capacity not more than 150% of the nominal motor horsepower. Adjustable drives as Manufactures by Browning, Gates, or Goodrich will be acceptable.
- D. All motors shall be selected so that they will not overload if the static pressure drops one-half inch. Motor Controller will be furnished by this division, unless noted otherwise on the plans. Refer to drawings for 2-speed fan motor requirements. Provide fan guard for all wall mounted fans.
- E. Fans shall be installed as detailed on drawings and in accordance with Manufacturer's recommendations. Fans moving 2,000 CFM and more shall have smoke detector installed in ductwork or other suitable location to detect products of combustion and shut-off fan.

3-5 AIR FILTERS

- A. The following Manufacturers are approved subject to Specification Compliance: American Air Filter, Air Guard Industries Inc., and Cambridge.
- B. The filters shall be Fpr 30/30 2 inch thick or approved equal.


END OF SECTION

ABBREVIATIONS

A	
A	AMPERES
ABV	AIR CONDITIONING
A/C	ALTERNATING CURRENT,
ACC	AIR COOLED CHILLER
ACCU	AIR COOLED CONDENSING UNIT
AD	ACCESS DOOR
ADA	AMERICANS WITH DISABILITIES ACT
AF	AMPERE FUSE, AMPERE FRAME
AFC	ABOVE FINISHED CEILING
AFI	ABOVE FINISHED FLOOR
AFO	ABOVE FINISHED GRADE
AHU	AIR HANDLING UNIT
AIC	AMPERE INTERRUPT CAPACITY
AL	ALUMINUM
AM	AMMETER
AMP	AMPLIFIER
ANN	ANNUNCIATOR
AP	ACCESS PANEL, ALARM PANEL
ARCH	ARCHITECT, ARCHITECTURAL
ASC	AMPERES SHORT CIRCUIT
AT	AMPERE TRIP RATING
ATS	AUTOMATIC TRANSFER SWITCH
AVG	AVERAGE
AUX	AUXILIARY
AWG	AMERICAN WIRE GAUGE
B	
BAS	BUILDING AUTOMATION SYSTEM
BC	BELOW COUNTER
BKR	BREAKER
BLDG.	BUILDING
C	
C	CONDUIT, CELSIUS
CATV	CABLE TELEVISION SYSTEM
CCTV	CLOSED CIRCUIT TELEVISION
CWP	CONDENSER WATER PUMP
CH	CHILLER
CHP	CHILLED WATER PUMP
CIRC	CIRCULATING
CKT	CIRCUIT
CL	CENTERLINE
CLG.	CEILING
CMU	CONCRETE MASONRY UNIT
COL	COLUMN
CONC	CONCRETE
CONN	CONNECTION
CONT.	CONTINUOUS, CONTINUATION
CONTR.	CONTROLLER, CONTRACTOR
CP	CIRCUITING PUMP
CPUC	CPU CHILLER
CR	CARD READER, CORD REEL
CRU	CONDENSATE RETURN UNIT
CT	CURRENT TRANSFORMER, COOLING TOWER
CTR	CENTER
CU	COPPER
D	
dB	DECEBEL
DC	DIRECT CURRENT
DDC	DIRECT DIGITAL CONTROL
DIA	DIAMETER
DIM	DIMENSION
DISC	DISCONNECT
DN	DOWN
DP	DISTRIBUTION PANEL
DPDT	DOUBLE-POLE, DOUBLE-THROW
DPST	DOUBLE-POLE, SINGLE-THROW
DR	DROPPED RECEPTACLE
DS	DAYLIGHT SENSOR
DW	DISHWASHER
DWG	DRAWING
DWH	DOMESTIC WATER HEATER
DWP	DOMESTIC WATER PUMP
DZ	DAYLIGHT ZONE
E	
(E)	EXISTING
EA	EACH
EC	ELECTRICAL CONTRACTOR
E.C.	EMPTY CONDUIT
EDF	ELECTRIC DRINKING FOUNTAIN
EF	EXHAUST FAN
EFF	EFFICIENCY
EHC	ELECTRIC HEATING COIL
EJ	EXPANSION JOINT
EL	ELEVATION
ELEC.	ELECTRICAL
ELEV.	ELEVATOR
EMCS	ENERGY MANAGEMENT AND CONTROLS SYSTEM
EMERG	EMERGENCY
EMS	ENERGY MANAGEMENT SYSTEM
ENCL.	ENCLOSURE
ENGR.	ENGINEER
EPO	EMERGENCY POWER OFF
EQUIP	EQUIPMENT
(ER)	EXISTING TO REMAIN
EUH	ELECTRIC UNIT HEATER
EW	ELECTRIC WATER HEATER
EXH	EXHAUST
F	
F	FAHRENHEIT, FAN, FIRE
FA	FIRE ALARM
FACP	FIRE ALARM CONTROL PANEL
FCU	FAN COIL UNIT
FF	FURNITURE FEED
FIXT	FIXTURE
FLA	FULL LOAD AMPS
FLX	FLEXIBLE
FLR	FLOOR
FLUOR	FLUORESCENT
FP	FIRE PUMP, FAN POWERED
FPTB	FAN POWERED TERMINAL BOX
FRZR	FREEZER
FS	FUSED SWITCH, FLOW SWITCH
FSD	MOTORIZED FIRE SMOKE DAMPER
FT	FOOT, FEET
FTL	FEED-THRU LUGS
FUT	FUTURE
FVNR	FULL-VOLTAGE, NON-REVERSING

G	
GA	GAUGE
GAL	GALLON
GALV	GALVANIZED
GC	GENERAL CONTRACTOR
GEN	GENERATOR
GFI	GROUND FAULT CIRCUIT INTERRUPTER
GND	GROUND
GTO	GENERATOR TRANSFER DEVICE
GUH	GAS UNIT HEATER
H	
HACR	HEATING, AIR CONDITIONING RATED CIRCUIT BREAKER
HD	ELECTRIC HAND DRYER
HD	HIGH INTENSITY DISCHARGE
HOA	HAND-OFF-AUTOMATIC
HORIZ	HORIZONTAL
HP	HORSEPOWER
HPS	HIGH PRESSURE SODIUM
HS	HAND SET
HSC	HAND SCANNER
HTG	HEATING
HTR	HEATER
HVAC	HEATING, VENTILATING, AND AIR CONDITIONING
HVU	HEATING/ VENTILATING UNIT
HWB	HOT WATER BOILER
HWC	HOT WATER CIRCULATOR
HWP	HEATING WATER PUMP
HZ	HERTZ
I	
ID	INSIDE DIAMETER
IG	ISOLATED GROUND
IN	INCH
INCAND	INCANDESCENT
INT	INTERNAL, INTERIOR
J	
JB	JUNCTION BOX
JP	JOCKEY PUMP
K	
KEC	KITCHEN EQUIPMENT CONTRACTOR
KO	KNOCKOUT
kVA	KILOVOLT- AMPS
kW	KILOWATT
kWh	KILOWATT-HOUR
L	
LED	LIGHT EMITTING DIODE
LF	LINEAR FEET
LRA	LOOKED ROTOR AMPS
LTG	LIGHTING
LVL	LOW VOLTAGE TRANSFORMER LEVEL
M	
MAP	METER
MATV	MASTER ALARM PANEL
MAX	MAXIMUM
MC	METAL CLAD CABLE
MCA	MINIMUM CIRCUIT AMPS
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER
MD	MOTORIZED DAMPER
MDP	MAIN DISTRIBUTION PANEL
MECH.	MECHANICAL
MFR	MANUFACTURER
MH	METAL HALIDE
MC	MICROPHONE
MIN	MINIMUM
MLO	MAIN LUGS ONLY
MCCP	MAXIMUM OVER-CURRENT PROTECTION
MSB	MAIN SWITCHBOARD
MTD	MOUNTED
MV	MERCURY VAPOR
N	
N3R	NEMA 3R ENCLOSURE
N4X	NEMA 4X ENCLOSURE
N.C.	NORMALLY CLOSED
NCO	NATIONAL ELECTRICAL CODE
NEMA	NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION
NF	NON-FUSED
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NFS	NON-FUSED SWITCH
NC	NOT IN CONTRACT
NL	NIGHT LIGHT
N.O.	NORMALLY OPEN
NO.	NUMBER
NTS	NOT TO SCALE
O	
OAF	OUTSIDE AIR FAN
OAHU	OUTSIDE AIR HANDLING UNIT ON CENTER
OD	OUTSIDE DIAMETER
OHE	OVERHEAD ELECTRICAL OPENING
OPG	OPENING
P	
BB	POLE, PUMP
BC	PUSHBUTTON
PC	PHOTOCELL
PH	PHASE
PL	PILOT LIGHT
PLBG	PLUMBING
PNEU	PNEUMATIC
PNL	PANEL
POS	POINT OF SALE
PP	POWER POLE
PR	PAIR
PR	PRIMARY
PS	PHOTOSENSOR
PVC	POLYVINYL CHLORIDE
PWR	POWER

Q	
R	
QTY	QUANTITY
S	
R	EXISTING TO BE REMOVED
RA	RETURN AIR
RAD	REFRIGERATED AIR DRYER
RAF	RETURN AIR FAN
RC	RECONNECT EXISTING DEVICE TO CIRCUIT INDICATED
RCP	REFLECTED CEILING PLAN
RCPT	RECEPTACLE
RE	REFERENCE, REFER
REC	RECEPTACLE
REFR	REFRIGERATOR
REINF	REINFORCING
REL	EXISTING TO BE RELOCATED
REL/EX	NEW LOCATION OF RELOCATED EQUIPMENT
REQD	REQUIRED
REV	REVISION, REVISE
RGS	RIGID GALVANIZED STEEL
RLA	RUNNING LOAD AMPS
RPM	REVOLUTIONS PER MINUTE
RR	REMOVE, AND REPLACE
RTU	ROOFTOP UNIT
T	
SA	SUPPLY AIR
SAP	SUPPLY AIR FAN
SCHED	SCHEDULE
SE	SEWAGE EJECTOR
SEC	SECONDARY
SECT	SECTION
IG	SQUARE FEET
SHT	SHEET
SM	SMILAR
SKVA	STARTING KILOVOLT-AMPS
SKW	STARTING KILOWATTS
SP	SPECIFICATION
SPEC	SPEAKER
SPF	STAIR PRESSURIZATION FAN
SPKR	SPEAKER
SPD	SURGE PROTECTION DEVICE
SPDT	SINGLE-POLE, DOUBLE-THROW
SPST	SINGLE-POLE, SINGLE-THROW
SQ.	SQUARE
SRF	SMOKE REMOVAL FAN
SS	START-STOP PUSH BUTTON
SSSC	SOLID STATE SPEED CONTROL
ST	SHUNT TRIP
STB	STEAM BOILER
STD	STANDARD
STL	STEEL
SURF	SURFACE
SW	SWITCH
SWBD	SWITCHBOARD
U	
TC	TEMPERATURE CONTROL
TEL	TELEPHONE
TF	TRANSFER FAN
TL	TRIM-LOOK
TCC	TOP OF CURB
TOS	TOP OF STEEL
TP	CHILD TAMPER PROOF DEVICE
TSTAT	THERMOSTAT
TTB	TELEPHONE TERMINAL BOARD
TTC	TELEPHONE TERMINAL CABINET
TU	TERMINAL UNIT
TV	TELEVISION
TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSOR
TYP	TYPICAL
V	
V	VOLT
VA	VOLT-AMPERE
VAV	VARIABLE AIR VOLUME
VC	VOLUME CONTROL
VERT	VERTICAL
VFD	VARIABLE FREQUENCY DRIVE
VP	VACUUM PUMP
VM	VOLT METER
W	
W	WATT, WIRE, WIDTH
WG	WIREGUARD
W/	WITH
W/O	WITHOUT
WP	WEATHERPROOF
WS	WATER SOFTENER
WT	WATERIGHT, WEIGHT
WWE	WELDED WIRE FABRIC
W/FT²	WATTS PER SQUARE FOOT
X	
XFMR	TRANSFORMER
Z	
Z	ZONE



ELECTRICAL SYMBOLS

MOTORS AND CONTROLS	
	SINGLE OR THREE PHASE MOTOR NUMBER INDICATES HORSE POWER
	DISCONNECT (SAFETY) SWITCH "200/3/150" DENOTES AMPERES/POLE/FUSE, "N" DENOTES NON-FUSED "N3R" DENOTES NEMA 3R
	ENCLOSED CIRCUIT BREAKER-- "200/3/150" DENOTES AMPERES/POLE/TRIP
	MOTOR STARTER FURNISHED BY DIVISION 23 AND INSTALLED BY DIVISION 26.
	COMBINATION DISCONNECT (SAFETY) SWITCH AND STARTER, "30/3/15/40" DENOTES AMPERES/POLES/FUSE/STARTER SIZE, "N" DENOTES NON-FUSED, FURNISHED BY DIVISION 23 AND INSTALLED BY DIVISION 26.
	VARIABLE FREQUENCY DRIVE PROVIDED BY DIVISION 23 AND INSTALLED BY DIVISION 26.
	EMERGENCY POWER OFF BUTTON.

RECEPTACLES AND OUTLETS

	SIMPLEX WALL RECEPTACLE, NEMA 5-20R, 20A, 125V.
	DUPLEX WALL RECEPTACLE, NEMA 5-20R, 20A, 125V.
	DUPLEX WALL RECEPTACLE ON EMERGENCY CIRCUIT, RED COLOR.
	DUPLEX WALL RECEPTACLE ON A CIRCUIT DEDICATED TO DATA PROCESSING, GRAY COLOR. PROVIDE ISOLATED GROUND TYPE RECEPTACLES WHERE NOTED.
	SPLIT WIRED RECEPTACLE. TOP RECEPTACLE SHALL BE SWITCHED ACCORDING TO PLANS, AND BOTTOM SHALL REMAIN UNSWITCHED.
	CONTROLLED DUPLEX WALL RECEPTACLE, NEMA 5-20R, 20A, 125V. "SP" DENOTES SPLIT WIRED
	FOURPLEX (DOUBLE DUPLEX) WALL RECEPTACLE, NEMA 5-20R, 20A, 125V.
	FOURPLEX WALL RECEPTACLE ON EMERGENCY CIRCUIT, RED COLOR.
	CONTROLLED FOURPLEX (DOUBLE DUPLEX) WALL RECEPTACLE, NEMA 5-20R, 20A, 125V.
	SPECIAL RECEPTACLE, NEMA CONFIGURATION AS NOTED.
	FLUSH ELECTRICAL FLOOR OUTLET, "P" DENOTES POKE-THRU, "D" INDICATES DUPLEX RECEPTACLE, "R" INDICATES RED RECEPTACLE ON EMERGENCY POWER. REFER TO FLOOR BOX SCHEDULE, FIRE RATED POKE-THROUGH SCHEDULE AND KEYED NOTES.
	MULTI-OUTLET SURFACE RACEWAY. SEE ARCHITECTURAL DRAWINGS FOR EXACT MOUNTING HEIGHTS.
	JUNCTION BOX "MD" DENOTES MOTOR DAMPER, "C" DENOTES CORD REEL, "D" DENOTES DROP CORD RECEPTACLE.
	DUPLEX RECEPTACLE WITH HOMERUN
	DUPLEX RECEPTACLE (PEDESTAL MOUNTED)
	TWO-GANG CEILING OUTLET
	TWO-GANG FLOOR OUTLET
	THREE-GANG FLOOR OUTLET
	POWER POLE
	DIRECT CONNECTION TO EQUIPMENT
	PULL BOX (OVER 4" SQUARE)
	CLOCK RECEPTACLE TO BE MOUNTED 12" BELOW FINISHED CEILING. (2) DENOTES DOUBLE SIDED CLOCK.

LIGHTING

LETTER(S) DENOTE TYPE-- SEE LIGHTING FIXTURE SCHEDULE FOR ADDITIONAL INFORMATION.	
	2' X 4' LIGHTING FIXTURE.
	2' X 2' LIGHTING FIXTURE.
	1' X 4' LIGHTING FIXTURE.
	1' X 2' LIGHTING FIXTURE.
	1' X 1' LIGHTING FIXTURE.
	STRIP LIGHTING FIXTURES.
	STAGGERED STRIP LIGHTING FIXTURE.
	ROUND DOWNLIGHT FIXTURE.
	SQUARE DOWNLIGHT FIXTURE.
	WALL MOUNTED LIGHTING FIXTURE.
	TRACK LIGHTING FIXTURE, MOUNTED AS SHOWN ON LIGHTING FIXTURE SCHEDULE.
	CEILING MOUNTED EXIT SIGN; ARROWS AS INDICATED. SHADED AREA DENOTES FACE.
	WALL MOUNTED EXIT SIGN; ARROWS AS INDICATED. SHADED AREA DENOTES FACE.
	EMERGENCY WALL MOUNTED LIGHTING FIXTURE. BATTERY OPERATED UNLESS NOTED OTHERWISE.
	SECURITY WALL PACK
	SITE LIGHTING FIXTURE.
	POST-TOP FIXTURE/ACORN FIXTURE BRACKET ARM INDICATES WALL MOUNT WITH ARM
	EMERGENCY LIGHT FIXTURE WITH BATTERY PACK. PROVIDE WITH UNSWITCHED HOT FOR LOSS OF VOLTAGE AND CHARGING (SAME CIRCUIT AS NORMAL POWER LIGHTING). FIXTURES SHALL BE WIRED IN A MANNER AS TO ALLOW SWITCHING OF FIXTURES WITHOUT DISCHARGING THE EMERGENCY BATTERY. BATTERY PACK IS TO ONLY OPERATE IN THE EVENT OF A POWER OUTAGE.
	LIGHT FIXTURE ON EMERGENCY BRANCH CIRCUIT. CIRCUIT NUMBER ADJACENT TO FIXTURE INDICATES EMERGENCY CIRCUIT CONNECTED TO FIXTURE. PROVIDE UNSWITCHED HOT, NEUTRAL AND GROUND FOR ALL EMERGENCY LIGHTING ORIGINATING FROM THE EMERGENCY CIRCUIT SHOWN.
	EMERGENCY "NIGHT LIGHT" LIGHT FIXTURE. LIGHT FIXTURE IS UNSWITCHED AND INTENDED FOR 24 HOUR OPERATION. FEED VIA UNSWITCHED HOT.

RACEWAYS AND WIRING	
	CAP AND STAKE
	CONDUIT CONCEALED IN WALL OR CEILING
	CONDUIT UNDERGAS OR UNDERGROUND
	EMERGENCY CONDUIT
	EXPOSED CONDUIT
	UNDERGROUND CONDUIT, "DB" DENOTES DUCTBANK ENCASED IN CONCRETE
	OVERHEAD ELECTRIC PRIMARY UTILITY POWER LINE
	CONDUIT TURNED UP
	CONDUIT TURNED DOWN
	HASH MARKS INDICATE NUMBER OF CONDUCTORS. LEFT TO RIGHT: PHASE/NEUTRAL/SWITCH LEG/GROUND/ISOLATED GROUND. NO HASH MARKS INDICATES 2# 12, PLUS GROUND, UNLESS NOTED OTHERWISE.
	HOMERUN TO PANEL WITH CIRCUIT NUMBER(S) AS INDICATED.
	PARTIAL CIRCUIT HOMERUN TO PANEL.
	COMMUNICATIONS CONDUIT OR CABLE: "CL" DENOTES MASTER CLOCK, "CR" DENOTES CASH REGISTER, "D" DENOTES DATA, "FA" DENOTES FIRE ALARM, "I" DENOTES INTERCOM, "OHE" DENOTES OVERHEAD ELECTRICAL LINE, "PA" DENOTES PAGING, "SP" DENOTES SECURITY, "T" DENOTES TELEPHONE, "V" DENOTES VIDEO.
	TELECOMMUNICATIONS CABLE TRAY TO BE CONCEALED ABOVE ACCESSABLE CEILING.

ELECTRICAL EQUIPMENT


	DISTRIBUTION PANEL
	SWITCHBOARD, MAIN DISTRIBUTION PANEL OR MOTOR CONTROL CENTER
	PANELBOARD (FLUSH/SURFACE MOUNT)
	FLOOR MOUNTED DRY-TYPE TRANSFORMER
	SUSPENDED OR WALL MOUNTED TRANSFORMER
	AUTOMATIC TRANSFER SWITCH
	FIRE RATED PLYWOOD TERMINAL BOARD, TYPE AS NOTED, 4" X 8" X 3/4" UNLESS NOTED OTHERWISE
	TERMINAL CABINET (FLUSH/SURFACE MOUNT), TYPE AS NOTED, 24" X 48" X 3-1/2" UNLESS NOTED OTHERWISE.
	BATTERY/INVERTER UNIT
	LOW VOLTAGE TRANSFORMER.

COMMUNICATIONS

ALL OUTLET BOXES SHALL BE MOUNTED 18" ABOVE FINISHED FLOOR TO CENTER OF DEVICE UNLESS NOTED OTHERWISE.	
THE FOLLOWING NOTATIONS REFER TO ALL COMMUNICATIONS OUTLETS: "FAX" DENOTES OUTLET DEDICATED FOR A FAX, "W" DENOTES WALL PHONE SHALL BE MOUNTED AT 42" A.F.F., "PAY" DENOTES PAY PHONE SHALL BE MOUNTED 42" A.F.F.	
	SCHOOL INTERCOMMUNICATION SYSTEM HANDETS.
	INDICATES THE LOCATION OF A NEW TECHNOLOGY WALL OUTLET, PROVIDE DUAL GANG BOX. REFERENCE TECHNOLOGY SHEET FOR CONTENT.
	MICROPHONE FLOOR OUTLET, "W" INDICATES WALL MOUNTED "F" INDICATES FLOOR MOUNTED "H" INDICATES HANGING MOUNTED
	CEILING MOUNTED SPEAKER. "VC" INDICATES VOLUME CONTROL ON SPEAKER.
	WALL MOUNTED SPEAKER. "L" INDICATED LOCAL SOUND REINFORCEMENT
	SCHOOL INTERCOMMUNICATION SYSTEM CALL-IN. PUSH BUTTON
	BELL, BUZZER OR CHIME AT 80+ A.F.F.
	VOLUME CONTROL - WALL MOUNTED
	AUXILIARY INPUT JACK. "W" INDICATES WALL MOUNTED "F" INDICATES FLOOR MOUNTED "H" INDICATES HANGING MOUNTED
	"HIGH" PORTION OF "HIGH/LOW" OUTLETS, REFER TO OUTLET DETAIL.
	"LOW" PORTION OF "HIGH/LOW" OUTLETS, REFER TO OUTLET DETAIL.
REFERENCE TECHNOLOGY/SECURITY SHEET FOR ADDITIONAL INFORMATION.	

ONE LINE AND RISER DIAGRAMS

	TRANSFORMER, TYPE AND RATINGS AS NOTED
	SWITCH, RATING AS SHOWN
	FUSE, RATING AS SHOWN
	CIRCUIT BREAKER, RATING AS SHOWN, 3 POLE UNLESS NOTED OTHERWISE. "CL" DENOTES CURRENT LIMITING
	DRAWOUT CIRCUIT BREAKER, RATINGS AS SHOWN, 3 POLE UNLESS NOTED OTHERWISE
	SHUNT TRIP
	GROUND FAULT RELAY
	KIRK-KEY INTERLOCK
	DIGITAL METER
	AMMETER, RANGE AS SHOWN
	AMMETER SWITCH
	VOLTMETER, RANGE AS SHOWN
	VOLTMETER SWITCH
	WATT-HOUR METER, "D" DENOTES DEMAND REGISTER "15" DENOTES MINUTES OF DEMAND



- ELECTRICAL KEYED NOTES: ① →
1. APPROXIMATE LOCATION OF EXISTING TRANSFORMER AT PERFORMING ARTS. FIELD COORDINATE CONNECTION AND POWER COMPANY REQUIREMENTS PRIOR DIGGING.
 2. PROPOSED ROUTING FOR MULTIPURPOSE BUILDING ELECTRICAL SERVICE DUCT BANK. REFER TO ONE LINE DIAGRAM ON SHEET E2.0 FOR ADDITIONAL INFORMATION.
 3. PROVIDE (2) 4" UNDERGROUND CONDUIT WITH PULLSTRING FOR COMMUNICATIONS SERVICES. FIELD COORDINATE ADDITIONAL INFORMATION WITH SERVICE PROVIDER AND TECHNOLOGY CONTRACTOR.



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

ELECTRICAL
SITE PLAN -
EDINBURG
HIGH


E1.0

1
E1.0 ELECTRICAL SITE PLAN - EDINBURG HIGH
Scale: 1/64" = 1'-0"

5/16/25

ISSUED FOR PERMIT

1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25



1
E1.1
ELECTRICAL POWER FLOOR PLAN - TYPICAL BLDG.
Scale: 3/16" = 1'-0"

ELECTRICAL KEYED NOTES:

1. PROVIDE 120V POWER FOR MOTORIZED OVERHEAD DOOR. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH DOOR INSTALLER PRIOR TO PLACEMENT. PROVIDE MOTOR RATED SWITCH.
2. PROVIDE BACK BOX FOR UP/DOWN PUSHBUTTON CONTROL STATION FOR MOTORIZED OVERHEAD DOOR. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH DOOR INSTALLER PRIOR TO ROUGH-IN. ROUTE (1) 3/4" CONDUIT WITH CONTROL WIRE TO MOTORIZED DOOR CONTROL BOX.
3. PROVIDE HUBBELL 4-GANG FLOOR BOX #CFBG30RCR WITH (2) # PWFBMPCR20GRYTR DUPLEX RECEPTACLES, #CFBHUB2 HUB AND #CFBSIR8CVXX COVER. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH ARCHITECT AND OWNER PRIOR TO PLACEMENT. ROUTE (1) 3/4" UNDERGROUND CONDUIT FOR POWER WIRING AND (1) 2" UNDERGROUND CONDUIT WITH PULL-STRING FOR DATA CABLE TO NEAREST WALL AND UP TO STRUCTURE.
4. PROVIDE 60A/3P/NF/N3R SAFETY DISCONNECT FOR ROOF TOP UNIT. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH MECHANICAL CONTRACTOR PRIOR TO PLACEMENT.
5. PROVIDE FIRE ALARM SYSTEM SHUT DOWN RELAY FOR HVAC EQUIPMENT. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH MECHANICAL CONTRACTOR PRIOR TO PLACEMENT.
6. PROVIDE DUCT SMOKE DETECTOR FOR HVAC EQUIPMENT SHUT DOWN. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH MECHANICAL CONTRACTOR PRIOR TO PLACEMENT.
7. PROPOSED LOCATION FOR SERVICE EQUIPMENT AND POWER COMPANY METERING GEAR. REFER TO ONE LINE DIAGRAM AND SITE PLANS FOR ADDITIONAL INFORMATION.
8. PROVIDE QUAD RECEPTACLE AND DATA OUTLET FOR I.T. RACK. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH TECHNOLOGY CONTRACTOR PRIOR TO PLACEMENT.
9. PROVIDE QUAD RECEPTACLE AND DATA OUTLET FOR SOUND EQUIPMENT. FIELD COORDINATE EXACT LOCATION AND ADDITIONAL REQUIREMENTS WITH AV CONTRACTOR PRIOR TO ROUGH-IN.

ELECTRICAL GENERAL NOTES:

- A. ELECTRICAL CONTRACTOR SHALL GROUP HOMERUNS WITH THREE HOTS (A,B, AND C PHASE), AND #10 NEUTRAL TO PROVIDE MULTI-WIRE BRANCH CIRCUITS. NO MORE THAN 2 MULTI-WIRE HOMERUNS PER CONDUIT. CONTRACTOR SHALL PROVIDE HANDLE TIES MANUFACTURED BY THE SWITCH GEAR SUPPLIER ON ALL MULTI-WIRE CIRCUITS TO MEET THE REQUIREMENTS OF ARTICLE 210.4(B) OF THE 2020 NEC. AT THE CONTRACTOR'S OPTION, TWO AND THREE POLE BREAKERS MAY BE USED.
- B. CONTRACTOR SHALL VERIFY DEVICE LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN. REFER TO ARCHITECTURAL CASEWORK AND MILLWORK ELEVATIONS.
- C. ELECTRICAL CONTRACTOR SHALL PROVIDE CONDUIT, OUTLET BOXES, JUNCTION BOXES FOR ALL TECHNOLOGY DEVICE OUTLETS. REFER TO DIVISION 26 SPECIFICATIONS AND TECHNOLOGY DRAWINGS FOR ALL WORK REQUIRED.
- D. ELECTRICAL CONTRACTOR SHALL COORDINATE WITH MECHANICAL CONTRACTOR FOR ALL EXHAUST FAN CONTROLS. PROVIDE A FAN SWITCH IF INDICATED BY MECHANICAL. ALL EXHAUST FANS SHALL BE PROVIDED WITH BUILT-IN DISCONNECT SWITCH.
- E. HVAC AND PLUMBING EQUIPMENT MAY DIFFER FROM LOCATIONS AS SHOWN ON ELECTRICAL DRAWINGS. COORDINATE EXACT LOCATIONS WITH MECHANICAL AND PLUMBING CONTRACTOR.
- F. CONTRACTOR SHALL INDICATE CIRCUIT SERVING EACH RECEPTACLE BY PROVIDING TYPE WRITTEN LABELING LOCATED ON INSIDE FACE OF EACH RECEPTACLE COVER PLATE.
- G. ELECTRICAL CONTRACTOR SHALL ROUTE ELECTRICAL CONDUIT AND WIRING TO ALL ROOF HVAC EQUIPMENT THROUGH ROOF CURBS. ELECTRICAL CONTRACTOR SHALL COORDINATE WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN.
- H. CONTRACTOR SHALL ARRANGE PANELBOARDS IN ELECTRICAL ROOM TO PROVIDE CLEARANCE PER NEC 110.26.
- I. MECHANICAL CONTRACTOR SHALL FURNISH INTEGRAL DISCONNECT SWITCH FOR ALL MECHANICAL EQUIPMENT. ELECTRICAL CONNECTIONS SHALL BE PROVIDED BY DIVISION 26.
- J. VAVS WITH DAMPER ONLY SHALL BE CONNECTED BY MECHANICAL CONTRACTOR.
- K. PROVIDE JUNCTION BOX AND POWER FOR ALL HARD WIRED PLUMBING FLUSH VALVES AND SENSOR EQUIPMENT TRANSFORMERS FROM NEAREST 120V/20A CIRCUIT. COORDINATE WITH PLUMBER PRIOR TO ROUGH-IN FOR EXACT LOCATION.
- L. ALL RECEPTACLES LOCATED IN RESTROOMS, JANITOR CLOSETS, MECHANICAL ROOMS, SERVING ELECTRIC DRINKING FOUNTAINS OR VENDING MACHINES, LOCATED WITHIN 6' OF A SINK, LOCATED ABOVE A WET COUNTERTOP OR IN A KITCHEN OR COFFEE BAR SHALL BE GFCI. EACH GFCI PROTECTED RECEPTACLE SHARING THE SAME CIRCUIT SHALL HAVE ITS OWN RE-SET AND TEST BUTTON.



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

**ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74**

**EDINBURG
HIGH SCHOOL**


2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD


REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

**ELECTRICAL
POWER
FLOOR PLAN -
TYPICAL BLDG.**



E1.1



- ELECTRICAL KEYED NOTES:**
- 1. PROVIDE MOMENTARY CONTACT SWITCH ROUTED TO INTERIOR LIGHTING LIGHTING CONTACTOR.

- ELECTRICAL GENERAL NOTES:**
- A. ALL CEILING MOUNTED OCCUPANCY SENSORS SHALL BE HUBBELL (WATTSTOPPER) #OMDT-2000 (#DT-300). PROVIDE (#BZ-50 UNIVERSAL VOLTAGE) POWER PACKS AND OVERRIDE SWITCHES AS REQUIRED FOR CONTROL INDICATED.
 - B. ALL WALL MOUNTED OCCUPANCY SENSORS SHALL BE HUBBELL (WATTSTOPPER) #HMTST (DSW-100)..
 - C. ALL CEILING MOUNTED DEVICES LOCATED IN LAY-IN CEILINGS SHALL BE CENTERED IN THE CEILING TILE.
 - D. ALL WALL BOX DIMMERS SHALL BE LUTRON NT SERIES UNLESS NOTED OTHERWISE.
 - E. MULTIPLE SWITCHES SHOWN TOGETHER SHALL BE GANGED UNDER A COMMON COVER PLATE.
 - F. PROVIDE UN-SWITCHED CIRCUIT TO ALL EXIT SIGNS.
 - G. CONTRACTOR SHALL INDICATE LIGHTING CIRCUIT CONTROLLED BY EACH SWITCH BY PROVIDING TYPE WRITTEN LABELING LOCATED ON INSIDE FACE OF EACH SWITCH COVER PLATE.
 - H. SPRINKLER CONTRACTOR SHALL COORDINATE SPRINKLER HEAD LOCATIONS WITH CEILING MOUNTED LIGHTING FIXTURES.
 - I. FIXTURES DESIGNATED "NL" SHALL BE UNSWITCHED NIGHTLIGHT. FIXTURES SHALL BE CONNECTED TO EMERGENCY CIRCUIT INDICATED.
 - J. PROVIDE ALL EMERGENCY LIGHT FIXTURES WITH UNSWITCHED HOT LEG AS DEFINED IN NEC 700.12
 - K. ROUTE AN UNSWITCHED HOT LEG TO ALL LIGHT FIXTURES DESIGNATED AS EMERGENCY FIXTURES. HOT LEG SHALL ORIGINATE FROM CIRCUIT SERVING NORMAL LIGHTING FIXTURES IN THAT SPACE. UNSWITCHED HOT LEG SHALL CONNECT TO THE NORMAL POWER SENSING LUG ON THE EMERGENCY BATTERY PACK.
 - L. LOWER CASE CHARACTER ADJACENT TO SWITCH AND/OR LIGHTING FIXTURE INDICATES SWITCHING GROUP.



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:		
No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25


**ELECTRICAL
LIGHTING
FLOOR PLAN -
TYPICAL BLDG.**

5/16/25

ISSUED FOR PERMIT

1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25

E1.2



ELECTRICAL KEYED NOTES:

1. PROVIDE METER DISCONNECT SWITCH PER POWER COMPANY SERVICE STANDARDS. FIELD COORDINATE ADDITIONAL REQUIREMENTS WITH POWER COMPANY.
2. PROVIDE 320A METER CAN PER POWER COMPANY SERVICE STANDARDS. REFER TO POWER PLANS FOR PROPOSED LOCATION.
3. PROVIDE FUSED SERVICE DISCONNECT PER POWER COMPANY SERVICE STANDARDS. REFER TO POWER PLANS FOR PROPOSED LOCATION.

TRANSFORMER SCHEDULE						
MARK	KVA	PRI. VOLTAGE	SECONDARY VOLTAGE	MOUNTING	REMARKS	PHASE SHIFT
TLA	30	480V, 3Ø	120Y/208V, 3Ø, 4 W	FLOOR	GENERAL PURPOSE TRANSFORMER. PROVIDE WITH DRIP-SHIELD	--

SPD SCHEDULE			
MARK	MANUFACTURER	MODEL	ACCUGUIDE CABLE SIZE
SPD-1	SOUTHERN TIER TECHNOLOGIES	T45277Y125ALAM1C	5 #6, 1 1/2" C.
SPD-2	SOUTHERN TIER TECHNOLOGIES	T45120Y100AWAJ2S	5 #10, 3/4" C.

Edinbug CISD Multipurpose Building - Load Analysis									
Voltage		Load Type	Date: 5/16/2025		Units	Qty Of Floors	Load (KVA)		Notes
480			Qty	Unitary Load			Per Floor	Total	
Total Square Footage									
5400									
Load Description									
Exterior Lighting		EL	1	750.00	VA	1	0.00	0.0	
Lighting Load		L	5,400	2.00	VA/SF	1	0.75	0.8	
Receptacles		R	16	180.00	VA	1	10.80	10.8	
							2.88	2.9	
							0.00	0.0	
HVAC							0.00	0.0	
Electrical Heating		H	5,400	12.50	VA/SF	1	67.50	67.5	
Cooling		C	5,400	10.60	VA/SF	1	57.24	57.2	
Fans		MS	5,400	2.00	VA/SF	1	10.80	10.8	

LIGHTING FIXTURE SCHEDULE							
TYPE	MANUFACTURER	MOUNTING	LAMPS	VOLTS	WATTS	REMARKS	NOTES
H1	DAY-BRITE LIGHTING HCY2437LBCST-UN3-DIM	PENDANT	4000K L.E.D. INCLUDED	UNIVERSAL	150	L.E.D. HIGH BAY WITH 24,000 LUMENS OUTPUT, 0-10V DIMMING DRIVER. PROVIDE WITH #HCY2437L REFLECTOR AND #HCY2437L WIRE GUARD.	
H1E	DAY-BRITE LIGHTING HCY2437LBCST-UN3-DIM-EM	PENDANT	4000K L.E.D. INCLUDED	UNIVERSAL	150	SAME AS H1. PROVIDE WITH BODINE #ELI SERIES INVERTER, RATED FOR 90-MINUTE BATTERY RUNNING TIME.	
H2	STONCO LIGHTING LPGCA05-840-SCD-SUR-UNV-BL20MW	SURFACE	4000K L.E.D. INCLUDED	UNIVERSAL	60	L.E.D. CANOPY LIGHT WITH 10,000 LUMENS OUTPUT, BI-LEVEL DOWN TO 20% DIMMING DRIVER. PROVIDE WITH MICROWAVE MOTION SENSOR.	
H2	STONCO LIGHTING LPGCA05-840-SCD-SUR-UNV-BL20MW-BR-EM	SURFACE	4000K L.E.D. INCLUDED	UNIVERSAL	60	SAME AS H2. PROVIDE WITH EMERGENCY BY-PASS RELAY AND BODINE #ELI SERIES INVERTER, RATED FOR 90-MINUTE BATTERY RUNNING TIME.	
W1	STONCO LIGHTING LPW16-50-NW-G3-4-UNV	WALL	4000K L.E.D. INCLUDED	UNIVERSAL	50	L.E.D. SCONCE WITH 5,263 LUMEN OUTPUT	
W1E	STONCO LIGHTING LPW16-50-NW-G3-4-UNV-BAC	WALL	4000K L.E.D. INCLUDED	UNIVERSAL	50	SAME AS W1. PROVIDE WITH EMERGENCY BATTERY PACK RATED FOR 90-MINUTE RUNNING TIME.	
X1	CHLORIDE LIGHTING CLX-N-RW	UNIVERSAL	RED L.E.D. FURNISHED	120/277	5.0	SINGLE FACED EXIT SIGN WITH RED LETTERS ON WHITE PANEL AND EXTRA STENCIL FOR DOUBLE FACED APPLICATIONS. PROVIDE WITH WIREGUARD.	
X2	CHLORIDE LIGHTING CLX-N-RW	UNIVERSAL	RED L.E.D. FURNISHED	120/277	5.0	DOUBLE FACED EXIT SIGN WITH RED LETTERS ON WHITE PANEL. PROVIDE WIREGUARD.	

Panelboard LA																	
65,000 AIC Rating Existing X New																	
120/208 Volt, 3-Phase, 4-Wire 1 Section N3R -Nema Rating						X	MCB MLO	100	AMP MCB AMP BUS (Copper) ISO GRND. BUS	X Single Double Feed - Thru						Mounting Surface X Flush	
Notes	Load (VA)	Description	Type	Wire	CB	CKT #	A	B	C	#	CKT #	CB	Wire	Type	Description	Load (VA)	Notes
	540	RC - MP AREA	R	12	20/1	1	●				2	20/1	12	R	RC - IT RACK	1200	
	720	RC - MP AREA	R	12	20/1	3					4	20/1	12	R	RC - SOUND RACK	1200	
	540	RC - MP AREA	R	12	20/1	5				●	6				SPACE		
	540	RC - MP AREA	R	12	20/1	7	●				8				SPACE		
	900	RC - MP AREA	R	12	20/1	9				●	10				SPACE		
		SPARE			20/1	11					12				SPACE		
		SPARE			20/1	13	●				14	20/1			SPARE		
		SPARE			20/1	15					16	20/1			SPARE		
		SPARE			20/1	17				●	18	20/1			SPARE		
		SPARE			20/1	19	●				20	20/1			SPARE		
		SPARE			20/1	21				●	22	20/1			SPARE		
		SPARE			20/1	23				●	24	20/1	12	M	EQ - FACP	500	
		SPARE			20/1	25					26	30/2	10		SPD-2		
	1127	EQ - MOT. OH DOOR	M			27		●			28	-	10		-		
	1127	EQ - MOT. OH DOOR	M			29				●	30	-	10		-		
	5,494	Subtotal													Subtotal	2,900	
N.E.C.		Load Type	Conn.	Fct.	Diversity	N.E.C.		Conn.		Fct.	Diversity						
220.44	(R) Recept.	5,640			5,640	210.20(a)		(L) Lighting		0	125%	0					
220.56	(K) Kitchen	0	100%	0	0			(EL) Ext. Ltg.		0	125%	0					
220.60	(C) Cooling	0	0%	0	0	620.14		(E) Elevators		0	100%	0					
220.60	(H) Heating	0	0%	0	0			(WH) Water Ht.		0	100%	0					
220.60	(F) Fans	0	100%	0	0	220.5		(MT) Lrg. Mot.		0	125%	0					
	(M) Misc.	2,754	100%	2,754	0			(SP) Sub Panel		0	100%	0					
610.50	(CR) Cranes	0	100%	0	0												
Total Connected Load				8,394 VA =		23.3		AMPS		Location of Panel:							
Total Load (Diversified)				8,394 VA =		23.3		AMPS									

Panelboard HA																		65,000 AIC Rating Existing X New			
277/480 Volt, 3-Phase, 4-Wire 1 Section N3R -Nema Rating						X	MCB	400	AMP MCB AMP BUS (Copper) ISO GRND. BUS				X Single Double Feed - Thru				Mounting Surface X Flush				
Notes	Load (VA)	Description	Type	Wire	CB	CKT	#	A	B	C	CKT	#	CB	Wire	Type	Description	Load (VA)	Notes			
1	2400	LT - INTERIOR	L	12	20/1	1					2		20/1	12	L	LT - EXIT SIGNS	250				
	2400	LT - INTERIOR	L	12	20/1	3					4										
2	600	LT - EXT. CANOPY	EL	12	20/1	5					6										
3	300	LT - EXT. WALL	EL	12	20/1	7					8										
						9					10										
						11					12										
						13					14										
						15					16										
						17					18										
						19					20										
						21					22										
						23					24										
						25					26										
						27					28										
		SPACE				29					30										
	3824	RTU-1	F	8	50/3	31					32										
	18000	-	H	8	-	33					34										
	-	-	C	8	-	35					36										
	3824	RTU-2	F	8	50/3	37					38	70/3	4	SP	XFMR - TLA	8394					
	18000	-	H	8	-	39					40	-	4	-	-						
	-	-	C	8	-	41					42	-	4	-	-						
	49,348	Subtotal															8,644				
N.E.C.		Load Type	Conn.	Fct.	Diversity	N.E.C.		Conn.		Fct.	Diversity										
220.44	(R) Recept.	0				210.20(a)		(L) Lighting		0,050	125%	6,313									
220.56	(K) Kitchen	0	100%	0				(EL) Ext. Ltg.		900	125%	1,125									
220.60	(C) Cooling	0	0%	0		620.14		(E) Elevators		0	100%	0									
220.60	(H) Heating	36,000	100%	36,000				(WH) Water Ht.		0	100%	0									
220.60	(F) Fans	7,648	100%	7,648		220.5		(MT) Lrg. Mot.		0	125%	0									
	(M) Misc.	0	100%	0				(SP) Sub Panel		8,394	100%	8,394									
610.50	(CR) Cranes	0	100%	0																	
Total Connected Load						57,992 VA =		69.8		AMPS		Location of Panel:									
Total Load (Diversified)						59,480 VA =		71.6		AMPS											


PANELBOARD SCHEDULE KEYED NOTES:

1. ROUTE VIA LIGHTING CONTACTOR LC1.
2. ROUTE VIA LIGHTING CONTACTOR LC2.
3. ROUTE VIA LIGHTING CONTACTOR LC3

TIME CLOCK SCHEDULE					
MARK	AMPS	CIRCUITS	COIL VOLTAGE	NOTE	REMARKS
TC-1	20	16	120/277	1	
NOTE #1. ALL TIME CLOCKS SHALL BE INTERMATIC ET90000, SERIES RATED FOR 20 AMP, 277 VOLT BALLAST SWITCHING.					
ZONE CIRCUITS: SITE, EXTERIOR WALLS, ENTRANCES, FLAG POLES/SIGNS & BAYS. PROVIDE OVERRIDE SWITCH AT REAR DOOR.					

CONTACTOR SCHEDULE					
MARK	AMPS	POLES	COIL VOLTAGE	CONTROL	REMARKS
LC1	30	6	120	H-O-A, \$ ⁴⁰⁰	AUTOMATIC CONTROL BY TIME SWITCH TC-1- SERVES INTERIOR LIGHTING
LC2	30	4	120	H-O-A, \$ ⁴⁰⁰	AUTOMATIC CONTROL BY TIME SWITCH TC-1- SERVES EXTERIOR CANOPY
LC3	30	4	120	H-O-A, \$ ⁴⁰⁰	AUTOMATIC CONTROL BY TIME SWITCH TC-1- SERVES EXTERIOR WALL

5/16/25



ISSUED FOR PERMIT

VME
ENGINEERING

1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:

EDINBURG CISD


REVISION:

No.	Description	Date


PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

ELECTRICAL
SCHEDULES


E3.0




1 TYPICAL DEVICE ELEVATIONS
NOT TO SCALE E11001




2 GROUNDING ELECTRODE SYSTEM AND BONDING DETAIL
NOT TO SCALE E13042




3 BACK-TO-BACK OUTLETS
NOT TO SCALE E13022




4 UNISTRUT CONDUIT DETAIL
NOT TO SCALE E10003




5 1 AND 2 HR. GYPSUM/WALLBOARD PIPE PENETRATION
NOT TO SCALE E10017




6 PIPE AND/OR CONDUIT PENETRATION
NOT TO SCALE E10018




7 TYP. RACEWAY CONFIGURATION USING METAL CLAD (MC) CABLE
NOT TO SCALE E18006




8 HORIZONTAL RECEPTACLE MOUNTING DETAIL
NOT TO SCALE E13016




9 TYPICAL RECEPTACLE MOUNTING DETAIL
NOT TO SCALE E13018




10 LINE VOLTAGE WALL MOUNTED OCCUPANCY SENSOR.
NOT TO SCALE EW2502



11 CEILING MOUNTED OC SENSOR WIRING DETAIL - 1 ON/OFF ZONE
NOT TO SCALE



12 ROOF MOUNTED RECEPTACLE
NOT TO SCALE E13023



13 DISCONNECT SWITCH MOUNTING AT CONCRETE PAD
NOT TO SCALE E13014



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:
EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

ELECTRICAL
DETAILS



E4.0



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CG5ARCHITECT.COM

SEAL:

ECISD HIGH
SCHOOL
ATHLETIC
MULTI-USE
BUILDING
25-74

EDINBURG
HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:

EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

ELECTRICAL
SPECIFICATIONS

5/16/25



ISSUED FOR PERMIT



E N G I N E E R I N G

1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25

E5.0

SECTION 26 00 00
ELECTRICAL SPECIFICATIONS

PART 1: GENERAL – ELECTRICAL

1-1 DESCRIPTION:

All work on these drawings shall be done in strict accordance with these specifications. All work fairly implied as essential to the complete functioning of the electrical systems shown on the Drawings and Specifications shall be completed as part of the work of this Division unless specifically stated otherwise. It is the intention of the Drawings and Specifications to establish the types of the systems, but not set forth each item essential to the functioning of the system. In case of doubt as to the work intended, or in the event of amplification thereof, the Contractor shall call upon the Architect for supplementary instructions, Drawings, etc. Refer to landord s criteria for additional requirements and include in bid.

1-2 WARRANTY:

The undertaking of the work described in this Division shall be considered equivalent to the issuance, as part of this work, of a specific guarantee extending one year beyond the date of completion of work and acceptance by Owner, against defects in materials and workmanship. Materials, appliances and labor necessary to effect repairs and replacement so as to maintain said work in good functioning order shall be provided as required. Replacements necessitated by normal wear in use or by Owner's abuse are not included under this guarantee.

1-3 PROJECT CONDITIONS:

Visit the site of the proposed construction in order to fully understand the facilities, difficulties and restriction attending the execution of the work. No additional compensation will be allowed this Contractor for work or items omitted from his original Proposal due to his failure to inform himself regarding such matters affecting the performance of the work in this Contract or necessary for the installation and completion of the work included herein.

1-4 PERMITS AND FEES:

The contractor shall arrange and pay for all permits, fees, tests, and all inspections as required by governmental authorities.

1-5 COORDINATION WITH FIELD CONDITIONS:

Contractor shall review all pertinent Drawings and adjust his work to all conditions shown there on. Discrepancies between Plans, Specifications, and actual field conditions shall be brought to the prompt attention of the Architect.

Approximate location of transformers, feeders, branch circuits, lighting and power outlets panels, outlets for special systems, etc., are indicated on the Drawings. However, the Drawings, do not give complete and accurate detailed locations of such outlets, conduit runs, etc., and exact locations must be determined by actual field measurement. Such locations will, at all times, be subject to the approval of the Architect.

Communicate with the Architect and secure his approval of any outlet (light fixture, receptacle, switch, etc.) location about which there may be the least question. Outlets obviously placed in a location not suitable to the finished room or without specific approval, shall be removed and relocated when so directed by the Architect. Location of light fixtures shall be coordinated with reflected ceiling plans.

1-6 SUBMITTALS:

Contractor shall provide six sets of submittals, shop drawings, descriptive literature, physical data and a specification critique for the following items:

Panelboards
Wiring Gutters
Heavy Duty Disconnect Switches
Lighting Fixtures and Lamps
Lighting Contactors
Time Clocks
Photocells
Wiring Devices and Plates
Conduit and Fittings
Wire
Fire Alarm System
Transformers
Lighting Controls
Generator
Automatic Transfer Switch

Any deviations from the specified items shall be listed on the cover sheet and clearly itemized for all deviations. The contractor shall provide two copies of owner's manuals to the architect upon completion of the work.

1-7 SUBSTITUTIONS

A. The names, manufacturers, and model numbers have been used in the Contract documents to establish types of equipment and standards of quality. Where more than one manufacturer is named for a specific item of equipment, only one of the specified manufacturers will be considered for approval. Where only one manufacturer is mentioned with the phrase "or approved equal", Contractor may submit an alternate manufacturer for consideration, provided the following conditions are met:

1. Submit alternate equipment with complete descriptive data in shop drawing form. Provide sample of equipment upon request for review by Architect. Samples will be returned if requested in writing.
2. Alternate equipment must be equal from the standpoint of materials, construction and performance.
3. Alternate submittal must be presented to the Engineer/Architect ten (10) days prior to bid date for approval.

B. The Architect and Engineer shall be the sole judge of quality and equivalence of equipment, materials and methods.

1-8 QUALITY ASSURANCE:

All work shall be performed in accordance with all state, local & federal codes and all authorities having jurisdiction, including but not limited to:

National Electrical Code (NEC)
American Society for Testing and Materials (ASTM)
Underwriter's Laboratories, Inc. (UL)
Insulated Power Cable Engineer's Association (IPCEA)
National Electrical Manufacturer's Association (NEMA).
Institute of Electrical and Electronic's Association (IEEE).
American National Standards Institute (ANSI).
National Fire Protection Association (NFPA).

1-9 SLEEVES, CUTTING AND PATCHING:

This Section shall be responsible for the placing of sleeves for all conduit passing through walls, partitions, beams, floors, roof, etc. Sleeves through below-grade walls shall be as specified and detailed on the plans.

All cutting and patching will be done under another Division, but this Section will be responsible for timely performance of this work and layout of holes and setting sleeves.

1-10 EXCAVATION AND BACKFILL:

Trenching and backfilling and other earthwork operations required to install the facilities specified herein shall conform to the applicable requirements of Division 2 (95% of maximum standard density). Where trenching or excavation is required in improved areas, the backfill shall be compacted to a condition equal to that of adjacent undisturbed earth and the surface of the area restored to the condition existing prior to trenching or excavating operations. The plans indicate information pertaining to surface and sub-surface obstructions; however, this information is not guaranteed. Should obstructions be encountered whether or not shown, the Contractor shall alter routing of new work, reroute existing lines, remove obstructions where permitted, or otherwise perform whatever work is necessary to satisfy the purpose of new work and leave existing surfaces and structures in a satisfactory and serviceable condition.

1-11 CLEANING:

Clean lighting fixtures and equipment.

Touch-up and refinish scratches and marred surfaces on panels, switches, starters, and transformers.

1-12 TESTS AND INSPECTIONS

Tests and inspection requirements shall be coordinated Architect.

Date for final acceptance test shall be sufficiently in advance of completion date of contract to permit alterations or adjustments necessary to achieve proper functioning of equipment prior to contract completion date.

Conduct re-tests as directed by Architect on portions of work or equipment altered or adjusted as determined to be necessary by final acceptance test. No resultant delay or consumption of time as a result of such necessary re-test beyond contract completion date shall relieve Contractor of his responsibility under contract.

Put circuits and equipment into service under normal conditions, collectively and separately, as may be required to determine satisfactory operation. Demonstrate equipment to operate in accordance with requirements of these specifications. Perform tests in the presence of Architect. Furnish instruments and personnel required for tests.

At the time designated by the Architect, the entire system shall be inspected by the Architect and Engineer. The contractor or his representative shall be present at this inspection.

Panelboards, switches, fixtures, etc., shall be cleaned and in operating condition. Certificates and documents required hereinbefore shall be in order and presented to the Architect prior to inspection.

Panel covers, junction box covers, etc., shall be removed for visual inspection of the wire, bus bars, etc.

After the inspection, any items that are noted as needing to be changed or corrected in order to comply with these specifications and the drawings shall be accomplished without delay.

PART 2: PRODUCTS – ELECTRICAL

2-1 ALL PRODUCTS:

All products shall be listed by Underwriter's Laboratories and have the U.L. label affixed.

2-2 RACEWAYS AND FITTINGS:

Except as noted or otherwise specified, all wiring shall be installed in galvanized rigid steel conduit or electrical steel tube (EMT) of the proper size to contain the number of conductors required in accordance with the latest edition of the N.E.C. Where conduit sizes are shown on the drawings, those shall take preference.

Provide EMT in sizes up to 4 inches when concealed or not exposed to damage; Rigid steel, galvanized for underground use, where exposed to damage, or in exterior applications; Rigid galvanized steel where embedded in concrete or masonry construction.

Minimum size shall be 3/4 inch except for fixture whips not exceeding 6'-0" long. Branch circuits run underground shall be run in Carton Schedule 40 PVC conduit. Install ground wire in accordance with NEC table 250-95. Electrical metallic tubing systems shall utilize watertight compression type fittings where exposed to moisture and set screw type fittings elsewhere.

Conduit shall be run concealed in finished areas. Conduit may be exposed in mechanical rooms and where otherwise indicated.

Concealed conduit shall run in as direct manner with as long bends as possible. Exposed conduit shall be run parallel with, or at right angles to the lines of the building; and all bends shall be made with standard conduit elbows or conduit bent to not less than same radius. Not more than equivalent of four quarter bends shall be used in any run between terminals and cabinet, or between outlet or junction boxes. Approved conduits shall be used in lieu of conduit ells where ease of installation and appearance warrants their use. Conduit joints shall be made with approved couplings and unions.

Provide #30 nylon pulling line in all conduits in which permanent wiring is not installed.

Branch circuit conduits installed in concrete slabs on fill or grade shall be positioned in a manner to ensure complete concrete cover. In no case shall such conduits be exposed below or above the slab surfaces, or penetrate the waterproof membrane.

At locations where feeder, or other large conduits, must pass through slabs on fill or grade, the conduit shall be PVC coated rigid galvanized steel, extended 6 inches into the earth, and 2 inches above exposed surface of slab.

All conduit shall be securely fastened and supported using hot galvanized malleable iron one-hole pipe straps, clamps, hangers or other means approved by the engineer. Supports shall be as required by NEC. Tie wire shall not be used as support or securing means. Support conduit independently of ceiling hanger wire.

2-3 OUTLET AND JUNCTION BOXES:

Provide an approved galvanized outlet box with adequate volume for number of conductors concerned.

Provide standard galvanized switch boxes of the required number of gangs. Switch boxes for exposed wiring shall be handy boxes or approved equal.

Outlet boxes for receptacles shall be similar to Universal 52151 with suitable raised cover. Receptacle boxes on exposed wiring shall be handy boxes or approved equal.

Weatherproof boxes where necessary shall be FS or FD.

Outdoor boxes shall be NEMA 3R, with conduit connections made by Myers Hubs.

See notes and details on Drawings for special box requirements.

Provide junction boxes required to facilitate installation of the various conduit systems. Provide support boxes required for risers, each complete with approved cable supports as described elsewhere in this Division.

Outlet boxes for drywall shall be standard galvanized 4" square boxes with the appropriate device cover. Secure all outlet boxes with a backing brace connected to two adjacent studs. Mounting brackets with a single ear to rest against the backing sheet rock are not acceptable.

Provide coverplates for all outlet boxes.

Provide junction boxes and conduit system for all electrical systems and low voltage systems: (i.e. electrical, sound, security, fire alarm, CCTV, cameras, CATV, intercom).

2-4 PULL BOXES:

Pull boxes shall be provided for conduit systems as required and shall be constructed of galvanized steel of not less than gauge and size specified by National Electrical Code.

Where two or more feeders pass through a common pull box, they shall be tagged to indicate clearly their electrical characteristics, circuit number, and panel designation.

2-5 WIRE AND CABLE:

All wire shall be new and continuous without weld, splice, or joints throughout its length. It must be uniform in cross-section, free from flaws, scales and other imperfections.

Wire shall be soft drawn, annealed, 98% pure copper, with tin coating. Aluminum wiring is not acceptable.

Acceptable manufacturers for 600 volt wire and cable shall be Southwire, Encore, and Cerno.

Acceptable manufacturers for 300 volt wire and cable shall be Westpenn, Beldon, Alpha and Tappan.

Acceptable manufacturers for connectors shall be AMP, Burndy, Ideal, 3M, O.Z. Gedney, and Thomas & Betts.

A. TYPES:

1. Provide code gauge type "THHN/THWN-2" insulation.
2. All wiring shall be stranded. Minimum wire shall be No. 12, unless otherwise shown on Drawings.
3. Fire alarm device wiring shall be 300 volt, PVC jacket UL-listed when routed in a raceway. The jacket shall be UL listed for use in air plenums when a raceway is not used.
4. Control wiring shall be No. 14 AWG copper conductor unless otherwise shown; 600 volt rated insulation.
5. Open low voltage wiring in return air plenums shall be plenum rated or run in conduit. All wiring in mechanical rooms electrical rooms and other areas subject to physical damage shall be run in conduit.

B. COLOR CODING: Conductors shall be color coded in accordance with the governing authority requirements or as follows:

120/208V 277/480V 120/240V

NEUTRAL: White Neutral:Gray Neutral:White
PHASE A: Black Phase A:Brown Phase A:Black
PHASE B: Red Phase B:Purple Phase B:Orange
PHASE C: Blue Phase C:Yellow Phase C:Blue
GROUND: Green Ground:Green Ground:Green

C. SPLICES:

Splices, where required, shall be fully made up in outlet boxes with compression crimp-on type splice connectors and at least 12 inches tagged end left for the fixture hanger. Where local requirements specify certain colors for phases and neutral, etc., these shall become the standard for this project.

Joints and splices will not be permitted in mains or feeder. Joints in branch circuits will be permitted where branch circuits divide, and then shall consist of one through-circuit to which the branch shall be spliced. Joints shall not be left for the fixture hanger to make. Fit joints and splices with Buchanan Series "2000" solderless connectors complete with insulating caps or properly sized wire nuts. Wago push-in connectors are not acceptable.

D. Terminations: Provide STA-COM devices to terminate stranded conductors on device not rated to accept stranded conductors. All wiring shall be torqued per manufacturers specifications.

E. METAL CLAD CABLE – TYPE MC

1. At the contractor's option, metal clad cable (MC) may be used if approved by the authority having jurisdiction and building owner. The cable shall contain an insulated green grounding conductor (3 wire) and shall be the same size as the phase conductor. Conductors shall be solid copper.
2. Metal clad cable shall not be used for homeruns. Metal clad cable shall only be used for branch circuit drops from ceiling mounted junction boxes to outlets and for horizontal runs in a common wall from outlet to outlet. Do not route outlet to adjacent walls. Fixture to fixture wiring is acceptable in hard non-accessible ceilings.
3. Metal clad shall be UL approved connectors and shall be used and installed per Article 334 of the National Electrical Code.

2-6 WRING DEVICES:

Provide decora devices except in remodeled areas where existing devices not being replaced are toggle switches and standard receptacles.

Acceptable manufacturer is Hubbell.

A. SWITCHES

Furnish and install generally where indicated on the Drawings. Coordinate final color and exact locations with architect.

Wall switches shall be 20 amp, 120V-277 volt and shall be as follows:

1. SINGLE POLE SWITCHES: DS-120W, White, Decora,(HBL 1221 TOGGLE)
3. THREE WAY SWITCHES: DS-320W, White, Decora,(HBL 1223 TOGGLE)

B. DIMMERS:

Provide Lutron "DIVA" series wall box dimmers sized to handle the load. Gang dimmers without removing heat sink fins and mount under a common Lutron coverplate.

C. RECEPTACLES:

Furnish and install generally where indicated on the Drawings. Coordinate final color and exact location with architect. Provide tamper resistant when required. All devices shall be 20AMP unless otherwise noted.

Receptacles shall be Hubbell as follows:

1. Duplex 20A-125V-self grounding: DR20WH decora (Nema configuration 5-20R) (5362 standard).
2. Ground fault circuit interrupter (GFI) receptacle 20A-125V; GFRST20. (White with indicator light Nema Configuration 5-20R, with "Feed through" connectors capable of protecting connected downstream receptacles on a single circuit, and of being installed in a 2-3/4" deep outlet box without adapter).
3. Equipment receptacles shall be coordinated with owner/manufacturer requirements and the correct and appropriate receptacle and cover plate then installed.

D. PLATES:

1. Furnish and install plates on all outlet boxes.
2. Plates in offices and break rooms and similar finished areas shall be HUBBELL white smooth thermo-plastic.
3. Wet Locations: Provide Taymac or Carlon Nema 3R, impact resistant polycarbonate enclosure. Enclosure shall be suitable for wet locations when in use.

4. Indoor Exposed Raceway Systems: Stamped sheet metal, sized to match box without overlapping sharp edges.

E. Floor boxes shall be cast iron as manufactured by Hubbell and as indicated below: (Note: If floors are wood, provide a Hubbell cast iron floor box and flush cover designed for this application.)

1. Slab at grade (dual level, fully adjustable type I).
- a. Single gang: #B-2436 w/#SB-3083 carpet flange.
- b. Two gang: #B-4233 w/#SB-3084 carpet flange.
- c. Three gang: #B-4333 w/#SB-3085 carpet flange.
2. Slab above grade (shallow, semi-adjustable, type II)
- a. Single gang: #B-2414 w/#SB-3083 carpet flange.
- b. Two gang: #B-4214 w/#SB-3084 carpet flange.
- c. Three gang: #B-4314 w/#SB-3085 carpet flange.
3. Cover plates shall have brass finish as follows:
- a. #S-3825 for duplex flap for duplex receptacles.
- b. #S-2425 for data/communications.
- c. Provide appropriate coverplate for special purpose receptacles.

F. Fire rated poke-thrus shall be manufactured by Hubbell. Poke-thrus shall be Hubbell SystemOne unless noted otherwise. Provide sub-plate and cover as required. Confirm floor finish with architect prior to ordering cover.

Unless noted to the contrary on plans, or directed otherwise during the progress of the Work, wiring devices shall be set as follows:

1. Switches 42 inches above finished floor.
2. Duplex and single receptacles 18 inches above finish floor to the center of the device except where located above counters or interferes with shelving or as required by local codes.
3. Wall telephone outlets, except where counters or shelving interferes 18 inches above finished floor to the center of the outlet box.
4. At locations above counters, set devices 1 foot-0 inches above counter tops, verify exact mounting height with the architect.

2-7 GROUNDING AND BONDING:

Provide electrical service, equipment and wiring device grounding as shown, scheduled and as specified.

The types of grounding include, but are not limited to, the grounding bonding of all equipment devices, building steel piping, and as required by the National Electrical Code, Local Inspection Department and Power Company. A grounding conductor is required for all feeders and circuits.

Provide grounding products manufactured by Copperweld and Cadwell.

Ground rods shall be 3/4" inch diameter by 10 feet long construction with copper jacket and a steel core. Ground clamps shall be copper except for steel or iron pipes in which the clamps shall be galvanized iron. Conductors shall be connected by means of an approved pressure connector or clamp.

Perform a ground resistance test using a biddle megger. The system resistance shall not exceed 5 OHMS. Provide additional electrodes as required (refer to 250-84 of the NEC). Test shall not be conducted following wet weather. Provide personnel and instruments to conduct these tests and submit certified test for review.

A. BUILDING STEEL AND PIPING SYSTEM: Install a bonding jumper between building steel and metallic piping systems to bond them to the electrical grounding system.

B. NEUTRAL: The neutral shall be grounded only at the service entrance and other separately derived systems. The neutral shall be kept separate from the grounding system and shall not be used as a ground.

C. GROUNDING CONDUCTOR: A grounding conductor and metallic conduit system shall bond all equipment served by the electrical system. Provide a flexible bonding jumper for isolated metallic piping and ductwork and ground expansion fittings and joints.

D. MOTORS: The frame of all motors shall grounded.

E. SPECIAL GROUNDING: Provide a #6 AWG copper grounding conductor for each telephone board, television system, MDF rooms, IDF rooms, etc. Terminate the grounding conductor on ground bus and to the building electrical grounding system. Refer to article 800 and 820 of the NEC.

F. LIGHTING FIXTURES: Provide grounding conductor in all flexible whips, whips shall not exceed 6 feet.

G. RECEPTACLES: All receptacle shall be grounded. Receptacles shall use an approved grounding yoke.

H. REMOTE PANELBOARDS: Provide a grounding electrode conductor at all remote panels as required by the NEC.

2-10 PANELBOARDS:

Furnish and install power distribution, lighting and appliance panelboards as indicated in the panelboard schedule and as shown on the plans. Power distribution panelboards shall be equipped with fusible switches or circuit breakers as shown on the schedule. Panelboards shall be equipped with thermal-magnetic, molded case circuit breakers of frame and trip ratings as shown on the schedule. Acceptable manufacturers are General Electric Company or Square D Company. Load centers are not acceptable.

Panelboard bus structure and main lugs or main breaker shall have current ratings as shown on the panelboard schedule. Such ratings shall be established by heat rise tests with maximum hot spot temperature on any connector or bus bar not to exceed 50°C rise above 40°C ambient. Heat rise test shall be conducted in accordance with Underwriters Laboratories Standard UL 67. The use of conductor dimensions will not be accepted in lieu of actual heat tests. All current carrying parts of the bus shall be tin plated copper.

Bus structure shall be insulated. Bus bar connections to the branch circuit breakers shall be distributed phase or phase sequence type and shall accept bolt-on circuit breakers for lighting and appliance panelboards.

Provide a bare uninsulated and/or insulated ground bus and full or double size neutral bus as required and indicated in each panelboard schedule.

Each panelboard shall have an engraved bakelite nameplate. Nameplates shall be white with black letters and show panel designation. Nameplates shall be attached with stainless steel screws.

Place a neat, carefully typewritten directory card identifying the load served by each branch circuit in the frame on the panel door, under a clear plastic cover. Spares and spaces shall be written with erasable pencil for future use.

Where circuit breakers or fuses are applied in compliance with the series combination ratings marked on the equipment by the manufacturers, the equipment enclosure(s) shall be legibly marked in the field to indicate the equipment has been applied with a series combination rating. The marking shall be readily visible and state "caution – Series Rated System." (NEC 110-22). Nameplate shall identify replacement components.

A. Circuit Breakers

Where circuit breakers or fuses are applied in compliance with the series combination ratings marked on the equipment by the manufacturers, the equipment enclosure(s) shall be legibly marked in the field to indicate the equipment has been applied with a series combination rating. The marking shall be readily visible and state "caution – Series Rated System." (NEC 110-22).



TEXAS ARCHITECT
FIRM No: BR4247
WWW.CGSARCHITECT.COM

SEAL:

ECISD HIGH SCHOOL ATHLETIC MULTI-USE BUILDING 25-74

EDINBURG HIGH SCHOOL

2600 E
Wisconsin Rd,
Edinburg, TX
78542

CLIENT:


EDINBURG CISD

REVISION:

No.	Description	Date

PROJECT #: 25-030102
DRAWN BY: N.M.
CHECKED BY: CG3
DATE: 4/28/25

ELECTRICAL SPECIFICATIONS



ISSUED FOR PERMIT

VME
ENGINEERING

1615 Laurel Ct Donna, Texas 78537
P: 956.472.5161 www.vme-engineering.com
Texas Registered Engineering Firm - F14031
Project number: 025.25

E5.1

- Distribution Panelboards:
Circuit breakers shall be equipped with individually insulated, braced and protected connectors. The front faces of all circuit breakers shall be flush with each other. Large, permanent, individual circuit numbers shall be affixed to each breaker in a uniform position. Tripped indication shall be clearly shown by the breaker handle taking a position between "ON and "OFF". Provisions for additional breakers shall be such that no additional connectors will be required to add breakers. Circuit breakers shall be of the frame size, trip setting and interrupting capacity as indicated on the drawings.

Current limiting circuit breakers shall be equal to Square D Company "I-Limiter" Series.

Circuit breakers shall be conventional interrupting capacity but in no case be less than the following symmetrical amperes RMS.

FRAME SIZE/ VOLTAGE	CONVENTIONAL CAPACITY	HIGH INTERRUPTING CAPACITY	CURRENT LIMITING
100AF/240V	10,000 AIC	65,000 AIC	200,000 AIC
225AF/240V	10,000 AIC	65,000 AIC	200,000 AIC
400AF/240V	42,000 AIC	65,000 AIC	200,000 AIC
600AF/240V	42,000 AIC	65,000 AIC	200,000 AIC
800AF/240V	42,000 AIC	65,000 AIC	200,000 AIC
1000AF/240V	42,000 AIC	65,000 AIC	200,000 AIC
1200AF/240V	42,000 AIC	65,000 AIC	200,000 AIC
100AF/480V	14,000 AIC	25,000 AIC	200,000 AIC
225AF/480V	22,000 AIC	65,000 AIC	200,000 AIC
400AF/480V	30,000 AIC	65,000 AIC	200,000 AIC
600AF/480V	30,000 AIC	65,000 AIC	200,000 AIC
800AF/480V	30,000 AIC	65,000 AIC	200,000 AIC
1000AF/480V	30,000 AIC	65,000 AIC	200,000 AIC
1200AF/480V	50,000 AIC	65,000 AIC	200,000 AIC

- 480/277 Volt Lighting Panelboards:

All main circuit breakers shall be vertically mounted and shall not be installed in branch breaker spaces. Circuit breakers shall be ball-on thermal-magnetic, molded case circuit breakers. Breakers shall be 1, 2 or 3 pole with an integral crossbar to assure simultaneous opening of all poles in multiple circuit breakers. Breakers shall have an over-center, tri-free, toggle-type operating mechanism with quick-make, quick-break action and positive handle indication. Handles shall have "ON", "OFF" and "TRIPPED" positions. Circuit breakers shall be UL listed in accordance with UL Standard 489 and shall be rated 277 volts ac (single pole, 15-30 amperes) or 480Y/277 volts ac (2 and 3 pole) with continuous current ratings as noted on the plans. Interrupting ratings shall be 14,000 rms symmetrical amperes at 277 volts ac (single pole) or 480Y/277 volts ac (2 and 3 pole). Single pole, 15 and 20 ampere circuit breakers intended to switch fluorescent lighting loads on a regular basis shall carry the SWD marking. The lugs for terminating conductors shall be rated at 75°C.

- 240 Volt Lighting and Appliance Panelboard:

All main circuit breakers shall be vertically mounted and shall not be installed in branch breaker spaces. Circuit breakers shall be ball-on thermal-magnetic, molded case circuit breakers. Breakers shall be 1, 2, or 3 pole with an integral crossbar to assure simultaneous opening of all poles in multiple circuit breakers. Breakers shall have an over-center, tri-free, toggle-type operating mechanism with quick-make, quick-break action and positive handle indication. Handles shall have "ON", "OFF" and "TRIPPED" positions.

Circuit breakers shall be UL listed in accordance with UL standard 489 and shall be rated 240 volts ac maximum with continuous current rating as noted on the plans. The lugs for terminating conductors shall be rated at 75°C.

Single pole 15 and 20 ampere circuit breakers shall be UL listed as "Switching Breakers" at 120V ac and carry the SWD marking.

UL Class A ground fault circuit protection shall be provided on all receptacle circuits serving wet areas and on all 120V ac branch circuits as specified on the plans or panelboard schedule. This protection shall be an integral part of the branch circuit breaker, which also provides overload, and short circuit protection for branch circuit wiring. Tripping of a branch circuit breaker containing ground fault circuit interruption shall not disturb the feeder circuit to the panelboard. A single pole circuit breaker with integral ground fault circuit interruption shall require no more panelboard branch circuit space than a conventional circuit breaker. Circuit breakers shall be rated 10,000 AIC at 240V unless otherwise noted on plans.

- Fusible Switches

All fusible switches shall be quick-make, quick-break with visible blades and dual horsepower ratings. Switch handles shall physically indicate "ON" and "OFF" positions. Switches shall be lockable only in the "OFF" position and accept three industrial type heavy duty padlocks. Switch covers and handles shall be interlocked to prevent opening in the "ON" position. A means shall be provided to permit authorized personnel to release the interlock for inspection purposes. Switches shall include positive pressure rejection type fuse clips for use with UL class R fuses and be UL labeled for 200,000 AIC. Class "J" fuses shall be UL labeled for 200,000 AIC. The lugs for terminating conductors shall be rated at 75°C.

- Cabinets and Fronts

The panelboard bus assembly shall be enclosed in a steel cabinet with multiple knockouts. The rigidity and gauge of steel to be as specified in UL Standard 50 for cabinets. Wiring gutter space shall be in accordance with UL Standard 67 for panelboards. The box shall be fabricated from galvanized steel or equivalent rust resistant steel. Provide stainless steel front cover for all panels located in all Pool Equipment rooms, Food Labs, Snack Bars, Culinary Arts, Kitchens and Life Skills rooms.All NEMA-1 lighting and receptacle panels shall have hinged front covers. The front cover shall have a door with hinges, latch and a lock. The hinged front covers shall allow full access to the circuit breaker gutter area without having to remove the entire front cover. All panelboard lock shall be keyed alike. Fronts shall have adjustable indicating trim clips, which shall be completely concealed when the doors are closed. Doors shall be mounted with completely concealed steel hinges. A circuit directory frame and card with a clear plastic covering shall be provided on the inside of the door. Where required by local code, provide Nema 3R enclosure where installed in a sprinkled area.

- Safety Barrier

The distribution panelboard interior assembly shall be dead front with panelboard front removed. Main lugs or main breakers shall have barriers on five sides. The barrier in front of the main lugs shall be hinged to a fixed part of the interior. The end of the bus structure opposite the mains shall have barriers.

- Integrated Equipment Short Circuit Rating

Each panelboard, as a complete unit, shall have a short circuit current rating equal to or greater than the integrated equipment rating shown on the panelboard schedule or on the plans. This rating shall be established by testing with the over-current devices mounted in the panelboard. The short circuit tests on the over-current devices and on the panelboard structure shall be made simultaneously by connecting the fault to each over-current device with the panelboard connected to its rated voltage source. Method of testing shall be per Underwriters Laboratories Standard UL 67. The source shall be capable of supplying the specified panelboard short circuit current or greater. Testing of panelboard over-current devices for short circuit rating only while individually mounted is not acceptable. Also, testing of the bus structure alone is not acceptable. Panelboards shall be marked with their maximum short circuit current rating at the supply voltage and shall be UL listed.

- MANUAL MOTOR STARTERS:

Manual starters shall consist of a manually operated toggle switch equipped with melting alloy type thermal overload relay. Thermal unit shall be of one-piece construction and interchangeable. Starter shall be inoperative if thermal unit is removed. Contacts shall be double break, silver alloy, visible from both sides of starter. Manual starters shall be Square "D" class 2510 or 2512 or approved equal. Provide the size and number of poles shall be as shown and required by equipment served. Furnish red pilot light as indicated.

All manual motor starter enclosures shall be NEMA 1, general purpose enclosures, unless shown otherwise. Provide Nema 3R enclosure where installed outside or in a sprinklered area when required by local code.

MOTOR CONNECTIONS: Provide electrical and grounding connections to motors as indicated. Connections as follows:

- Not less than 18 inch length of Sealite, extending from motor connection box to motor branch circuit conduit on outdoor and wet locations. Provide Greenfield for inside dry locations.
- Install connections mechanically secure, assuring electrical continuity, proper and effective grounding.

INSTALLATION OF MOTOR STARTER

Install motor starters in accordance with the manufacture's written instructions, the applicable requirements of the NEC and the NECA's "Standard of Installation", and recognized industry practices to ensure that products serve the intended function.

- CURRENT - LIMITING FUSES:

Provide 200,000 amp interrupting capacity current limiting fuses of the ampacity and voltage indicated and scheduled.

Upon completion of the building the contractor shall provide the owner with spare fuses as shown below.

A. 10% (minimum of 3) of each type and rating of installed fuses shall be supplied as spares.

B. BUSSMAN spare fuse cabinets - Catalog No. SFC - shall be provided to store the above spares.

Mains, Feeders and Branch Circuits

- Circuits 0 to 600 ampere shall be protected by current limiting BUSSMAN LOW-PEAK Dual Element Fuses LPN-RK (250 volts) or LPS-RK (600 volts). All dual-element fuses shall have separate overload and short-circuit elements. Fuse shall incorporate a spring activated thermal overload element having a 284 degree Fahrenheit melting point alloy and shall be independent of the short-circuited clearing chamber. The fuse must hold 500% of rated current for a minimum of 10 seconds and listed by Underwriters Laboratories Inc., with an interrupting rating of 200,000 amperes r.m.s. symmetrical. The fuses shall be UL Class RK1.

- Motor Circuits - All individual motor circuits rated 600 amperes or less shall be protected by BUSSMAN LOW-PEAK Dual Element Fuses LPN-RK (250 volts) or LPS-RK (600 volts). The fuses for 1.15 service factor motors shall be installed in ratings approximately 125% of motor full current except where high ambient temperatures prevail, or where the motor drives a heavy revolving part which cannot be brought up to full speed quickly, such as large fans. Under such conditions the fuse should be 150% to 200% of the motor full load current. Larger H.P. Motor shall be protected by BUSSMAN Type KRP-C H-CAP Time-Delay Fuses of the rating shown on the drawings. 1.0 service factor motors shall be protected by BUSSMAN LOW-PEAK Dual-Element Fuses LPN-RK (250 volts) or LPS-RK (600 volts) installed in ratings approximately 115% of the motor full load current except as noted above. The fuses shall be UL Class RK1 or L.

- SAFETY AND DISCONNECT SWITCH:

A. Products shall be designed, manufactured, tested and installed in compliance with applicable standards.

- NEMA KSI - Enclosed switches
- Federal specification W-S-885C-Heavy duty switches

Products shall conform all applicable UL standards, including UL98 (standard for safety, enclosed and dead front switches) and shall be UL-labeled.

Acceptable manufacturers are:

General Electric Company, Square D Company, or Eaton.

Furnish and install heavy-duty type safety switches with the number of switched poles as indicated on the plans and specifications. All safety switches shall be NEMA Heavy Duty Type HD, and Underwriters Laboratories listed.

- Switch Interior

All switches shall have switchblades, which are fully visible in the "OFF" position when the door is open. Switches shall have removable arc suppressor where necessary, to permit easy access to line side lugs. Lugs shall be front removable and UL listed for 60°C and 75°C copper aluminum cables. All switches blades and contacts shall be plated copper.

- Switch Mechanism

Switches shall have a quick-make and quick-break operating handle and mechanism, which shall be an integral part of the box, not the cover. Padlocking provisions shall be provided for locking in the "OFF" position with at least three padlocks. Switches shall have a dual cover interlock to prevent unauthorized opening of the switch door when the handle is in the "ON" position, and to prevent closing of the switch mechanism with the door open. A means shall be provided to permit authorized personnel to release the interlock for inspection purposes. Handle position shall indicate if switch is "ON" or "OFF".

- Neutral

A single neutral with the safety switch where a neutral is present in the circuit.

- Ratings

Switches shall be horsepower rated for ac and/or dc as indicated by the plans. The fused switches shall have Class R rejection fuse clips when required. Adjust load side terminal block as required to accept Class J fuses. UL listed short circuit ratings of the switches, when equipped with Class R or Class J fuses, shall be 200,000 symmetrical amperes.

- LIGHTING FIXTURES:

All fixtures shall conform to all applicable UL standards and shall be UL label including damp and wet location ratings. "ETL" is an acceptable listing.

All fluorescent ballasts shall comply with certified ballast manufacture (CBM) standard and CBM labeled.

Acceptable manufacturers for ballasts are Advance Transformer Company or Magnetek Universal Manufacturing.

Acceptable manufacturers for lamps are Osram-Sylvania or Philips.

Provide the size, type and rating of each light fixture shown and scheduled. All light fixtures shall be complete with reflectors, lens, trim rings, flanges, lamps, lamp holders, ballast, starters, fuses wiring, earthquake clips, etc. to provide a complete functioning light fixture.

STANDARDS

- All fixtures shall conform to all applicable UL standards and shall be UL label including damp and wet location ratings. "ETL" listed is an acceptable listing.
- All fluorescent ballast shall comply with certified ballast manufacture (CBM) standard and CBM labeled.
- NFPA 101
- ANSI C82.1
- NEMA-LE
- IEEE Publication 587 Category "A" (Electronic Ballast)
- All LED drivers shall be UL recognized Class 2 per UL1310 or non-class 2 per UI 1012 as applicable.
- All LED drivers shall comply with applicable requirements of the Federal Communications Commission (FCC) rules and regulations, Title 47 CFR part 15, for Non-Consumer Equipment.
- All LED drivers shall be RoHS compliant.
- TM-21
- LM-80
- LM-79
- M. L70
- N. DLC

- Lighting Fixture Types:

- Fluorescent and LED Fixtures
 - Fluore fixture ballast, lamp holders and drivers shall be pre-wired and installed. Fixture shall be equipped with a top access plate with knockouts for conduit entry. Fixture shall also include knockouts at each end plate for conduit entry.
 - Provide battery packs for emergency operation when specified.
- Incanescent Fixtures
 - Fixtures shall be pre-wired equipped with frame in kit and an integral thermal protection required by UL for recessed fixtures.
 - Provide appropriate trim rings for recessed mounted fixtures compatible with the ceiling in which the fixture is installed.
 - All lamps shall inside frosted unless otherwise noted or scheduled.
- High Intensity Discharge Fixtures (HID)
 - Fixtures shall be pre-wired with frame-in kit and integral thermal protection required by UL for recessed fixtures. Ballast shall be encased and potted and mounted on the frame-in kit.
 - Provide remote ballast mounted on a separate mounting plate where indicated or scheduled. Ballast shall include a splice box.
 - Provide a heat resistant glass shield below the lamp to contain lamp glass envelope and ARC tube to prevent them from falling to the floor and causing damage to life and property. Lamps rated for open bottom fixtures may be used in lieu of the glass shield if approved by the engineer.
 - Provide a fuse and fuse holder installed on the line side of each ballast to prevent branch circuit from tripping due to a faulty ballast. The fuse and fuse holder shall be mounted in a junction box for recessed fixtures and in the base of all poles. The fuse holder shall be waterproof when installed in damp or wet locations. Fuse size and type shall be as recommended by ballast manufacturer.
- LED Fixtures
 - Fixtures shall be pre-wired with frame-in kit and integral thermal protection required by UL for recessed fixtures. Driver shall be encased in metal-can construction for optimal thermal performance.
 - Total fixture lumen output is dependent on the chip, thermal management, driver current and optical system. LED fixtures shall be tested as a complete unit or system. Only DOE recognized CALIPER testing laboratory results shall be utilized.
 - LED fixtures shall have integral common mode and differential mode surge protection of 3kV (1.2/50s, 20hm combination wave).
 - Exit signs
 - Exit signs shall meet all federal, state and local codes.
 - Provide battery backup when not connected to a life safety generator.
 - Provide Bodine battery pack to provide 1 foot candle overages in the path of egress. These are not required when a life safety generator is used for emergency lighting.

- Ballasts - Coordinate with Light Fixture Schedule

- Fluorescent
 - Provide program parallel start electronic ballast. Ballasts shall be high power factor 98% minimum), operate lamp at 40 KHz, less than 10% total harmonic content, normal ballast factor 50,000 switching cycles, universal voltage, crest factor less than 1.7, multi-lamp, class "P" thermally protected, sound "A" rating, encased and potted and OT minimum starting temperature. Provide 5 year warranty parts and labor. Ballast shall be Advance Optanium/Centium/Smartnote or equal by Sylvania.
- LED Drivers
 - Driver manufacturer shall have a 10-year history producing electronic drivers for the North American market.
 - Driver shall carry a five year limited warranty from date of manufacture against defects in material or workmanship (including replacement) for operation at a maximum case temperature of 80 degrees Celsius.
 - Drivers shall not contain any Polychlorinated Biphenyl (PCB).
 - Provide driver with integral color-coded leads.
 - Driver shall operate from 50/60 Hz input source of 120 Volt through 277 Volt or 347 Volt though 480 Volt with sustained Variation of +/- 10% (voltage) with no damage to the driver.
 - Driver output shall be regulated to +/- 5% across published load range. And shall have a power factor greater than .90 from primary application to 50% of full loadrating with an input current Total Harmonic Distortion (THD) of less than 20% to 50% of full load rating.
 - Provide drivers with a Class A sound rating.
 - Provide LED drivers for outdoor fixtures with a minimum operating temperature of -40 degrees Celsius (-40°F). Provide LED drivers for indoor fixtures with a minimum operating temperature of -20 degrees Celsius (-2°F).
 - Drivers shall tolerate sustained open circuit and short circuit output conditions without fail and auto-resetting without need for external fuses or trip devices.
 - Driver output ripple current shall be less than 15% measured peak-to-average, with ripple frequency being greater than 100Hz.
 - Driver performance requirements shall be met when operated to 50% of full load rating.
 - Driver shall have integral thermal feedback to reduce driver power above rated case temperature to protect the driver if temperature reach unacceptable levels.
 - Drivers shall comply with NEMA 410 for in-rush current limits.
 - Dimmable drivers shall be controlled by a class 2 low voltage 0-10VDC controller with dimming range controlled between 1 and 8VDC with source current 150A.

- Lamps - Coordinate with Light Fixture Schedule

- F032T8 fluorescent lamps shall be 40,000 hours 3,500K, 82 CRI or better, 32 watt and low mercury. Life rating is based on 3 hours/start using programmed start ballast.
- All compact fluorescent lamps shall be 4 pin, 12,000 hours 3,500K, 82 CRI or better.
- All incandescent lamps shall be inside frosted, extended life rated for 2500 hours unless otherwise noted. 130 volt lamps may be used to provide extended life.

- Coordination

- The contractor shall verify the type of fixtures with the ceiling types as indicated on the drawings. Any discrepancies shall immediately be brought to the architect's attention before the contractor places his order and accepts delivery. Fixtures shall fit exact in the type of ceiling scheduled. Provide plaster frames, trim rings and other accessories required for a correct fit.
- Provide supports attached to structural member to support fixtures when the ceiling system cannot maintain support. Provide separate supports for all recessed ceiling mounted HID fixtures.
- Refer to architectural reflected ceiling plan for the exact location of all light fixtures. Notify the architect for any discrepancies or conflicts with structural architectural, mechanical piping or ductwork before installation.

- Mounting

- Pendant or surface mounted fixture shall be provided with required mounting devices and accessories including hickey and stud--extensions, ball--aligners, canopies and stems. Locations of fixtures in mechanical areas shall be coordinated with mechanical contractor. Mounting stems of pendant fixtures shall be of the correct length to uniformly maintain the fixture heights shown on the drawings or established in the field. The allowable variation tolerance in mounting individual fixtures shall not exceed 1/4 inch and shall not vary more than 1/2 inch from the floor mounting height shown on the drawings. Fixtures hung in continuous runs shall be installed absolutely level and in line with each other. Hanging devices shall comply with Code requirements. Fixtures shall employ single - not twin - stem hangers unless otherwise noted.
- All structure mounted fixtures (i.e. bracket mounted, pipe mounted and surface mounted) shall be provided with cables of suitable size and weight to support the weight of the fixture. Cables shall be fastened around or fastened to the housing of the fixture. On pendant fixtures, one safety cable of suitable size and weight to support the weight of the fixture assembly shall connect the top of the pendant to the supporting structure by means of welding or bolting, and one safety cable shall connect the housing of the fixture to the bottom of the pendant. Where more than one pendant per fixture occurs, only one pendant must be cabled. Track fixtures for pendant mounted track shall also be supplied with clip-on safety cables of suitable size and weight to support the weight of the fixture.

- Electrical Connection

- All light fixtures installed in an accessible suspended ceiling shall be connected from a branch circuit junction box using 1/2" flexible metal conduit fixture pigtail not exceeding 6'- 0". All fixtures must be grounded by using a grounding conductor or the conduit system. Fixture to fixture wiring of fixtures installed in an accessible ceiling is not permitted.

- Fire Rated Ceiling

1. Provide fire rated canopy or enclosure for all fixtures recessed in a fire rated ceiling. The fire rated canopy or enclosure shall be as required by the UL design number listed in the UL fire resistance directory. Refer to architectural drawing for the UL design number. Coordinate with ceiling installer and manufacturer.

- Air Handling Fixtures

1. Install all air handling light fixtures with return air slot in the open position, if it is to be as an air handling fixture. Coordinate with mechanical contractor.

- Final Inspection:

- Remove all plastic and protective coating from all fixtures. Fixtures shall be thoroughly cleaned. Replace any damaged fixture or fixture parts including reflectors, louvers, lens and metal parts that show signs of corrosion.
- All final incandescent lamps used during construction shall be replaced with new lamps. Replace all other defective ballast, lamps or discolored lamps, showing signs of excessive usage.
- Demonstrate proper operation of all fixtures and controls.

- TELEPHONE RACEWAY SYSTEM

A. Provide pullboxes in telephone conduit runs spaced not greater than 100 ft. apart, and on backboard side of runs with more than two right angle bends. Place telephone label on pull and junction boxes. Provide pullwire in each telephone run. Provide plywood backboards and duplex receptacle in the telephone equipment room. Confirm location on jobsite prior to installation. All terminal cabinets/backboards and conduit shall be sized per the recommendations of the telephone system installer.

B. Provide telephone service conduit. Field coordinate exact requirements and include in bid.

- MISCELLANEOUS ELECTRICAL CONTROLS AND WRING

A. The types of miscellaneous control devices and wiring include but not limited to the following.

- Contactors
- Relays
- Photoells
- Time switches
- Additional control wiring and safety devices as shown and specified.

Various control devices, of an electrical nature, for the safe operation and temperature control of the heating, ventilating, air conditioning and plumbing systems are provided under Division 23.

All control wiring and conduit shall be furnished under Division 23 00 00. All power wiring 120 volt or larger shall be provided by Division 26 00 00.

B. CONTACTORS AND RELAYS: Provide contactors and relays with the number of poles, ampere-rating, control wiring as required, is shown and specified for a complete function system. Acceptable manufacturers are General Electric Company, Square D Company, and Automatic Switch Company. Provide 2-wire or 3-wire control modules as required to operate lighting contactors. Contactors shall be mechanically held. Contactor shall contain H-0-A control.

C. Photocells provide a specification grade self-contained, weatherproof, photoelectric control that shall be mounted on an FS type weatherproof junction box. The photocell shall:

- Switch "ON" at dusk and "OFF" at dawn.
- Adjustable from 2 to 50 foot condies.
- Rated at 2000 watts.
- Use 1" diameter cadmium sulfide cell.
- Have a 2 minute delay to prevent false switching.

Acceptable manufacturers are Tork, Inc., Intermatic time Controls, and AMF Paragon

Install photocells on the roof unless otherwise directed by Architect. Coordinate any roof penetrations with all other trades and shield from other light sources.

D. TIME SWITCHES: Provide electronic, 365 day time clock with power fail memory feature installed in a NEMA 1 enclosure. Acceptable manufacturers is Intermatic time Controls.

E. Control wiring shall be not less than #14 AWG type TW, and shall be color coded and labeled with Brody markers throughout. Bundle multiple conductors with Ty-Raps.